

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

No.PW-MDI(P)E-Tender-NIT/2026-27- **13031-37** Dated: **16/10/24**

To

The Chief Engineer (MZ),
HPPWD, Mandi.

Subject: - Publishing of tender notice.

Dear Sir,

Enclosed please find herewith the Tender Notice of works as given in the Notice Inviting Tender for uploading on department website as per notification Principal Secretary (PW) to the Govt. of H.P. letter No. PBW(B) A(3)1/2024 dated Shimla-2 the 03.01.2024 and No. PBW (B) A (3) 8/2025- 300858 dated 13th Nov., 2025 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender.

Executive Engineer,
Mandi Division No.I,
HP PWD at Padhar

Copy alongwith copy of Tender Notice is forwarded to the following for information and necessary action:-

1. The Superintending Engineer, JNR Circle, HPPWD, Joginder Nagar.
2. All the Assistant Engineers, Working under this Division.
3. The Drawing Branch of this office.
4. Notice Board.

Executive Engineer,
Mandi Division No.I,
HP PWD. at Padhar

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Sealed percentage rate tender on form No. 6&8 are hereby invited by the Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar on behalf of the Governor of Himachal Pradesh for the below noted works from eligible Contractors/firms registered in H.P.P.W.D. in appropriate class as per revised enlistment rules, so as to reach in this office on or before 24.10.2026 up to 12:00 Noon and the same shall be opened on the same day at 12:30 P.M. in the presence of the Contractors or their authorized representatives who may be present. The tender form can be held from this office against cash payment (Non Refundable) on 23.10.2026 upto 12:00 Noon Contractors in person or their authorized representatives. The application will not be accepted without Earnest Money & Cost of tender form.

The tender shall accompany with Earnest Money which should be in the shape of NSC/Time Deposit/Saving Bank account in the Post Office/bank in H.P. duly pledged in the favour of undersigned.

Conditional tenders, telegraphic and tender without earnest money will not be entertained. The Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar reserves the right to accept or reject the tenders. The tender shall remain valid for 75 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/ Gazetted Holiday the same shall be process on next date.


Sr. No.	Name of work.	Estimated Cost (in Rs.)	Earnest Money (in Rs.)	Cost of Tender Form (in Rs.)	Time
1	Restoration of rain damages on Jhanad Balh Khajwhal road Km 0/00 to 11/540 (PDNA-2023) (SH:- Construction of 900mm dia Hume pipe culvert at RD 6/255 alongwith wing walls)	2,91,517.93	5,800/-	350/-	One month
2	Restoration of rain damages on Jhanad Balh Khajwhal road Km 0/00 to 11/540 (PDNA-2023) (SH:- Construction of 900mm dia Hume pipe culvert at RD 4/165 alongwith wing walls)	2,91,517.93	5,800/-	350/-	One month
3	Restoration of rain damages on Jhanad Balh Khajwhal road Km 0/00 to 11/540 (PDNA-2023) (SH:- Construction of 900mm dia Hume pipe culvert at RD 0/065 alongwith wing walls)	2,91,517.93	5,800/-	350/-	One month
4	Restoration of rain damages on Drang Basahi road Km 0/0 to 22/00 (PDNA-2023) (SH:- Construction of wire created Breast wall at RD 3/335 to 3/345)	1,65,902.00	3,300/-	350/-	One month
5	Restoration of rain damages on Drang Basahi road Km 0/0 to 22/00 (PDNA-2023) (SH:- Construction of Composite Masonry Retaining wall at RD 7/010 to 7/022)	3,44,805.00	6,900/-	350/-	One month
6	Restoration of rain damages on Kufri Kheel Nihon Damela road Km 0/00 to 8/100. (PDNA-2023) (SH:- Construction of Composite masonry Breast wall at RD 5/510 to 5/530)	2,91,890.56	5,800/-	350/-	One month
7	Restoration of rain damages on Padhar Balh road Km 0/00 to 18/500 (SH:- Construction of Retaining wall at RD 6/320 to 6/328.65)	4,99,375.62	8,900/-	350/-	One month
8	Construction of Science Lab at GDC Narla (SH:- Making plinth protection, Construction course rubble hammer dressed "U" shape open surface drain)	1,27,443.08	2,500/-	350/-	One month

9	Restoration of rain damages on various road under Tikken Section Sub-Division HPPWD Jhatingri. (SH:- Hiring of Tipper for carriage of Mucks/ debris/ stone Boulder etc.)	97,350.00	1,950/-	350/-	One month
10	Restoration of rain damages on various road under Sudhar Section Sub-Division HPPWD Jhatingri. (SH:- Hiring of Tipper for carriage of Mucks/ debris/ stone Boulder etc.)	97,350.00	1,950/-	350/-	One month

1. Certified that tender of above works are being called of emergent nature in exigency of public interest.

TERMS AND CONDITIONS:-

1. The Contractor/ Firm should be enlisted with the HP.PWD & Registration/ Renewal copy attached.
2. The Contractor/Firm shall have his GST. No. & copy of the same be attached with the application.
3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
4. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender forms. In this regard, contractor has to submit an affidavit/ undertaking that he is not having more two works.
5. Only two tenders form will be issued to the contractor/firms which may be noted.
6. The intending Contractors are requested to see the site of the work before submitting the tender.
7. The offer of the tender shall remain valid upto 75 days after the opening of tender.
8. The tender shall be awarded to the lowest bidder if his tendered amount is within limit of (+) 5% of the amount put to tender, otherwise the tender will be cancelled and recalled.
9. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.


 Executive Engineer,
 Mandi Division No. I,
 HPPWD, at Padhar Distt. Mandi (H.P.)
 on behalf of Governor of Himachal Pradesh

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 291517.93
 Earnest Money Rs:- 5800.00
 Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP, PWD, at Padhar.

Name of work :- Restoration of rain damages on Jhanad Balh Khajwhal road km. 0/00 to 11/540. (PDNA -2023). (Sub Head :- Construction of 900 mm dia Hume Pipe Culvert at RD. 6/255 alongwith wing walls).

Contract No. :

Bidder Name :

SCHEDULE OF WORKS

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	47.25	Per cubic metre	522.50	24688.13	Rupees Twenty Thousand Six Hundred Eighty Eight and Paise Thirteen Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802.803,1202 & 1203. Plain cement concrete nominal mix 1:6:12 (One cement : Six sand : Twelve graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	1.21	Per cubic metre	4705.80	5694.02	Rupees Five Thousand Six Hundred Ninety Four and Paise Two Only
3	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802.803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	31.97	Per cubic metre	5183.80	165726.09	Rupees One Lakh Sixty Five Thousand Seven Hundred Twenty Six and Paise Nine Only
4	Providing concrete for plain/reinforced concrete Grade-M-10 nominal mix 1:3:6 (one cement : three sand : twelve graded,crushed stone aggregate 20mm (twenty millimetre) nominal size) in open foundations complete as per drawings and technical specifications clause 802. 803, 1202 & 1203 curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	9.73	Per cubic metre	5374.60	52294.86	Rupees Fifty Two Thousand Two Hundred Ninety Four and Paise Eighty Six Only
5	Providing and laying reinforced cement concrete 900mm (Nine hundred millimetre) diameter pipe NP2 as per design for culverts on first class bedding of granular material in single row including fixing collar with cement mortar. 1:2 (one cement: two sand) but excluding excavations, protection works, back filling, concrete and masonry works in head walls and parapets as per drawings and technical specifications for Rural roads clause 1101 including carriage of material within all leads, lifts and other incidentals complete in all respect as per direction of Engineer-in-Charge.	7.50	Per running metre	4204.70	31535.25	Rupees Thirty One Thousand Five Hundred Thirty Five and Paise Twenty Five Only

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
6	Providing weep hole in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm dia. (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical into twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	12.00	Each	282.00	3384.00	Rupees Three Thousand Three Hundred Eighty Four Only
7	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	5.42	Per cubic metre	1512.10	8195.58	Rupees Eight Thousand One Hundred Ninety Five and Paise Fifty Eight Only
Total in figure :					291517.93	Rupees Two Lakh Ninety One Thousand Five Hundred Seventeen and Paise
Total in Words :		Rupees Two Lakh Ninety One Thousand Five Hundred Seventeen and Paise Ninety Three Only				

Executive Engineer,
Mandi Division No.1,
HP, PWD, at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 291517.93
 Earnest Money Rs:- 5800.00
 Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.					
Name of work :- Restoration of rain damages on Jhanad Balh Khajwah road km. 0/00 to 11/540. (PDNA -2023). (Sub Head :- Construction of 900 mm dia Hume Pipe Culvert at RD. 4/165 alongwith wing walls).					
Contract No. :					
Bidder Name :					
SCHEDULE OF WORKS					
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	47.25	Per cubic metre	522.50	Rupees Twenty Four Thousand Six Hundred Eighty Eight and Paise Thirteen Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802.803,1202 & 1203. Plain cement concrete nominal mix 1:6:12 (One cement : Six sand : Twelve graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	1.21	Per cubic metre	4705.80	Rupees Five Thousand Six Hundred Ninety Four and Paise Two Only
3	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802.803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	31.97	Per cubic metre	5183.80	Rupees One Lakh Sixty Five Thousand Seven Hundred Twenty Six and Paise Nine Only
4	Providing concrete for plain/reinforced concrete Grade-M-10 nominal mix 1:3:6 (one cement : three sand : twelve graded,crushed stone aggregate 20mm (twenty millimetre) nominal size) in open foundations complete as per drawings and technical specifications clause 802. 803, 1202 & 1203 curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	9.73	Per cubic metre	5374.60	Rupees Fifty Two Thousand Two Hundred Ninety Four and Paise Eighty Six Only
5	Providing and laying reinforced cement concrete 900mm (Nine hundred millimetre) diameter pipe NP2 as per design for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement: two sand) but excluding excavations, protection works, back filling, concrete and masonry works in head walls and parapets as per drawings and technical specifications for Rural roads clause 1101 including carriage of material within all leads, lifts and other incidentals complete in all respect as per direction of Engineer-in-Charge.	7.50	Per running metre	4204.70	Rupees Thirty One Thousand Five Hundred Thirty Five and Paise Twenty Five Only

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
6	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	12.00	Each	282.00	3384.00	Rupees Three Thousand Three Hundred Eighty Four Only
7	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	5.42	Per cubic metre	1512.10	8195.58	Rupees Eight Thousand One Hundred Ninety Five and Paise Fifty Eight Only
Total in figure :					291517.93	Rupees Two Lakh Ninety One Thousand Five Hundred Seventeen and Paise Ninety Three Only
Total in Words :		Rupees Two Lakh Ninety One Thousand Five Hundred Seventeen and Paise Ninety Three Only				

Executive Engineer,
Mandi Division No.1,
HP. PWD. at Padhary

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 291517.93
Earnest Money Rs:- 5800.00
Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP, PWD, at Padhar.						
Name of work :- Restoration of rain damages on Jhanad Balh Khajwhal road km. 0/00 to 11/540. (PDNA -2023). (Sub Head :- Construction of 900 mm dia Hume Pipe Culvert at RD. 0/065 alongwith wing walls).						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	47.25	Per cubic metre	522.50	24688.13	Rupees Twenty Six Hundred Eighty Eight and Paise Thirteen Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:6:12 (One cement : Six sand : Twelve graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	1.21	Per cubic metre	4705.80	5694.02	Rupees Five Thousand Six Hundred Ninety Four and Paise Two Only
3	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:4:8 (one cement : four sand : eight graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	31.97	Per cubic metre	5183.80	165726.09	Rupees One Lakh Sixty Five Thousand Seven Hundred Twenty Six and Paise Nine Only
4	Providing concrete for plain/reinforced concrete Grade-M-10 nominal mix 1:3:5 (one cement : three sand : twelve graded,crushed stone aggregate 20mm (twenty millimetre) nominal size) in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 & 1203 curing complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	9.73	Per cubic metre	5374.60	52294.86	Rupees Fifty Two Thousand Two Hundred Ninety Four and Paise Eighty Six Only
5	Providing and laying reinforced cement concrete 900mm (Nine hundred millimetre) diameter pipe NP2 as per design for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement: two sand) but excluding excavations, protection works, back filling, concrete and masonry works in head walls and parapets as per drawings and technical specifications for Rural roads clause 1101 including carriage of material within all leads, lifts and other incidentals complete in all respect as per direction of Engineer-in-Charge.	7.50	Per running metre	4204.70	31535.25	Rupees Thirty One Thousand Five Hundred Thirty Five and Paise Twenty Five Only

3

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
6	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia. (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V-20H (one vertical into twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	12.00	Each	282.00	3384.00	Rupees Three Thousand Three Hundred Eighty Four Only
7	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	5.42	Per cubic metre	1512.10	8195.58	Rupees Eight Thousand One Hundred Ninety Five and Paise Fifty Eight Only
Total in figure :					291517.93	Rupees Two Lakh Ninety One Thousand Five Hundred Seventeen and Paise Ninety Three Only
Total in Words :		Rupees Two Lakh Ninety One Thousand Five Hundred Seventeen and Paise Ninety Three Only				

Executive Engineer,
Mandi Division No.1,
HP. PWD. at Padhary

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 165902.00
 Earnest Money Rs:- 3300.00
 Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.						
Name of work :- Restoration of rain damages on Drang Basahi road 0/00 to 22/00. (PDNA-2023) (Sub Head:- Constuction of wire created Breast wall at RD 3/335 to 3/345).						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	37.50	Per cubic metre	553.20	20745.00	Rupees Twenty Thousand Seven Hundred Forty Five Only
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) diameter G.I. wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (one hundred millimetre into one hundred millimetre) mesh (woven diagonally) including 10% (ten percent) extra for laps and joints laid with stones boulders weighting not less than 25 Kg. (twenty five kilogram) each as per drawing and technical specifications clause 1301 including carriage of material within all leads, lifts and other incidentâls complete in all respect as per direction of Engineer-in-Charge.	46.88	Per cubic metre	3096.36	145157.00	Rupees One Lakh Forty Five Thousand One Hundred Fifty Seven Only
Total in figure :					165902.00	Rupees One Lakh Sixty Five Thousand Nine Hundred Two Only
Total in Words :		Rupees One Lakh Sixty Five Thousand Nine Hundred Two Only				

Executive Engineer,
 Mandi Division No.I,
 HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 344805
Earnest Money Rs:- 5900.00
Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 H.P.P.W.D. at Padhar.

Name of work :- Restoration of rain damages on Drang Basahi road 0/00 to 22/00. (PDNA-2023) (Sub Head:- Constuction of Composite Masonry Retaining wall at RD 7/010 to 7/022).

Contract No. :

Bidder Name :

SCHEDULE OF WORKS

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	35.04	Per cubic metre	553.20	19384.13	Rupees Nineteen Thousand Three Hundred Eighty Four and Paise Thirteen Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:6:12 (One cement : Six sand : Twelve graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	4.25	Per cubic metre	4739.30	20142.03	Rupees Twenty Thousand One Hundred Forty Two and Paise Three Only
3	Stone masonry in cement mortar for substructure complete as per drawing and technical specification clauses 702, 704,1202 & 1204 in cement mortar (2nd short) 1:6 (one cement : six coarse sand) and curing complete including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	14.99	Per cubic metre	6319.00	94721.81	Rupees Ninety Four Thousand Seven Hundred Twenty One and Paise Eighty One Only
4	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : Ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	38.56	Per cubic metre	4898.10	188870.74	Rupees One Lakh Eight Hundred Seventy and Paise Seventy Four Only
5	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	27.00	Each	279.10	7535.70	Rupees Seven Thousand Five Hundred Thirty Five and Paise Seventy Only
6	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	9.12	Per cubic metre	1551.60	14150.59	Rupees Fourteen Thousand One Hundred Fifty and Paise Fifty Nine Only
Total in figure :					344805.00	Rupees Three Lakh Forty Four Thousand Eight Hundred Five Only
Total in Words :					Rupees Three Lakh Forty Four Thousand Eight Hundred Five Only	

Executive Engineer
Mandi Division No. 1
H.P.P.W.D. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 291890.56
Earnest Money Rs:- 5800.00
Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 H.P.P.W.D. at Padhar.

Name of work :- Restoration of rain damages on Kufri Kheel Nihon Damela Road km. 0/00 to 8/100. (PDNA -2023). (Sub Head:- Construction of Composite masonry Breast wall at R.D. 5/510 to 5/530).

Contract No. :

Bidder Name :

SCHEDULE OF WORKS

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	40.60	Per cubic metre	522.50	21213.50	Rupees Twenty One Thousand Two Hundred Thirteen and Paise Fifty Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:6:12 (One cement : Six sand : Twelve graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	4.84	Per cubic metre	4768.40	23079.06	Rupees Twenty Three Thousand Seventy Nine and Paise Six Only
3	Random rubble masonry in cement mortar for substructure complete as per drawing and technical specification in cement mortar 1:6 (one cement : six coarse sand) and curing complete including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	15.82	Per cubic metre	5974.70	94519.75	Rupees Ninety Four Thousand Five Hundred Nineteen and Paise Seventy Five Only
4	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : Ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	28.98	Per cubic metre	4947.60	143381.45	Rupees One Lakh Forty Three Thousand Three Hundred Eighty One and Paise Forty Five Only
5	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	34.00	Each	285.20	9696.80	Rupees Nine Thousand Six Hundred Ninety Six and Paise Eighty Only
Total in figure :					291890.56	Rupees Two Lakh Ninety One Thousand Eight Hundred Ninety and Paise Fifty Six Only
Total in Words :					Rupees Two Lakh Ninety One Thousand Eight Hundred Ninety and Paise Fifty Six Only	

Executive Engineer
Mandi Division No 1
H.P.P.W.D. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 499375.62
Earnest Money Rs:- 8900.00
Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.						
Name of work :- Restoration of rain damages on Padhar Balh road km. 0/00 to 18/500. (Sub Head: - Construction of Retaining wall at R.D. 6/320 to 6/328.65).						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	34.25	Per cubic metre	553.20	18947.10	Rupees Eighteen Thousand Nine Hundred Forty Seven and Paise Ten Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : Ten graded, crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	91.02	Per cubic metre	4983.40	453589.07	Rupees Four Lakh Fifty Three Thousand Five Hundred Eighty Nine and Paise Seven Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	24.00	Each	279.80	6715.20	Rupees Six Thousand Seven Hundred Fifteen and Paise Twenty Only
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	12.97	Per cubic metre	1551.60	20124.25	Rupees Twenty Thousand One Hundred Twenty Four and Paise Twenty Five Only
Total in figure :					499375.62	Rupees Four Lakh Ninety Nine Thousand Three Hundred and Paise Sixty Two Only
Total in Words :					Rupees Four Lakh Ninety Nine Thousand Three Hundred and Paise Sixty Two Only	

Executive Engineer,
Mandi Division No.1,
HP. PWD. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 127443.08

Earnest Money Rs:- 2500.00

Time One Month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.						
Name of work :- Construction of Science Lab at GDC Drang at Narla. (Sub Head:- Making plinth protection, Construction course rubble hammer dressed "U" shape open surface drain.						
Contract No. :						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Making plinth protection 50mm (fifty millimetre) thick of cement concrete 1:3:6 (one cement : three coarse sand : six graded, crushed stone aggregate 20 mm (twenty millimetre) nominal size) over 75mm (seventy five millimetre) thick bed of dry brick ballast 40 mm (forty millimetre) nominal size, well rammed and consolidated and grouted with fine sand, including necessary excavation, levelling & dressing & finishing the top smooth including curing and carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	54.96	Per square metre	495.00	27205.20	Rupees Twenty Seven Thousand Two Hundred Five and Paise Twenty Only
2	Constructing course rubble hammer dressed U-Shape open surface drain with side wall 15x22cm (fifteen into twenty two centimetre) in cement mortar 1:6 (one cement : six sand) and inside plastering with cement plaster 1:3 (one cement : three sand) including earth work and laying 10cm (ten centimetre) cement concrete in 1:5:10 (one cement : five sand : ten graded/crushed stone aggregate of 40mm (forty millimetre) nominal size) and 7.5cm (seven point five centimetre) cement concrete 1:2:4 (one cement : two sand : four graded, crushed stone aggregate of 20mm (twenty millimetre) nominal size) and finished with a floating coat of neat cement complete as per standard design including curing and carriage of material with in all leads, lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	91.60	Per Running metre	1094.30	100237.88	Rupees One Lakh Two Hundred Thirty Seven and Paise Eighty Eight Only
Total in figure :					127443.08	Rupees One Lakh Twenty Seven Thousand Four Hundred and Paise Eight Only
Total in Words :		Rupees One Lakh Twenty Seven Thousand Four Hundred Forty Three and Paise Eight Only				

Executive Engineer,
Mandi Division No-1,
HP. PWD. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 97350.00
Earnest Money Rs:- 1950.00
Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.						
Name of work:- Restoration of rain damages on various road under Tikken Section Sub-Division HPPWD Jhatingri. (Sub Head:- Hiring of Tipper for Carriage of Mucks/debris/stone Boulder etc.)						
Contact No. :						
Bidder Name:						
SCHEDULE OF WORKS						
Sr. No	Description of item	Qty.	Units	Estimate Rate Rs. P.	Total Amount with all taxes Including GST in Rs. P.	Total Amount with all taxes Including GST in words
1	Hiring of tipper of 10.5 cum / 10 tonne capacity (five point five cubic metre/ten tonne capacity) for carriage of earth/debris, boulder and other construction materials from various location etc. complete including wages of tipper driver, cleaner and P.O.L. any repair / damage during work will be absolute responsibility of the contractor/owner tipper has to work at least 8 hours per day. Only actual working day shall be accounted for the payment. No payment will be made for sunday and holidays as well as certain day if there is no work to the entire satisfaction of Engineer-in-Charge.	33.00	Per Day	2950.00	97350.00	Rupees Ninety Seven Thousand Three Hundred Fifty Only
Total in figure :					97350.00	Rupees Ninety Seven Thousand Three Hundred Fifty Only
Total in Words :		Rupees Ninety Seven Thousand Three Hundred Fifty Only				

Condition:- Contractor should have his own machinery or he should have an agreement with the owner of the machinery.

Executive Engineer,
Mandi Division No-I,
HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 97350.00

Earnest Money Rs:- 1950.00

Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.
Name of work : Restoration of rain damages on various road under Sudhar Section Sub-Division HPPWD Jhatingri. (Sub Head:- Hiring of Tipper for Carriage of Mucks/debris/stone, Boulder etc.)

Contact No. :

Bidder Name:

SCHEDULE OF WORKS						
Sr. No.	Description of item	Qty.	Units	Estimate Rate Rs. P.	Total Amount with all taxes Including GST in Rs. P.	Total Amount with all taxes Including GST in words
1	Hiring of tipper of 10.5 cum / 10 tonne capacity (five point five cubic metre/ten tonne capacity) for carriage of earth/debris, boulder and other construction materials from various location etc. complete including wages of tipper driver, cleaner and P.O.L. any repair / damage during work will be absolute responsibility of the contractor/owner tipper has to work at least 8 hours per day. Only actual working day shall be accounted for the payment. No payment will be made for sunday and holidays as well as certain day if there is no work to the entire satisfaction of Engineer-in-Charge.	33.00	Per Day	2950.00	97350.00	Rupees Ninety Seven Thousand Three Hundred Fifty Only
Total in figure :					97350.00	Rupees Ninety Seven Thousand Three Hundred Fifty Only
Total in Words :					Rupees Ninety Seven Thousand Three Hundred Fifty Only	

Condition:- Contractor should have his own machinery or he should have an agreement with the owner of the machinery.

Executive Engineer,
Mandi Division No-I,
HP. PWD. at Padhar.