



Himachal Pradesh
Public Works Department
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

No. PWD/BWD/TA/NIT/ 2026-27- 6875-84 Dated:- 06-10-2026

To

The Chief Engineer (KZ),
HPPWD Dharamshala.

Subject:-

Publication of Tender Notice.

Enclosed please find herewith Tender Notice of works as given in the Notice inviting Tenders along with schedule of quantities for uploading on departmental website as per directions received through e-mail dated 25.06.2026 from Worthy Engineer-in-Chief, HP.PWD Nigam Vihar Shimla.

It is certified that the work mentioned in the Notice inviting tenders are urgent in nature and in Public interest.

DA/ As Above


Executive Engineer
Bhawarna Division
HP.PWD Bhawarna

Copy along with copy of tender Notice is forwarded to the following for information.

1. The Superintending Engineer, 5th Circle, HPPWD Palampur.
2. All Assistant Engineers working under this division.
3. The Drawing/ Accounts Branch in this office.
4. Notice Board.


Executive Engineer
Bhawarna Division
HP.PWD Bhawarna



Himachal Pradesh
Public Works Department
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

CERTIFICATE

Certified that tender of works are being called of an emergent nature and for larger public interest so there is exigencies/ emergency in calling these tenders without press vide this office letter No. PWD/BWD/TA/NIT/2026-27- 6875-84 dated 06-10-2026.


Executive Engineer,
Bhawarna Division,
HPPWD. Bhawarna.



Himachal Pradesh
Public Works Department
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

"NOTICE INVITING TENDERS"


Sealed percentage rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Bhawarna Division HP.PWD. Bhawarna on behalf of the Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **13-10-2026** up to 11.00 AM. and the same shall be opened on the same day at **11.30 A.M.** in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable) on 12-10-2026 up to **4.00 P.M** and the application for issue of tender form shall be received on 12-10-2026 up to **1.00 PM**.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

Sr. No.	Name of Work	Estimated cost excluding GST(In Rs.)	Earnest Money	Time Limit	Cost of Tender form
1	A/R & M/O Executive Engineer office HPPWD Division Bhawarna (SH:- Providing and fixing Cup boards)	81,900/-	1600/-	Three Months	350/-
2	Restoration of rain damages on Garh Basti to Malkehar via Dogi ITI road. (SH:- Providing and Laying CC work in km 2/410 to 2/454)	84,615/-	1700/-	Three Months	350/-
3	Restoration of rain damages on Tikker Balhbhurian road (SH:- Construction of Retaining wall at km 0/055 to 0/064) (Under PDNA-2025)	1,62,579/-	3300/-	Six Months	350/-
4	Restoration of rain damages on Bairghatta to Sanhoon road (SW:- C/o unlined drain & Maintenance of Earthen shoulds at various RDs) (Under PDNA 2025)	1,90,000/-	3800/-	Three Months	350/-

Terms & Conditions:-

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor/firm has to produce the copy of latest enlistment and renewal enlisted in HP.PWD.
3. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tender without assigning any reason.


Executive Engineer
Bhawarna Division
HPPWD Bhawarna.

On behalf of Governor of Himachal Pradesh

Schedule of Quantity

Name of Work :- A/R & M/O Executive Engineer office HPPWD Division Bhawarna (Sh:- Providing and fixing Cup boards)

Estimated Cost :-Rs. 81,900/-
Earnest Money :-Rs. 1600/-

Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing and fixing the complete box of cup board shall be made of 25mm (Twenty Five millimetre) thick water proof termite resistant commercial board of Uniply / Green ply/ IS marked including shelves back side of board shall have 8 mm (Eight millimetre) thick water proof ply. All the cut portion of board shall have 6 mm (Six millimetre) thick hard wood edging. The shutter from all side shall be finished with 1mm thick lamination ISI Marked of approved shade of Century / Greenlam /Action Tesa and 19 mm (Nineteen millimetre) thick water proof commercial board of uniply / Greenply for shelves including hinges, handle,knob magnetic catcher complete as per specifications, approved drawing, design, as per the entire satisfaction and direction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, and any other taxes imposed by the Government but excluding GST.	19.50	4200.00	Rupees Four Thousand Two Hundred Only	Per Square metre	81900.00
Total :-						81900.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					

Executive Engineer
Bhawarna Division
HP PWD Bhawarna

Name of Work :- Restoration of rain damage on Garh Basti to Malkehar via Dogi ITI road. (SH:- Providing and Laying CC work in Km 2/410 to 2/454).

Schedule of Quantity

Estimated Cost :-Rs. 84,615/-
Earnest Money :-Rs. 1700/-
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing, laying, Soling 90 to 45mm (Ninety to forty five millimetre) nominal size Grading-1, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 Kn. Static roller in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 1 as per technical specification Clause 405 as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, and any other taxes imposed by the Government but excluding GST.	1.50	1740.00	Rupees Nineteen point five zero only	Per Cubic metre	2610.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) in sub structure nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 40mm (forty millimetre) nominal size using cement contents not less than 330 Kg (Three hundred thirty kilogram) per cubic metre on ground or under water and curing complete including pumping or boiling out water, dewatering, removal of slush which may arise at the time of laying concrete complete for all height/ depths including cost of form work in open foundation as per drawing and MORD technical specification section 800, 900, 1200 including carriage of material with in all leads, lifts and other incidentals as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, and any other taxes imposed by the Government but excluding GST.	15.13	5420.00	Rupees Nineteen point five zero only	Per Cubic metre	82005.00
Total :-						84615.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					

Executive Engineer
Bhawarna Division
HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Restoration of rain damages on Tikker Balbhurian road, (SH:- Construction of Retaining wall at Km 0/055 to 0/064) (Under PDNA-2025).

Estimated Cost :-Rs. 1,62,579/-
Earnest Money :-Rs. 3300/-
Time Limit :- Six Months

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, and any other taxes imposed by the Government but excluding GST.	17.82	210.00	Rupees Two Hundred Ten Only	Per Cubic metre	3742.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement : four sand : eight graded crushed/ broken stone aggregate 40mm (forty millimetre) nominal size on ground or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification section 800, 900 and 1200 and as per the entire satisfaction and direction of the Engineer -In-Charge including carriage of materials within all lead, and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, and any other taxes imposed by the Government but excluding GST.	38.88	3810.00	Rupees Three Thousand Eight Hundred Ten Only	Per Cubic metre	148133.00
3	Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, and any other taxes imposed by the Government but excluding GST.	10.80	680.00	Rupees Six Hundred Eighty Only	Per Cubic metre	7344.00

4	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, and any other taxes imposed by the Government but excluding GST.	16.00	210.00	Rupees Two Hundred Ten Only	Each	3360.00
Quoted rates percentage in figures				Total :-		162579.00
Quoted rates percentage in words						

Executive Engineer
Bhawarna Division
HP PWD Bhawarna

Schedule of Quantity

Name of Work :- Restoration of rain damages on Bairghatta to Sanhoon road. (SW:- C/o Unlined drain & Maintenance of Earthen Shoulder at various RDS). (Under PDA - 2025)

Estimate Cost :-Rs. 1,90,000/-
Earnest Money :-Rs. 3800/-
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Construction of un lined surface drain of average cross sectional area 0.40 Sqm. In soil to specified lines, grades, level and dimension excavated materials to be used in embankment with a lift upto 3 m and lead of 50m (Average lead 25m) as per technical specification clause 307. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, and any other taxes imposed by the Government but excluding GST.	1400.00	35.00	Rupees Thirty Five Only	Per Running metre	49000.00
2	Maintenance of Earthen shoulder (Filling with fresh selected soil) Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per Technical specification clause 1903. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, and any other taxes imposed by the Government but excluding GST.	4700.00	30.00	Rupees Thirty Only	Per Square metre	141000.00
Total :-						190000.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					

Executive Engineer
Bhawarna Division
HP PWD Bhawarna