

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

No.PW-MDI(P)E-Tender-NIT/2026-27- 12568-74 Dated:- 07/10/2026

To

The Chief Engineer (MZ),
HPPWD, Mandi.

Subject: - Publishing of tender notice.

Dear Sir,

Enclosed please find herewith the Tender Notice of works as given in the Notice Inviting Tender for uploading on department website as per notification Principal Secretary (PW) to the Govt. of H.P. letter No. PBW(B) A(3)1/2024 dated Shimla-2 the 03.01.2024 and No. PBW (B) A (3) 8/2025- 300858 dated 13th Nov., 2025 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender.

Executive Engineer,
Mandi Division No.I,
HP PWD, at Padhar

Copy alongwith copy of Tender Notice is forwarded to the following for information and necessary action:-

1. The Superintending Engineer, JNR Circle, HPPWD, Joginder Nagar.
2. All the Assistant Engineers, Working under this Division.
3. The Drawing Branch of this office.
4. Notice Board.

Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Sealed percentage rate tender on form No. 6&8 are hereby invited by the Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar on behalf of the Governor of Himachal Pradesh for the below noted works from eligible Contractors/firms registered in H.P.P.W.D. in appropriate class as per revised enlistment rules, so as to reach in this office on or before 15.10.2026 up to 12:00 Noon and the same shall be opened on the same day at 12:30 P.M. in the presence of the Contractors or their authorized representatives who may be present. The tender form can be held from this office against cash payment (Non Refundable) on 14.10.2026 upto 12:00 Noon Contractors in person or their authorized representatives. The application will not be accepted without Earnest Money & Cost of tender form.

The tender shall accompany with Earnest Money which should be in the shape of NSC/Time Deposit/Saving Bank account in the Post Office/bank in H.P. duly pledged in the favour of undersigned.

Conditional tenders, telegraphic and tender without earnest money will not be entertained. The Executive Engineer, Mandi Division No.I, HP. PWD., at Padhar reserves the right to accept or reject the tenders. The tender shall remain valid for 75 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/ Gazetted Holiday the same shall be process on next date.

Sr. No.	Name of work.	Estimated Cost (in Rs.)	Earnest Money (in Rs.)	Cost of Tender Form (in Rs.)	Time
1	Regarding Erosion of Land along Sub-Centre Building at Lapas. (SH:- Construction of Retaining wall to protection wall to protect the sub-center Building at Lapas) (Deposit)	2,59,296.59	5,200/-	350/-	One month
2	NDF/2025/14, R/O (Repair of) Restoration of rain damages on Silhbudhani Kungri Kortang road Km 0/00 to 5/500 Muhal. (Deposit) (SH:- Construction of wing wall before culvert at RD 4/650 and C/O Retaining wall at RD 4/670 to 4/674.20)	2,53,533.68	5,100/-	350/-	One month
3	NDF/2026/203, R/O (Repair of) Restoration of rain damages on Thaltukhod Marh road Km 0/00 to 5/00 Mohal (Deposit) (SH:- Removal of slips at RD 2/545 to 2/610 & Construction of Wire Crated Breast wall at RD 2/555 to 2/579)	3,12,327.29	6,200/-	350/-	One month
4	NDF/2023/1588, R/O (Repair of) Restoration of rain damages on Silhbudhani Kungri Kortang road Km 0/00 to 5/00 Mohal. (SH:- Construction of retaining wall at RD 3/465 to 3/470.25)	1,99,786.64	4,000/-	350/-	One month
5	NDF/2023/1594, R/O (Repair of) Restoration of rain damages on Ropa to Kathog road Km 0/00 to 5/00 Mohal. (SH:- Construction of retaining wall at RD 0/690 to 0/694.75)	1,68,289.84	3,400/-	350/-	One month
6	Restoration of rain damages on Ghatasani Jhatingri Tikken Barot road Km 0/00 to 25/00 (PDNA-2023) (SH:- Construction of Retaining wall at RD 1/900 to 1/903 & 9/990 to 9/994.80)	1,06,882.31	2,100/-	350/-	One month
7	Restoration of rain damages on Ghatasani Jhatingri Tikken Barot road Km 0/00 to 25/00 (SH:- Construction of wire crated retaining wall at RD 10/855 to 10/871.80)	2,03,742.67	4,100/-	350/-	One month

8	Restoration of rain damages on Ghatasani Jhatingri Tikken Barot road Km 0/00 to 25/00 (PDNA-2023) (SH:- Construction of Retaining wall at RD 8/930 to 8/945)	1,06,882.31	2,100/-	350/-	One month
9	Restoration of rain damages on Barot to Mayot road Km 0/00 to 25/00. (PDNA-2023) (SH:- Construction of Retaining wall at RD 5/427 to 5/440)	2,91,636.99	5,800/-	350/-	One month
10	Restoration of rain damages on Tikken to Thaltukhod road Km 0/00 to 4/500 (SH:- Construction of Retaining wall at RD 3/180 to 3/185)	1,79,936.42	3,600/-	350/-	One month
11	Restoration of rain damages on Silhbudhani Kungri Kortang road Km 0/00 to 5/500. (PDNA-2023) (SH:- Construction of wing wall before culvert & after at RD 2/016)	2,13,467.58	4,300/-	350/-	One month
12	Restoration of rain damages on Dharmehar Tarswan Dragar Gadghaon road Km 0/00 to 5/150 (PDNA-2023) (SH:- Construction of 900 dia HPC at RD 2/510 alongwith wing wall)	3,94,129.96	7,900/-	350/-	One month
13	Restoration of rain damages on Thaltukhod Marh road Km 0/00 to 5/00 (PDNA-2023) (SH:- Construction of Retaining wall at RD 0/039 to 0/048)	4,67,389.00	9,300/-	350/-	One month
14	Restoration of rain damages on Balh to Ropa road Km 0/00 to 5/100 (PDNA-2023) (SH:- Construction of Retaining wall at RD 4/420 to 4/426)	3,16,542.28	6,300/-	350/-	One month
15	Restoration of rain damages on Ropa Sarni road Km 0/00 to 3/720 (PDNA-2023) (SH:- Construction of Retaining wall at RD 0/085 to 0/093)	4,23,906.10	8,500/-	350/-	One month
16	Restoration of rain damages on Ropa Sarni road Km 0/00 to 3/720 (PDNA-2023) (SH:- Construction of Retaining wall at RD 2/120 to 2/130)	3,66,239.14	7,100/-	350/-	One month
17	Restoration of rain damages on Ropa Sarni road Km 0/00 to 3/720 (PDNA-2023) (SH:- Construction of Retaining wall at RD 0/093 to 0/100)	3,71,634.69	7,400/-	350/-	One month
18	Restoration of rain damages on Ropa Kathog road Km 0/0 to 5/00 (PDNA-2023) (SH:- Construction of Retaining wall at RDs 2/790 to 2/797 and 3/750 to 3/760)	4,13,532.81	8,300/-	350/-	One month
19	Restoration of rain damages on Ropa Kathog road Km 0/0 to 5/00 (PDNA-2023) (SH:- Construction of Retaining wall at RDs 3/780 to 3/790)	3,68,269.81	7,400/-	350/-	One month
20	Restoration of rain damages on Balh to Kathog road Km 0/00 to 5/00 (PDNA-2023) (SH:- Construction of Retaining wall at RDs 1/105 to 1/120 and 1/450 to 1/460)	4,98,583.90	10,000/-	350/-	One month
21	Restoration of rain damages on Tikkar Sarni road Km 0/00 to 3/720 (PDNA-2023) (SH:- Construction of Retaining wall at RD 0/900 to 0/920)	3,98,665.12	8,000/-	350/-	One month
22	Restoration of rain damages on Ropa to Droon road Km 0/00 to 3/00. (PDNA-2023) (SH:- Providing and Laying Kharanja Stone at RD 1/525 to 1/640)	57,286.70	1,150/-	350/-	One month

23	Restoration of rain damages on Ropa Droon road Km 0/00 to 5/00 (PDNA-2023) (SH:- Construction of wire crated solid Causeway at RD 1/676 to 1/192.80)	4,66,808.54	9,300/-	350/-	One month
----	--	-------------	---------	-------	-----------

1. Certified that tender of above works are being called of emergent nature in exigency of public interest.

TERMS AND CONDITIONS:-

1. The Contractor/ Firm should be enlisted with the HP.PWD & Registration/ Renewal copy attached.
2. The Contractor/Firm shall have his GST. No. & copy of the same be attached with the application.
3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & cost of tender form shall summarily be rejected.
4. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender forms. In this regard, contractor has to submit an affidavit/ undertaking that he is not having more two works.
5. Only two tenders form will be issued to the contractor/firms which may be noted.
6. The intending Contractors are requested to see the site of the work before submitting the tender.
7. The offer of the tender shall remain valid upto 75 days after the opening of tender.
8. The tender shall be awarded to the lowest bidder if his tendered amount is within limit of (+) 5% of the amount put to tender, otherwise the tender will be cancelled and recalled.
9. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.

Executive Engineer,
Mandi Division No. I,
HPPWD, at Padhar Distt. Mandi (H.P.)
on behalf of Governor of Himachal Pradesh

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 259296.59
 Earnest Money Rs:- 5200.00
 Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.						
Name of Work:- Regarding Erosion of Land along Sub-Center Building at Lapas.(Construction of Retaining Wall to protect the sub-center Building at Lapas) (Deposit)						
Contract No. :						
Name of the Bidder/Bidding Firm/Company :						
PRICE SCHEDULE						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	Total Amount with all taxes excluding GST in Rs. P.	Total Amount with all taxes excluding GST in words.
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50.00 metres, dressing of sides and bottoms and back filling in trenches with excavated suitable materials including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	25.68	Per cubic metre	485.30	12462.50	Rupees Twelve Thousand Four Hundred Sixty Two and Paise Fifty Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802.803,1202 & 1203. P.C.C. nominal mix 1:5:10 (1 cement: 5 Sand : 10 graded, crushed stone aggregate)(40mm aggregates) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-	39.71	Per cubic metre	5812.30	230806.43	Rupees Two Lakh Thirty Thousand Eight Hundred Six and Paise Forty Three Only
3	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing walls, return walls with 100mm dia PVC Pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204, 3.7 including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	18.00	Each	307.10	5527.80	Rupees Five Thousand Five Hundred Twenty Seven and Paise Eighty Only
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 (Granular material) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	6.96	Per cubic metre	1508.60	10499.86	Rupees Ten Thousand Four Hundred Ninety Nine and Paise Eighty Six Only
Total in figure :					259296.59	Rupees Two Lakh Fifty Nine Thousand Two Hundred Ninety Six and Paise Fifty Nine Only
Total in Words :		Rupees Two Lakh Fifty Nine Thousand Two Hundred Ninety Six and Paise Fifty Nine Only				

Executive Engineer,
 Mandi Division No.I,
 HP.PWD. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 253533.68
Earnest Money Rs:- 5100.00
Time one month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP, PWD, at Padhar.						
Name of Work:- NDF/2025/14, R/O (Repair of) Restoration of rain damages on Silbudhani Kungri Kortang road 0/00 to 5/500 Muhai (Deposit) (Sub Head:- Construction of wing wall before culvert at RD 4/650 and C/O Retaining wall at RD 4/670 to 4/674.20).						
Contract No:-						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50.00 metres, dressing of sides and bottoms and back filling in trenches with excavated suitable materials including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	21.43	Per cubic metre	522.50	11197.18	Rupees Eleven Thousand One Hundred Ninety Seven and Paise Seventeen Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. P.C.C. nominal mix 1:5:10 (one cement: Five Sand : Ten graded, crushed stone aggregate)(40mm aggregates) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	44.76	Per cubic metre	5043.50	225747.06	Rupees Two Lakh Twenty Five Thousand Seven Hundred Forty Seven and Paise Six Only
3	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing walls, return walls with 100mm dia PVC Pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204, 3.7 including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	24.00	Each	288.00	6912.00	Rupees Six Thousand Nine Hundred Twelve Only
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 (Granular material) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	6.40	Per cubic metre	1512.10	9677.44	Rupees Nine Thousand Six Hundred Seventy Seven and Paise Forty Four Only
Total in figure :					253533.68	Rupees Two Lakh Fifty Three Thousand Five Hundred Thirty Three and Paise Sixty Seven Only
Total in Words :		Rupees Two Lakh Fifty Three Thousand Five Hundred Thirty Three and Paise Sixty Seven Only				

Executive Engineer,
Mandi Division No.1,
HP, PWD, at Padhar

ga...

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 312327.29
Earnest Money Rs:- 6200.00
Time one month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP. PWD. at Padhar.

Name of Work:- NDF/2026/203, R/O (Repair of) Restoration of rain damages on Thaltukhod Marh road Km 0/00 to 5/00 Mohal. (Deposit) (Sub Head:- Removal of slips at RD 2/545 to 2/610 & Construction of Wire Crated Breast wall at RD 2/555 to 2/579)

Contract No:-

Bidder Name :

SCHEDULE OF WORKS						
Sr. No.	Description of Items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Removal of landslids/ slip clearncoe. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and road upto 1000 metre as per technical specification 302.3.5 and 1611.including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	831.75	Per cubic metre	147.20	122433.60	Rupees One Lakh Twenty Two Thousand Four Hundred Thirty Three and Paise Sixty Only
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50.00 metres, dressing of sides and bottoms and back filling in trenches with excavated suitable materials. including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	22.20	Per cubic metre	553.00	12276.60	Rupees Twelve Thousand Two Hundred Seventy Six and Paise Sixty Only
3	Providing and laying boulder apron laid in wire crates with 4mm dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm mesh (woven diagonally) including 10% extra for laps and joints laid with stones boulder weighing not less then 25Kg. Each as per drawing and technical specification clause 1301.including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	57.60	Each	3083.63	177617.09	Rupees One Lakh Seventy Seven Thousand Six Hundred Seventeen and Paise Nine Only
Total in figure :					312327.29	Rupees Three Lakh Twelve Thousand Three Hundred Twenty Seven and Paise Twenty
Total in Words :		Rupees Three Lakh Twelve Thousand Three Hundred Nine Only				Twenty Seven and Paise Twenty


Executive Engineer,
Mandi Division No. I,
HP. PWD. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs: 199786.64
 Earnest Money Rs: 4000.00
 Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP, PWD, at Padhar.

Name of Work:- NDF/2023/1588, R/O (Repair of) Restoration of rain damages on Silhbudhani Kungri Kortang road km 0/00 to 5/00 Mohal (Sub Head:- Construction of retaining wall at RD 3/465 to 3/470.25).

Contract No. :

Name of the Bidder/Bidding Firm/Company :

PRICE SCHEDULE

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	Total Amount with all taxes excluding GST in words.
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50.00 metres, dressing of sides and bottoms and back filling in trenches with excavated suitable materials including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	18.22	Per cubic metre	522.50	Rupees Nine Thousand Five Hundred Nineteen and Paise Ninety Five Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802.803, 1202 & 1203. P.C.C. nominal mix 1:5:10 (one cement: five Sand : ten graded, crushed stone aggregate)(40mm aggregates) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	34.14	Per cubic metre	5034.40	Rupees One Lakh Seventy One Thousand Eight Hundred Seventy Four and Paise Forty Two Only
3	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing walls, return walls with 100mm dia PVC Pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204, 3.7 including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	34.14	Each	287.60	Rupees Nine Thousand Eight Hundred Eighteen and Paise Sixty Six Only
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 (Granular material) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	5.67	Per cubic metre	1512.10	Rupees Eight Thousand Five Hundred Seventy Three and Paise Sixty One Only
Total in figure :				199786.64	Rupees One Lakh Ninety Nine Thousand Seven Hundred Eighty Six and Paise Sixty Four Only
Total in Words :					Rupees One Lakh Ninety Nine Thousand Seven Hundred Eighty Six and Paise Sixty Four Only

Executive Engineer,
 Mandi Division No.I,
 HP.PWD. at Padhar. *ge...*

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs: 168289.84
Earnest Money Rs: 3400.00
Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.						
Name of Work:- NDF/2023/1594, R/O (Repair of) Restoration of rain Damages on Ropa to Kathog road km 0/00 to 5/00 Mohal (Sub Head:- Construction of retaining wall at RD 0/690 to 0/694.75).						
Contract No. :						
Name of the Bidder/Bidding Firm/Company :						
PRICE SCHEDULE						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	Total Amount with all taxes excluding GST in words.	Total Amount with all taxes excluding GST in words.
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50.00 metres, dressing of sides and bottoms and back filling in trenches with excavated suitable materials including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	16.48	Per cubic metre	522.50	8610.80	Rupees Eight Thousand Six Hundred Ten and Paise Eighty Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. P.C.C. nominal mix 1:5:10 (one cement: five Sand : ten graded, crushed stone aggregate)(40mm aggregates) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	30.89	Per cubic metre	4845.80	149686.76	Rupees One Lakh Forty Nine Thousand Six Hundred Eighty Six and Paise Seventy Six Only
3	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing walls, return walls with 100mm dia PVC Pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204, 3.7.including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	8.00	Each	279.40	2235.20	Rupees Two Thousand Two Hundred Thirty Five and Paise Twenty Only
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 (Granular material) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	5.13	Per cubic metre	1512.10	7757.07	Rupees Seven Thousand Seven Hundred Fifty Seven and Paise Seven Only
Total in figure :					168289.84	Rupees One Lakh Sixty Eight Thousand Two Hundred Eighty Four Only
Total in Words :		Rupees One Lakh Sixty Eight Thousand Two Hundred Eighty Nine and Paise Eighty Four Only				

Executive Engineer,
Mandi Division No.I,
HP.PWD. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 106882.31
Earnest Money Rs:- 2100.00
Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.

Name of Work:- Restoration of rain damages on Ghatasani Jhatingri Tikken Barot road km. 0/00 to 25/00. (Sub Head:- Construction of Retaining wall at RD 1/900 to 1/903 & 9/990 to 9/994.80)

Contract No. :

Name of the Bidder/Bidding Firm/Company :

PRICE SCHEDULE

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	Total Amount with all taxes excluding GST in words.
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50.00 metres, dressing of sides and bottoms and back filling in trenches with excavated suitable materials including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	9.28	Per cubic metre	522.50	Rupees Four Thousand Eight Hundred Forty Eight and Paise Eighty Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. P.C.C. nominal mix 1:5:10 (one cement: five Sand : ten graded crushed stone aggregate)/(40mm aggregates) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	18.79	Per cubic metre	4946.10	Rupees Ninety Two Thousand Nine Hundred Thirty Seven and Paise Twenty Two Only
3	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing walls, return walls with 100mm dia PVC Pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204, 3.7.including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	8.00	Each	282.70	Rupees Two Thousand Two Hundred Sixty One and Paise Sixty Only
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 (Granular material) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	4.52	Per cubic metre	1512.10	Rupees Six Thousand Eight Hundred Thirty Four and Paise Sixty Nine Only
Total in figure :					106882.31 Rupees One Lakh Six Thousand Eight Hundred Eighty Two and Paise Thirty One Only
Total in Words :					Rupees One Lakh Six Thousand Eight Hundred Eighty Two and Paise Thirty One Only

Executive Engineer,
Mandi Division No.1,
HP.PWD. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 203742.67
 Earnest Money Rs:- 4100.00
 Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.						
Name of Work:- Restoration of rain Damages on Ghatasani Jhatingri Tikken Barot road km 0/00 to 25/00 (Sub Head:- Construction of wire crated retaining wall at RD 10/855 to 10/871.80).						
Contract No. :						
Name of the Bidder/Bidding Firm/Company :						
PRICE SCHEDULE						
Sr. No	Description of items.	Quantity	Units	Estimate Rate Rs. P.	Total Amount with all taxes excluding GST in words.	Total Amount with all taxes excluding GST in words.
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50.00 metres, dressing of sides and bottoms and back filling in trenches with excavated suitable materials including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	24.19	Per cubic metre	522.50	12639.28	Rupees Twelve Thousand Six Hundred Thirty Nine and Paise Twenty Eight Only
2	Providing and laying boulder apron laid in wire crates with 4mm dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm mesh (woven diagonally) including 10% extra for laps and joints laid with stones boulder weighing not less than 25Kg. Each as per drawing and technical specification clause 1301 including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	72.58	Per cubic metre	2318.00	168240.44	Rupees One Lakh Sixty Eight Thousand Two Hundred Forty and Paise Forty Four Only
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 (Granular material) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	15.12	Per cubic metre	1512.10	22862.95	Rupees Twenty Two Thousand Eight Hundred Sixty Two and Paise Ninety Five Only
Total in figure :					203742.67	Rupees Two Lakh Three Thousand Seven Hundred Forty Two and Paise Sixty Seven Only
Total in Words :		Rupees Two Lakh Three Thousand Seven Hundred Forty Two and Paise Sixty Seven Only				

Executive Engineer,
 Mandi Division No.I,
 HP.PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs. 106882.31
Earnest Money Rs. 2100.00
Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar. Name of Work:- Restoration of rain damages on Ghatasani Jhatangri Tikken Barot road km 0/00 25/00. (PDNA-2023) (Sub Head:- Construction of retaining wall at RD 8/930 to 8/945).						
Contract No. :						
Name of the Bidder/Bidding Firm/Company :						
PRICE SCHEDULE						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	Total Amount with all taxes excluding GST in Rs. P.	Total Amount with all taxes excluding GST in words.
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50.00 metres, dressing of sides and bottoms and back filling in trenches with excavated suitable materials including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	9.28	Per cubic metre	522.50	4848.80	Rupees Four Thousand Eight Hundred Forty Eight and Paise Eighty Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203, P.C.C. nominal mix 1:5:10 (one cement: five Sand : ten graded, crushed stone aggregate)(40mm aggregates) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	18.79	Per cubic metre	4946.10	92937.22	Rupees Ninety Two Thousand Nine Hundred Thirty Seven and Paise Twenty Two Only
3	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing walls, return walls with 100mm dia PVC Pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204, 3.7 including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	8.00	Each	282.70	2261.60	Rupees Two Thousand Two Hundred Sixty One and Paise Sixty Only
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 (Granular material) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	4.52	Per cubic metre	1512.10	6834.69	Rupees Six Thousand Eight Hundred Thirty Four and Paise Sixty Nine Only
Total in figure :					106882.31	Rupees One Lakh Six Thousand Eight Hundred Eighty Two and Paise Thirty One
Total in Words :		Rupees One Lakh Six Thousand Eight Hundred Eighty Two and Paise Thirty One Only				

Executive Engineer,
Mandi Division No.1,
HP.PWD. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 291636.99
 Earnest Money Rs:- 5800.00
 Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP, PWD, at Padhar.

Name of Work:- Restoration of rain damages on Barot to Mayot road km. 0/00 to 25/00. (PDNA-2023) (Sub Head:- Construction of Retaining wall at RD 5/427 to 5/440).

Contract No. :

Name of the Bidder/Bidding Firm/Company :

PRICE SCHEDULE

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	Total Amount with all taxes excluding GST in Rs. P.	Total Amount with all taxes excluding GST in words.
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of slumps and other deleterious materials and disposal upto a lead of 50.00 metres, dressing of sides and bottoms and back filling in trenches with excavated suitable materials including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	16.68	Per cubic metre	491.80	8203.22	Rupees Eight Thousand Two Hundred Three and Paise Twenty Two Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802.803, 1202 & 1203, P.C.C. nominal mix 1:5:10 (one cement: five Sand : ten graded, crushed stone aggregate)/(40mm aggregates) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	49.39	Per cubic metre	5363.20	264888.45	Rupees Two Lakh Sixty Four Thousand Eight Hundred Eighty Eight and Paise Forty Five Only
3	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing walls, return walls with 100mm dia PVC Pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204, 3.7 including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	18.00	Each	296.40	5335.20	Rupees Five Thousand Three Hundred Thirty Five and Paise Twenty Only
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 (Granular material) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	8.97	Per cubic metre	1472.70	13210.12	Rupees Thirteen Thousand Two Hundred Ten and Paise Twelve Only
Total in figure :					291636.99	Rupees Two Lakh Ninety One Thousand Six Hundred Thirty Six and Paise Ninety Nine Only
Total in Words :		Rupees Two Lakh Ninety One Thousand Six Hundred Thirty Six and Paise Ninety Nine Only				

Executive Engineer,
 Mandi Division No. I,
 HP, PWD, at Padhar.

[Signature]

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 179936.42
Earnest Money Rs:- 3600.00
Time one month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.						
Name of Work:- Restoration of rain damages on Tikken to Thaltukhod road 0/00 to 4/500. (Sub Head:- Construction of Retaining wall at RD 3/180 to 3/185).						
Contract No:-						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50.00 metres, dressing of sides and bottoms and back filling in trenches with excavated suitable materials including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	17.35	Per cubic metre	522.50	9065.38	Rupees Nine Thousand Sixty Five and Paise Thirty Eight Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. P.C.C. nominal mix 1:5:10 (1 cement: 5 Sand : 10 graded /crushed stone aggregate)(40mm aggregates) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	32.51	Per cubic metre	4935.10	160440.10	Rupees One Lakh Sixty Thousand Four Hundred Forty and Paise Ten Only
3	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing walls, return walls with 100mm dia PVC Pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204, 3.7.including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	8.00	Each	283.20	2265.60	Rupees Two Thousand Two Hundred Sixty Five and Paise Sixty Only
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 (Granular material) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	5.40	Per cubic metre	1512.10	8165.34	Rupees Eight Thousand One Hundred Sixty Five and Paise Thirty Four Only
Total in figure :					179936.42	Rupees One Lakh Seventy Nine Thousand Nine Hundred and Paise Forty Two Only
Total in Words :		Rupees One Lakh Seventy Nine Thousand Nine Hundred and Paise Forty Two Only				

Executive Engineer,
Mandi Division No.1,
HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost ₹ 213467.58
Earnest Money ₹ 4300.00
Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.
Name of Work:- Restoration of rain damages on Sihbudhani Kungri Kortang road 0/00 to 5/500. (PDNA -2023) (Sub Head:- Construction of wing wall before culvert & after at RD 2/016).

Contract No. :

Name of the Bidder/Bidding Firm/Company :

PRICE SCHEDULE						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	Total Amount with all taxes excluding GST in Rs. P.	Total Amount with all taxes excluding GST in words.
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50.00 metres, dressing of sides and bottoms and back filling in trenches with excavated suitable materials including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	17.46	Per cubic metre	553.00	9655.38	Rupees Nine Thousand Six Hundred Fifty Five and Paise Thirty Eight Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. P.C.C. nominal mix 1:5:10 (one cement: five Sand : ten graded, crushed stone aggregate)/(40mm aggregates) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	36.06	Per cubic metre	5041.00	181778.46	Rupees One Lakh Eighty One Thousand Seven Hundred Seventy Eight and Paise Forty Six Only
3	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing walls, return walls with 100mm dia PVC Pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204, 3.7.including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	10.00	Each	288.70	2887.00	Rupees Two Thousand Eight Hundred Eighty Seven Only
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 (Granular material) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	12.34	Per cubic metre	1551.60	19146.74	Rupees Nineteen Thousand One Hundred Forty Six and Paise Seventy Four Only
Total in figure :					213467.58	Rupees Two Lakh Thirteen Thousand Four Hundred Sixty Six and Paise Fifty Eight Only
Total in Words :		Rupees Two Lakh Thirteen Thousand Four Hundred Sixty Six and Paise Fifty Eight Only				

Executive Engineer,
Mandi Division No.1,
HP.PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 394129.96
Earnest Money Rs:- 7900.00
Time one month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.
Name of Work:- Restoration of rain damages on Dharmehar Tarswan Dragar Gadghaon road km. 0/00 to 5/150. (PDNA -2023).(Sub Head:-Construction of 900 dia HPC at RD 2/510 alongwith wing wall)
Contract No:-
Bidder Name :

SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50.00 metres, dressing of sides and bottoms and back filling in trenches with excavated suitable materials including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	60.53	Per cubic metre	522.50	31626.93	Rupees Thirty One Thousand Six Hundred Twenty Six and Paise Ninety Two Only
2	Providing concrete for plain / reinforced concrete in open foundation complete as per drawing and technical specifications clauses 802, 803, 1202, 1203. Nominal mix 1:6:12 (40mm aggregate) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	1.21	Per cubic metre	5364.92	6491.55	Rupees Six Thousand Four Hundred Ninety One and Paise Fifty Five Only
3	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 & 1203. P.C.C. nominal mix 1:4:8 (one cement: four Sand : Eight graded, crushed stone aggregate)/(40mm aggregates) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	51.99	Per cubic metre	4772.00	248096.28	Rupees Two Lakh Forty Eight Thousand Ninety Six and Paise Twenty Eight Only
4	Providing concrete for plain / reinforced concrete in open foundation complete as per drawing and technical specifications clauses 802, 803, 1202, 1203. Nominal mix 1:3:6 (40mm aggregate) M-10 including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	11.52	Per cubic metre	5465.00	62956.80	Rupees Sixty Two Thousand Nine Hundred Fifty Six and Paise Eighty Only
5	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1106. 900mm dia including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	7.50	Per cubic metre	4143.40	31075.50	Rupees Thirty One Thousand Seventy Five and Paise Fifty Only
6	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing walls, return walls with 100mm dia PVC Pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204, 3.7. including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	18.00	Per cubic metre	283.20	5097.60	Rupees Five Thousand Ninety Seven and Paise Sixty Only

7	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 (Granular material) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	5.81	Per cubic metre	1512.10	8785.30	Rupees Seven Hundred and Paise Thirty Only	Thousand Eight Hundred and Paise Thirty Only
Total in figure :					394129.96	Rupees Three Lakh Ninety Four Hundred and Paise Sixty Only	Three Lakh Ninety Thousand One Hundred and Paise Sixty Only
Total in Words :					Rupees Three Lakh Ninety Four Thousand One Hundred and Paise Ninety Six Only		Twenty Nine

Executive Engineer,
Mandi Division No.1,
HP. PWD. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 467389.00
Earnest Money Rs:- 9300.00
Time One Month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.

Name of Work:- Restoration of rain damages on Thaltukhod Marh road at Km 0/00 to 5/00.(PDNA-2023). (Sub Head:- Construction of Retaining Wall at RD 0/039 to 0/048).

Contract No:-

Bidder Name :

SCHEDULE OF WORKS

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	42.48	Per cubic metre	553.20	23500.00	Rupees Twenty Three Thousand Five Hundred Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. Plain cement concrete nominal mix 1:5:10 (one cement : five sand : ten graded,crushed stone aggregate 40mm (forty millimetre) nominal size) curing complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	84.13	Per cubic metre	4989.30	419750.00	Rupees Four Lakh Nineteen Thousand Seven Hundred Fifty Only
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm dia.(one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	20.00	Each	285.30	5706.00	Rupees Five Thousand Seven Hundred Six Only
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 Granular material complete including carriage of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-Charge.	11.88	Per cubic metre	1551.60	18433.00	Rupees Eighteen Thousand Four Hundred Thirty Three Only
Total in figure :					467389.00	Rupees Four Lakh Sixty Seven Thousand Eighty Nine Only
Total in Words :						Rupees Four Lakh Sixty Seven Thousand Three Hundred Eighty Nine Only

Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar.

ga

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 316542.28
 Earnest Money Rs:- 6300.00
 Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.						
Name of work:- Restoration of Rain damages on Balh to Ropa road Km 0/00 to 5/100 (PDNA-2023) . (Sub Head:-Construction of Retaining wall in Km 4/420 to 4/426).						
Contract No. :						
Name of the Bidder/Bidding Firm/Company :						
PRICE SCHEDULE						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	Total Amount with all taxes excluding GST in Rs. P.	Total Amount with all taxes excluding GST in words.
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50.00 metres, dressing of sides and bottoms and back filling in trenches with excavated suitable materials including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	24.06	Per cubic metre	553.00	13305.18	Rupees Thirteen Thousand Three Hundred Five and Paise Eighteen Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. P.C.C. nominal mix 1:5:10 (one cement: five Sand : ten graded ,crushed stone aggregate)(40mm aggregates) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	57.38	Per cubic metre	5041.00	289252.58	Rupees Two Lakh Eighty Nine Thousand Two Hundred Fifty Two and Paise Fifty Eight Only
3	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing walls, return walls with 100mm dia PVC Pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204, 3.7,including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	10.00	Each	281.30	2813.00	Rupees Two Thousand Eight Hundred Thirteen Only
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 (Granular material) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	7.20	Per cubic metre	1551.60	11171.52	Rupees Eleven Thousand One Hundred Seventy One and Paise Fifty Two Only
Total in figure :					316542.28	Rupees Three Lakh Sixteen Thousand Five Hundred Forty Two and Paise Twenty Eight Only
Total in Words :		Rupees Three Lakh Sixteen Thousand Five Hundred Forty Two and Paise Twenty Eight Only				

Executive Engineer
 Mandi Division No.1
 HP.PWD. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 423906.10
Earnest Money Rs:- 8500.00
Time one month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.						
Name of Work:- Restoration of Rain Damages on Ropa Sarni road Km 0/00 to 3/720. (PDNA-2023) (Sub Head:- Construction of Retaining wall at RD 0/085 to 0/093).						
Contract No:-						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50.00 metres, dressing of sides and bottoms and back filling in trenches with excavated suitable materials including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	32.08	Per cubic metre	553.00	17740.24	Rupees Seventeen Thousand Seven Hundred Forty and Paise Twenty Four Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. P.C.C. nominal mix 1:5:10 (one cement: five Sand : ten graded, crushed stone aggregate)(40mm aggregates) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	76.50	Per cubic metre	5041.00	385636.50	Rupees Three Lakh Eighty Five Thousand Six Hundred Thirty Six and Paise Fifty Only
3	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing walls, return walls with 100mm dia PVC Pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204, 3.7 including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	20.00	Each	281.70	5634.00	Rupees Five Thousand Six Hundred Thirty Four Only
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 (Granular material) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	9.60	Per cubic metre	1551.60	14895.36	Rupees Fourteen Thousand Eight Hundred Ninety Five and Paise Thirty Six Only
Total in figure :					423906.10	Rupees Four Lakh Twenty Three Thousand Nine Hundred Six and Paise Ten Only
Total in Words :		Rupees Four Lakh Twenty Three Thousand Nine Hundred Six and Paise Ten Only				

Executive Engineer,
Mandi Division No.1,
HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 355239.14
Earnest Money Rs:- 7100.00
Time one month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 H.P.W.D. at Padhar.

Name of work :- Restoration of rain damages on Ropa to Sarni road km. 0/00 to 3/720 (PDNA -2023), (Sub Head:- Construction of Retaining wall at RD 2/120 to 2/130)

Contract No:-

Bidder Name :-

SCHEDULE OF WORKS

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50.00 metres, dressing of sides and bottoms and back filling in trenches with excavated suitable materials including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	34.70	Per cubic metre	522.50	18130.75	Rupees Eighteen Thousand One Hundred Thirty and Paise Seventy Five Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. P.C.C. nominal mix 1:5:10 (1 cement: 5 Sand : 10 graded, crushed stone aggregate)(40mm aggregates) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	65.03	Per cubic metre	4863.80	316292.91	Rupees Three Lakh Sixteen Thousand Two Hundred Ninety Two and Paise Ninety One Only
3	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing walls, return walls with 100mm dia PVC Pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204, 3.7 including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	16.00	Each	280.30	4484.80	Rupees Four Thousand Four Hundred Eighty Four and Paise Eighty Only
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 (Granular material) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	10.80	Per cubic metre	1512.10	16330.68	Rupees Sixteen Thousand Three Hundred Thirty and Paise Sixty Eight Only
Total in figure :					355239.14	Rupees Three Lakh Fifty Five Thousand Two Hundred Thirty Nine and Paise Fourteen Only
Total in Words :						Rupees Three Lakh Fifty Five Thousand Two Hundred Thirty Nine and Paise Fourteen Only

Executive Engineer
Mandi Division No.1
H.P.W.D. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 371634.69
Earnest Money Rs:- 7400.00
Time one month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.						
Name of Work:- Restoration of Rain Damages on Ropa Sami road Km 0/00 to 3/720. (PDNA-2023) (Sub Head:- Construction of Retaining wall at RD 000 to 0/100).						
Contract No:-						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50.00 metres, dressing of sides and bottoms and back filling in trenches with excavated suitable materials including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	28.07	Per cubic metre	553.00	15522.71	Rupees Fifteen Thousand Five Hundred Twenty Two and Paise Seventy One Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. P.C.C. nominal mix 1:5:10 (one cement: five Sand : ten graded, crushed stone aggregate)(40mm aggregates) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	66.94	Per cubic metre	5041.00	337444.54	Rupees Three Lakh Thirty Seven Thousand Four Hundred Forty Four and Paise Fifty Four Only
3	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing walls, return walls with 100mm dia PVC Pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204, 3.7 including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	20.00	Each	281.70	5634.00	Rupees Five Thousand Six Hundred Thirty Four Only
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 (Granular material) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	8.40	Per cubic metre	1551.60	13033.44	Rupees Thirteen Thousand Thirty Three and Paise Forty Four Only
Total in figure :					371634.69	Rupees Three Lakh Seventy One Thousand Six Hundred Thirty Four and Paise Sixty Nine Only
Total in Words :					Rupees Three Lakh Seventy One Thousand Six Hundred Thirty Four and Paise Sixty Nine Only	

Executive Engineer,
Mandi Division No.I,
HP. PWD. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 413532.81
 Earnest Money Rs:- 6300.00
 Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.

Name of Work:- Restoration of rain damages on Ropa Kathog road km 0/00 to 5/00. (PDNA-2023). (Sub Head:- Construction of Retaining Wall at RD's 2/790 to 2/797 and 3/750 to 3/760).

Contract No. :

Name of the Bidder/Bidding Firm/Company :

PRICE SCHEDULE

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	Total Amount with all taxes excluding GST in Rs. P.	Total Amount with all taxes excluding GST in words.
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50.00 metres, dressing of sides and bottoms and back filling in trenches with excavated suitable materials including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	35.34	Per cubic metre	553.00	19543.02	Rupees Nineteen Thousand Five Hundred Forty Three and Paise Two Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. P.C.C. nominal mix 1:5:10 (one cement: five Sand : ten graded, crushed stone aggregate)(40mm aggregates) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	73.29	Per cubic metre	5041.00	369454.89	Rupees Three Lakh Sixty Nine Thousand Four Hundred Fifty Four and Paise Eighty Nine Only
3	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing walls, return walls with 100mm dia PVC Pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204, 3.7 including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	21.00	Each	281.70	5915.70	Rupees Five Thousand Nine Hundred Fifteen and Paise Seventy Only
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 (Granular material) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	12.00	Per cubic metre	1551.60	18619.20	Rupees Eighteen Thousand Six Hundred Nineteen and Paise Twenty Only
Total in figure :					413532.81	Rupees Four Lakh Thirteen Thousand Five Hundred Thirty Two and Paise Eighty One
Total in Words :		Rupees Four Lakh Thirteen Thousand Five Hundred Thirty Two and Paise Eighty One Only				

Executive Engineer,
 Mandi Division No. I,
 HP.PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 368269.81
 Earnest Money Rs:- 7400.00
 Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.
Name of Work:- Restoration of rain damages on Ropa Kathog road km 0/00 to 5/00. (PDNA-2023). (Sub Head:- Construction of Retaining Wall at RD's 3/780 to 3/790).

Contract No. :

Name of the Bidder/Bidding Firm/Company :

PRICE SCHEDULE

Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	Total Amount with all taxes excluding GST in words.	Total Amount with all taxes excluding GST in
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50.00 metres, dressing of sides and bottoms and back filling in trenches with excavated suitable materials including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	34.70	Per cubic metre	553.00	Rupees Nineteen Thousand One Hundred Eighty Nine and Paise Ten Only	19189.10
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. P.C.C. nominal mix 1:5:10 (one cement: five Sand : ten graded, crushed stone aggregate)(40mm aggregates) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	65.03	Per cubic metre	5041.00	Rupees Three Lakh Twenty Seven Thousand Eight Hundred Sixteen and Paise Twenty Three Only	327816.23
3	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing walls, return walls with 100mm dia PVC Pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204, 3.7.including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	16.00	Each	281.70	Rupees Four Thousand Five Hundred Seven and Paise Twenty Only	4507.20
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 (Granular material) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	10.80	Per cubic metre	1551.60	Rupees Sixteen Thousand Seven Hundred Fifty Seven and Paise Twenty Eight Only	16757.28
Total in figure :					Rupees Three Lakh Sixty Eight Thousand Two Hundred Sixty Nine and Paise Eighty One Only	368269.81
Total in Words :		Rupees Three Lakh Sixty Eight Thousand Two Hundred Sixty Nine and Paise Eighty One				

Executive Engineer,
 Mandi Division No.I,
 HP.PWD. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 498583.90
Earnest Money Rs:- 10000.00
Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.						
Name of Work:- Restoration of rain damages on Balh to Kathog road km. 0/00 to 5/00. (PDNA -2023). (Sub Head:- Construction of Retaining wall at R.D. 1/105 to 1/120 and 1/450 to 1/460).						
Contract No. :						
Name of the Bidder/Bidding Firm/Company :						
PRICE SCHEDULE						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	Total Amount with all taxes excluding GST in Rs. P.	Total Amount with all taxes excluding GST in words.
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50.00 metres, dressing of sides and bottoms and back filling in trenches with excavated suitable materials including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	43.00	Per cubic metre	553.00	23779.00	Rupees Twenty Three Thousand Seven Hundred Seventy Nine Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. P.C.C. nominal mix 1:5:10 (one cement: five Sand : ten graded, crushed stone aggregate)(40mm aggregates) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	87.9	Per cubic metre	5041.00	443103.90	Rupees Four Lakh Forty Three Thousand One Hundred Three and Paise Ninety Only
3	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing walls, return walls with 100mm dia PVC Pipe extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204, 3.7 including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	30.00	Each	280.90	8427.00	Rupees Eight Thousand Four Hundred Twenty Seven Only
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 (Granular material) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	15.00	Per cubic metre	1551.60	23274.00	Rupees Twenty Three Thousand Two Hundred Seventy Four Only
Total in figure :					498583.90	Rupees Four Lakh Ninety Eight Thousand Five Hundred Eighty Three and Paise Ninety Only
Total in Words :		Rupees Four Lakh Ninety Eight Thousand Five Hundred Eighty Three and Paise Ninety Only				

Executive Engineer,
Mandi Division No. I,
HP.PWD. at Padhar.

Ga...

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 398665.12

Earnest Money Rs:- 8000.00

Time one month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.						
Name of Work:- Restoration of Rain Damages on Tikker Sami road Km 0/00 to 3/720. (PDNA-2023) (Sub Head:- Construction of Retaining wall at RD 0/900 to 0/920).						
Contract No:-						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50.00 metres, dressing of sides and bottoms and back filling in trenches with excavated suitable materials including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	34.00	Per cubic metre	553.00	18802.00	Rupees Eighteen Thousand Eight Hundred Two Only
2	Providing and laying concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 & 1203. P.C.C. nominal mix 1:5:10 (one cement: five Sand : ten graded ,crushed stone aggregate)(40mm aggregates) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	70.32	Per cubic metre	5041.00	354483.12	Rupees Three Lakh Fifty Four Thousand Four Hundred Eighty Three and Paise Twelve Only
3	Providing weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing walls, return walls with 100mm dia PVC Pipe, extending through the full width of structures with slope of 1(V):20 (H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204, 3.7.including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	24.00	Each	281.70	6760.80	Rupees Six Thousand Seven Hundred Sixty and Paise Eighty Only
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 (Granular material) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	12.00	Per cubic metre	1551.60	18619.20	Rupees Eighteen Thousand Six Hundred Nineteen and Paise Twenty Only
Total in figure :					398665.12	Rupees Three Lakh Ninety Eight Thousand Six Hundred Sixty Five and Paise Twelve Only
Total in Words :		Rupees Three Lakh Ninety Eight Thousand Six Hundred Sixty Five and Paise Twelve Only				

Executive Engineer,
Mandi Division No.1,
HP. PWD. at Padhar.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 57286.70
 Earnest Money Rs:- 1150.00
 Time one month

Tender Inviting Authority : Executive Engineer, Mandi Division No. I HP.PWD. at Padhar.						
Name of Work:- Restoration of rain damages on Ropa to Droon road km. 0/00 to 3/00. (PDNA -2023). (Sub Head:- Providing and Laying Kharanja Stone at R.D. 1/525 to 1/640).						
Contract No:-						
Bidder Name :						
SCHEDULE OF WORKS						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	TOTAL AMOUNT with all taxes excluding GST in Rs. P.	TOTAL AMOUNT with all taxes excluding GST in words.
1	Preparation of sub grade by dressing to camber (earth work for the cutting involved for sub grade to be paid for separately depending upon the classification of soil) complete as per H.P.P.W.D. Specifications.	379.50	Per cubic metre	1.84	698.28	Rupees Six Hundred Ninety Eight and Paise Twenty Eight Only
2	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour)	56.93	Per cubic metre	994.00	56588.42	Rupees Fifty Six Thousand Five Hundred Eighty Eight and Paise Forty Two Only
Total in figure :					57286.70	Rupees Fifty Seven Thousand Two Hundred Eighty Six and Paise Seventy Only
Total in Words :		Rupees Fifty Seven Thousand Two Hundred Eighty Six and Paise Seventy Only				

Executive Engineer,
 Mandi Division No.I,
 HP. PWD. at Padhar

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 466808.54
Earnest Money Rs:- 9300.00
Time:- One month

Tender Inviting Authority : Executive Engineer, Mandi Division No. 1 HP.PWD. at Padhar.						
Name of Work:- Restoration of rain damages on Ropa Droon road km. 0/00 to 5/00. (PDNA -2023 at Sr. No. 2244) R-Severely-Damaged-(30-70%). (Sub Head:- Construction of Wire Crated solid Causeway at R.D. 1/676 to 1/192.80).						
Contract No. :						
Name of the Bidder/Bidding Firm/Company :						
PRICE SCHEDULE						
Sr. No.	Description of items.	Quantity	Units	Estimate Rate Rs. P.	Total Amount with all taxes excluding GST in words.	Total Amount with all taxes excluding GST in words.
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50.00 metres, dressing of sides and bottoms and back filling in trenches with excavated suitable materials, including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	18.14	Per cubic metre	553.00	10031.42	Rupees Ten Thousand Thirty One and Paise Forty Two Only
2	Providing and laying boulder apron laid in wire crates with 4mm dia GI wire conforming to IS:280 and IS:4826 in 100mm x 100mm mesh (woven diagonally) including 10% extra for laps and joints laid with stones boulder weighing not less than 25Kg. Each as per drawing and technical specification clause 1301 including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	48.38	Per cubic metre	2318.00	112144.84	Rupees One Lakh Twelve Thousand One Hundred Forty Four and Paise Eighty Four Only
3	Providing and laying reinforced cement concrete pipe NP2 for culvert on 1st class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation protection work back filling concrete and masonry work in head walls and parapets clause 1106 including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	15.00	Per running metre	3889.50	58342.50	Rupees Fifty Eight Thousand Three Hundred Forty Two and Paise Fifty Only
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 (Granular material) including carriage of material with in all leads and lifts and other incidental complete as per direction of Engineer-in-Charge.	78.62	Per cubic metre	1551.60	121986.79	Rupees One Lakh Twenty One Thousand Nine Hundred Eighty Six and Paise Seventy Nine Only
5	Providing and Laying reinforced cement concrete in substructure complete as per drawing and technical specifications 802.804, 805, 804, 806, 807, 1202 & 1204. Plain cement concrete nominal mix 1:2:4 (one cement: two sand: four graded, crushed stone aggregate 20mm (twenty octroi, royalty, malkana, toll tax, sale tax or other taxes imposed by the Government, but excluding GST & including entire carriage of material with in all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	25.20	Per cubic metre	6519.96	164302.99	Rupees One Lakh Sixty Four Thousand Three Hundred Two and Paise Ninety Nine Only
Total in figure :					466808.54	Rupees Four Lakh Sixty Six Thousand Eight Hundred Eight and Paise Fifty Four Only
Total in Words :		Rupees Four Lakh Sixty Six Thousand Eight Hundred Eight and Paise Fifty Four Only				

Executive Engineer,
Mandi Division No.1,
HP.PWD. at Padhar