



Office of
Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur Himachal Pradesh
Works Department Jaisinghpur 176095 Phone No. 01894-228030
Email ee-jaipwd-hp@gov.in

No.PWD/JSPR/CB/Tenders/2026-27-

8096-8103

Dated:- 01/10/2026

To,

The Chief Engineer (KZ),
Himachal Pradesh, PWD,
Dharamshala (HP).

Subject:- Publication of Tender Notice on departmental website.

Sir,

Enclosed please find herewith tender notice for publication of the same on departmental website as per Notification issued by the worthy Principal Secretary (PW) to the Govt. of HP letter No. PBW-(B) A-(3) 1/2024 dated Shimla-2 dated 03.01.2025 and instructions issued by the worthy E-in-C, HPPWD Shimla letter No. PWD/ ICT Wing/ Website dated 22.05.2026.

It is certified that the works for which tenders invited are of urgent nature and in public interest.

DA/ As above.


Executive Engineer,
Jaisinghpur Division,
HPPWD Jaisinghpur

Copy forwarded to the following for information and necessary please:-

1. The Superintending Engineer, 5th Circle. HPPWD, Palampur.
- 2-4. All the Assistant Engineers working under this Division.
- 5-6. The Drawings Branch and Accounts Branch in this office.
7. Notice Board.
8. N.I.T. Register


Executive Engineer
Jaisinghpur Division,
HP.PWD., Jaisinghpur.



"NOTICE INVITING TENDERS"

Sealed percentage rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, HP.PWD., Division Jaisinghpur on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **09.10.2026 up to 11:00 A.M.** and the same shall be opened on the same day at **11:30 A.M.** in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **08.10.2026 up to 4:00 PM** and the application for issue of tender form shall be received on or before **08.10.2026 up to 1:00 PM**. The applications for issue of tender forms should accompanied with enlistment letter or renewal letter and the Earnest Money in the shape of National Saving Certificates / Saving Account of the Post Office / Time Deposit account / FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP.PWD., Division Jaisinghpur.

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for **75 days**:-

Sr. No.	Name of Work	Estimated Cost (Rs.)	EMD	Time limit	Cost of tender form
1	Preparation of DPR and CBR Test for various roads under HPPWD Sub-Division Jaisinghpur Tehsil Jaisinghpur Distt. Kangra (H.P). Construction of Link road to village Dandel km 0/00 to 3/500 (Portion 0/00 to 1/500)	90000/-	2000/-	Two Month	350/-
2	R/O Bijapur to Netru road Km 0/00 to 1/800 (SH:- C/O R/wall at Km 0/435 to 0/450 and 0/660 to 0/675 to protect exist CC pavement) Deposit-	168246/-	3400/-	Two Month	350/-
3	Restoration of rain damages on various roads under Sub Division panchrukhi Section Jalag(SH:-Painting of boards and writing letter Kms stone etc)	84880/-	2000/-	Two Month	350/-
4	Restoration of rain damages on Keru Kelan to Kotlu road Km 0/00 to 1/700 (SH:- C/O R/wall at RD 1/445 to 1/467) Deposit	411609/-	8300/-	Two Month	350/-
5	Preparation of DPR and CBR Test for various roads under HPPWD Sub Division Jaisinghpur Tehsil Jaisinghpur Distt. Kangra (H.P). Construction of Link Road From Kohala to Lower Ganguhi Kms 0/00 to 2/500 (Portion 0/00 to 1/500)	90000/-	2000/-	Two Month	350/-


-----Continued P-2-----

8

-2-

Terms & Conditions:-

1. The contractors will have to produce a copy of enlistment / renewal of valid class at time of application / tender form.
2. The contractors will have to produce a copy of GST, EPF and PAN.
3. The contractors are directed to insert the rate / percentage both in figures and words.
4. The tenders forms will not be issued to those contractors who have not completed their previous works / commitments or whose performance is not found satisfactory.
5. The Executive Engineer reserves the right to reject / cancel any or all the tenders without assigning any reason.


Executive Engineer
Jaisinghpur Division
H.P. PWD., Jaisinghpur.
(On behalf of Governor of Himachal Pradesh)

①

Executive Engineer,
Jaisinghpur Division,
HP, PWD Jaisinghpur

2

Name of work :-R/O Bijapur to Netru road Km 0/00 to 1/800 (SH:- C/O R/wall at Km 0/435 to 0/450 and 0/660 to 0/675 to protect exist CC pavement) SDF/2026/1096						
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
			Time Limits			
			Estimated cost Rs.	168246.00		
			Earnest Money Rs.	3400.00		
					Two month	
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	21.60	210.00	Rupees Two Hundred Ten Only	Per Cubic Metre	4536.00
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	44.70	3400.00	Rupees Three Thousand Four Hundred Only	Per Cubic Metre	151980.00

SCHEDULE OF QUANTITY



3	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORDD technical specification section 700, 1200 including carriage of materials with in all leads, lifts and other incidentals. The rate is imposed by the Government but excluding GST	21.00	210.00	Rupess Two Hundred Ten Only	Per Running Metre	4410.00
4	Back filling with granular materials behind abutment, Retaining wall/Breast wall, Wing walls and the like complete as per drawings and MORDD technical specification section 1200, 1600 and as per direction and entire satisfaction of the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	9.15	800.00	Rupess Eight Hundred Only	Per cubic Metre	7320.00
Total						
Quoted Rate (in Figures) Percentage						
			Excess (+)		%	
			Less (-)		%	
			G.Total in Figures			
			G.Total in Words			

Executive Engineer,
Jaisinghpur Division,
HP/PWD Jaisinghpur

Name of work :-Restoration of rain damages on various roads under Sub-Division panchrukhi Section Jalag(SH:-									
S. N.	Description of Item	Quantity	Rate		Unit	Amount	Time Limits		
			In Figures	In Word			Estimated cost Rs.	Earnest Money Rs.	2000.00
1	Removing dry or oil bound distemper, water proofing cement paint and the like by repairs to scratches etc. complete and direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	68.04	8.20	Rupees Eight And Paise Twenty Only	Per square metre	558.00			
3	Painting two coats (excluding priming coat) on new steel and other metal surfaces with enamel paint of Asian/ Nerolac brushing to give an even shade including cleaning the surfaces of all dirt, dust and other foreign matters with enamel paint of approval shade as per specifications, approved drawing, design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	68.04	50.00	Rupees Fifty Only	Per square metre	3402.00			
4	Writing letters of figures on any surface with synthetic enamel paint (other than white) (stop, comas, border, hyphens and like not to be measured and paid separately) in Indian letter/figure complete and as per directions of Engineer - in-Charge including hauling /carriage of materials to various location through all modes of transportation with in all leads, lifts and other incidental The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	48800.00	1.65	Rupees One And Paise Sixty Five Only	Per letter per centimetre	80520.00			
Total						84480.00			
Quoted Rate (in Figures) Percentage		Excess (+)			%				
G.Total in Figures		Less (-)			%				
G.Total in Words									

Executive Engineer,
Jaisinghpur Division,
HP, PWD Jaisinghpur

3

(4)

Name of work :- Restoration of rain damages on Keru Kelan to Kollu road Km 0/00 to 1/700 (SH:- C/O R/wall at RD 1/445 to 1/467) Defect									
S. N.		Description of Item		Quantity	In Figures	Rate	In Word	Unit	Amount
							Time Limits	Estimated cost Rs.	Earliest Money Rs.
								Two month	411609.00
								8300.00	
1		Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiselling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deteriorous materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST		51.70	200.00	Rupees Two Hundred Only	Per Cubic Metre	10340.00	
2		Providing and laying in position cement concrete 1:4:8 (One cement isto four sand isto eight graded broken/crushed stone aggregate 40mm (Forty millimetres) nominal size mechanically mixed and vibrated curing complete excluding the cost of centering and shuttering in foundation and plinth including carriage of material within all leads, lifts and other incidentals as per approved drawing, design, specifications and as directed by the Engineer-In-Charge. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST		102.74	3650.00	Rupees Three Thousand Six Hundred Fifty Only	Per Cubic Metre	375001.00	
SCHEDULE OF QUANTITY									

SCHEDULE OF QUANTITY



3	Construction of embankment with approved materials obtained from borrow pits any lift transporting to site to spreading, grading to required slope and compacting to meet the requirement of table 300.1 and 300.2 as per MORD technical specification clause 301.5 and as per direction of Engineer - in-Charge including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	8.14	200.00	Rupess Two Hundred Only	Per Cubic Metre	1628.00
4	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700, 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	44.00	200.00	Rupess Two Hundred Only	Per Running Metre	8800.00
5	Back filling with granular materials behind abutment, Retaining wall/Breast wall, Wing walls and the like complete as per drawings and MORD technical specification section 1200, 1600 and as per direction and entire satisfaction of the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	19.80	800.00	Rupess Eight Hundred Only	Per cubic Metre	15840.00
Total						
Quoted Rate (in Figures) Percentage		Excess (+)			%	411609.00
G.Total in Figures		Less (-)			%	
G.Total in Words						

Executive Engineer,
Jaisinghpur Division,
HP, PWD Jaisinghpur

5

Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur