

HIMACHAL PRADESH
PUBLIC WORK DEPARTMENT

No. PW/DT/TA/ NIT /2026-27-

5599

Dated:- 8-10-2026

To,


The Chief Engineer (KZ)
HP PWD Dharmshala HP
e-mail:-hp-kan@nic.in

Subject: _

Publication of Tender Notice .


Enclosed please find herewith Tender Notice of works as given in the Notice inviting Tenders alongwith schedule of quantities for uploading on departmental website as per directions received through e-mail dated 22.05.2026 of worthy Engineer-in-Chief, HP.PWD Nigam Vihar Shimla It is certified that the work mentioned in the Notice inviting tenders are urgent in nature and in Public interest.

Encls:- 10 Nos copy of Schedule of quantity.


Executive Engineer
Tanda Division HP PWD
at Nagrota Bagwan

CERTIFICATE

Certified that the tenders of works, called vide this office letter No. PW-DT-NIT-2026-27- 5600 -14 Dated:- 8-10-2026 are urgent nature.


Executive Engineer
Tanda Division HP PWD
at Nagrota Bagwan

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Sealed Percentage rate tender on form No. 6 & 8 are hereby invited by the **Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan** on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HP PWD (B & R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **22.10.2026** up to **11:00 A.M.** And the same shall be opened on the same day at **04:00 P.M.** in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **21.10.2026** up to **4:00 P.M.** and the application for issue of tender form shall be received on **19.10.2026** up to **12:00 noon.** The applications for issue of tender forms accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates/Saving Account of the Post Office /Time Deposit account/FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan.

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 120 days.

Sr. No.	Name of work	Estimated Cost	Earnest Money	Time limit
1	Restoration of rain damages of Lecture Theatre Complex in Dr. R.P. Govt. Medical College at Tanda in Distt. Kangra HP Deposit Work (SH: Hiring of Haydralic Excavator for dismantling removal of concrete from site).	99000.00	2000.00	One Month
2	Repair of Boys Hostel at Dr. R.P.G.M.C. Tanda Distt. Kangra HP (SH: Painting and Distemperin in Various rooms).	98552.00	1971.00	Three Months
3	Construction of Trangari (Bridge) at Ustehar in gram Panchayat Ustehar in Distt. Kangra HP Deposit Work (SH: Construction of Trangari Bridge) SDP/2023/571	322766.00	6500.00	Two Months
4	Providing way road side Ammenities on Kharat Jandrah Aerla in Distt. Kangra HP (SH: Providing and erection of Rain shelter at Jandrah). DC Deposit	134068.00	2700.00	Two Month
5	Construction of link road Shamshanghat Machinder Mahadev in G.P. Mumta in District Kangra HP (SH: Construction of Retaining wall at Rd 0/138 to 0/141 (r/ side), 0/144.30 to 0/153.6 (L/side) & CC Pavement).	99882.00	2000.00	Two Month
6	Providing way road side Ammenities on Dehrain Gharan Kandi road in Distt. Kangra HP (SH: Providing and erection of Rain shelter at Danoa). D.C. Deposit	134234.00	2700.00	Two Month
7	Providing way road side Ammenities on Sakreh Damtehar road in Distt. Kangra HP (SH: Providing and erection of Rain shelter). D.C. Deposit	134200.00	2700.00	Two Month
8	Providing way road side Ammenities on Kerta Pandol Chowk Distt. Kangra HP (SH: Providing and erection of Rain shelter). D.C. Deposit	134203.00	2700.00	Two Month
9	Restoration of rain damages on NH 154 to Govt. Phirmay School Kaisthwari road km 0/00 to 1/500 in distt. Kangra HP (SH: Providing and laying cement concrete pavement in km 1/150 to 1/220) D.C Deposit work	169220.00	3400.00	Two Months
10	Annual Repair and maintence of steel truss foot bridge on Sera to Chhanwar road in Tehsil Nagrota Bagwan Distt. Kangra HP (SH: Providing and applying paint work of Bridge	57402.00	1150.00	One Months
11	Annual Repair and Maintance of Rest House at Dadh in Distt. Kangra HP (SH: Providing and Installaion Air Conditioner.Photo Frames. Almirah and Looking Mirror etc).	121351.00	2450.00	One Month
12	Repair of Type-III Colony Residential Quarters at Nagrota Bagwan in District Kangra HP Deposit Work (SH: Providing and fixing glass panes plaster work & paint work etc).	106988.00	2200.00	Two Month
13	Constrution of lik Road Shamshanghat Machinder Mahadev in G.P. Mumta in District Kangra HP (SH: Construction of Breast wall at Rd 0/120 to 0/127 (r/side) & C.C. pavement).	96463.00	2000.00	One Months
14	Protection of existing MMV Workshop Building Govt. I.T.I. at Sarotari in Distt. Kangra HP Deposit work (SH: Balance work of Wire crates work).	99026.00	2000.00	Two Month
15	Restoration of rain damages on Patiyalkar to kaled road km 0/00 to 3/500 in Distt. Kangra HP Under PDNA2025 (SH: Construction of U- shape drain & Breast wall in between km 3/450 to 3/478.(4349-1	194174.00	3900.00	Three Months
16	Restoration of rain damges on Chandni Chowk to Rin road km 0/00 to 2/200 in Distt. Kangra HP HP Under PDNA 2025 (SH: Construction of Toe wall & Providing and laying cement concrete pavement over Hime pipe 4355-1).	111564.00	2300.0	Two Month
17	Construciton of link road from Dhaloon road to Dhaloon Society km 0/00 to 0/800 in District Kangra HP (SH: providing and laying cement concrete pavem in km 0/000 to 0/10) Under Deposit	170381.00	3500.00	Two Month
18	Restoration of rain damages on link orad from sera to Chhanwar including bridge over Saroon Khad in G.P. Sera Thana in Distt. Kangra HP (SH: Providing and laying Cement Concrete pavement).	169026.00	3400.00	One Months

Terms & Conditions:-)

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor / firm have to produce the copy of latest enlistment and renewal enlisted in HPPWD.

3. If any of the date mentioned above happened to be Gazetted Holidays the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tenders without assigning any reason.
5. The Contractor will have to submit affidavit along with application for issue of tender form.
6. Next tender will be issued only after completion of previous works in hand.

HIMSUCHANA AVAM & JAN SAMPARK

Executive Engineer
H.P.P.W.D. Tanda Division
at Nagrota Bagwan
(On behalf of Governor of Himachal Pradesh)

No.PW/NBD/TA/Tender/NIT/2026-27- **5600-14**
Copy to the following for information and necessary action:-

Dated/ **8-10-2026**

1. The Chief Engineer (KZ), HPPWD, Dharamshala.
2. The Executive Engineer IT Cell Shimla HP PWD Shimla.
3. The Superintending Engineer, 5th Circle, HPPWD, Palampur.
4. The Deputy Commissioner, Kangra at Dharamshala.
5. All the S.E.s/E.E.s under North Zone.
6. The Sub-Divisional Officer(C) Nagrota Bagwan.
7. All the Assistant Engineer under this Division.
8. The Drawing /Accounts Branch in this office.
9. Notice Board.

Executive Engineer
H.P.P.W.D. Tanda Division
at Nagrota Bagwan

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 99000.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : ONE MONTH

NAME OF WORK :- Restoration of rain damages of Lecture Theatre Complex in Dr. R.P. Govt. Medical College at Tanda in Distt. Kangra (H.P.). DEPOSIT WORK
SUB-HEAD :- Hiring of Hydraulic Excavator for dismantling/removal of concrete from site.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Hiring of crawler mounted hydraulic excavator (Poclain-210) for dismantling/removal of concrete from site complete and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	33.00 Hours	3000.00	Rupess Three thousand and paise Nil only.	Per hour	99000.00
TOTAL :-						99000.00

Quoted rates percentage in figure

Quoted rates percentage in words

Executive Engineer,
H.P.P.W.D., Division,
Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

NAME OF WORK :-

Repair of Boys Hostel at Dr.R.P.G.M.C. Tanda Distt. Kangra H.P.

UB-HEAD :-

Painting and Distemping in various rooms.

No.

Description of items

ESTIMATED COST:-
EARNEST MONEY :- ₹ 98552.28
TIME LIMIT :- THREE MONTHS

1	2	Quantity	Rate		Unit	Amount
			In fig	In words		
1	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour, complete and as per direction of Engineer- Incharge, including carriage of materials within all leads, lifts and other incidentals.	812.63 Square metres	82.00	Rupees Eighty two and paise Nil only	Per Square metre	66635.66
2	Providing and applying white cement based putty of average thickness 1 mm (One millimetres), of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth lifts and other incidentals.	234.79 Square metres	58.00	Rupees Fifty Eight and paise Nil only	Per Square metre	13617.82
	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.75 ltr/10 sqm of approved brand and manufacture, complete and as per direction of Engineer- Incharge, including carriage of materials within all leads, lifts and other incidentals.	215.28 Square metres	85.00	Rupees Eighty five and paise Nil only	Per Square metre	18298.80
TOTAL :-						98552.28

ed rates percentage in figure
ed rates percentage in words

Executive Engineer,
H.P.P.W.D. Division,
Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 322766.00
EARNEST MONEY :- ₹ 6500.00
TIME LIMIT :- TWO MONTHS

NAME OF WORK:- Construction of Trangari (Bridge) at Ustehar in Gram Panchayat Ustehar in Distt Kangra (H.P) (Deposit Work)

SUB HEAD: - Construction of Trangari. ~~Bohdel~~ 508190831571

Sr. No.	Description	Quantity	Rate		Unit	Amount
			In fig.	in words		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government	3 11.25 Cubic meters	245.76	Rupees Two hundred forty five and seventy six only.	Per cubic metre	2765.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead, dressing of sides and bottom and backfilling in trenches with excavated suitable material complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	14.81 Cubic meters	262.71	Rupees Two hundred sixty two and paise seventy only. <i>one</i>	Per cubic metre	3891.00
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering. Plain cement concrete 1:3:6 (One Cement : Three coarse sand : Ten graded stone aggregate 20 mm (Twenty millimetres) nominal size complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	27.54 Cubic meters	3940.68	Rupees Three thousand nine hundred forty and paise sixty eight only.	Per cubic metre	108526.00
4	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (One Cement : Four coarse sand) : Eight graded stone aggregate 40 mm (Forty millimetres) nominal size complete and as per drawing and HP.PWD technical specifications, as directed by the Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	18.34 Cubic meters	3559.32	Rupees Three thousand five hundred fifty nine and paise thirty two only.	Per cubic metre	65278.00
5	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government	12.00 Running metres	271.19	Rupees Two hundred seventy one and paise nineteen only.	Per running metre	3254.00

JP

6	Providing and laying plain/ reinforced cement concrete in superstructure M-25 (M-twenty five) 1:1.5:3 (One cement : One and Half coarse sand): Three graded stone aggregate 20mm (Twenty millimetres nominal size including curing complete as per drawing and technical specifications Clauses 800, 1205.4 and 1205.5 complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government	6.77	Cubic metres	6249.79	Rupees Six thousand two hundred forty nine and paise seventy nine only.	Per cubic metre	42311.00
7	Supplying fitting and placing HYSD bar reinforcement for bridge work in super structure including cutting, bending, binding and placing in position complete in all respect including cost of binding wire upto any floor level complete in all respect including cost of binding wire upto any level complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification clause 1002, 1010 and 1202 including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government	1184.40	Kilogram	76.27	Rupees Seventy six and paise twenty seven only.	Per kilo gram	90334.00
8	Backfilling with granular material behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8, granular material complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government	10.08	Cubic metres	635.59	Rupees Six hundred thirty five and paise fifty nine only.	Per cubic metre	6407.00
TOTAL: -							322766.00

Quoted rates percentage in figure
Quoted rates percentage in words

Executive Engineer,
H.P.W.D Division,
Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

NAME OF WORK :- Providing way road side Amenities on Kharat Jandurah Aerla in Dist. Kangra (H.P.).

SUB-HEAD :- Providing and erection of Rain Shelter at Jandurah.

ESTIMATED COST:- ₹ 134068.00
EARNEST MONEY:- ₹ 2700.00
TIME LIMIT :- TWO MONTHS

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Excavation work by mechanical means (hydraulic excavator) manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within any lead complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	0.86 3	262.71 4	Rupess Two hundred sixty two and paise seventy one only.	Per cubic metre	226.00 7
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (One cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimetres nominal size) complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	0.22 Cubic metres	3389.83	Rupess Three thousand three hundred eighty nine and paise eighty three only.	Per cubic metre	746.00
3	Providing and laying cement concrete 1:2:4 (One cement : two sand : four graded crushed stone aggregate 20mm (Twenty millimetres) nominal size mechanically mixed and curing complete excluding cost of forms work in foundation and plinth complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	0.47 Cubic metres	5084.75	Rupess Five thousand eighty four and paise seventy five only.	Per cubic metre	2390.00
4	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in girders, frames, guard bar, ladder, railings, brackets, gates and similar works complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	474.87 Kilo gram	88.98	Rupess Eighty eight and paise ninety eight only.	Per kilo-gram	42254.00
5	Providing and fixing 0.60mm (Zero decimal Six Zero millimetres) thick pre-painted sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating to back coat of polyester of 5 (Five) microns over 5 (Five) microns primer coating including fixing with pre-painted iron J or L hooks, bolts and nuts 6mm (Six millimetres) diameters with pre-painted limpet and rubber washers complete with all accessories as required complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	16.80 Square metres	1101.69	Rupess One thousand one hundred one and paise sixty nine only.	Per square metre	18508.00
6	Providing and fixing ridges or hips 60cm (Sixty centimetres) over all with 0.60mm (Zero point Sixty millimetres) thick pre-painted sheet roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating to back coat of polyester of 5 (Five) microns over 5 (Five) microns primer coating including fixing with pre-painted iron J or L hooks, bolts and nuts 6mm (Six millimetres) diameters with pre-painted G.I. limpet and bitumen washers complete with all accessories as required complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	10.26 Running metres	713.56	Rupess Seven hundred thirteen and paise fifty six only.	Per running metre	7321.00

2

7	Providing and fixing M.S. B.P. sheet 1.66 mm to 2mm thick in eaves board/facia/soffits/ ceiling including cutting, Fixing and welding to seal roof members and applying a coat of red lead primer complete as per the instruction of Engineer-in-charge (Base members of steel work shall be measured & paid separately) complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	15.53	Square metres	1396.31	Rupees One thousand three hundred ninety six and paise thirty one only.	Per square metre	21685.00
8	Supplying, filling, spreading & leveling stone boulders of size range 5 cm to 20 cm (Five centimetre to twenty centimetre) nominal size in recharge pit, in the required thickness complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	1.58	Cubic metres	889.83	Rupees Eight hundred eighty nine and paise eighty three only.	Per cubic metre	1406.00
9	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering. Plain cement concrete 1:3:6 (One Cement : Three coarse sand : Ten graded stone aggregate 20 mm (Twenty millimetres) nominal size complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	1.58	Cubic metres	3940.68	Rupees Three thousand nine hundred forty and paise sixty eight only.	Per cubic metre	6226.00
10	Providing and laying of 25mm (Twenty five millimeter) thick Kota stone slab flooring 20mm (Twenty millimeter) average thick base of cement mortar of 1:4 (One cement:4 sand) laid over and jointed with grey cement slurry mixed with pigments of match the shade of the slab including rubbing and polishing complete (for all floor level) complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	10.530	Square metres	1030.25	Rupees One thousand thirty and paise twenty five only.	Per square metre	10849.00
11	Kota stone slabs 20 mm (Twenty millimetre) thick in risers of steps, skirting, dado and pillars laid on 12 mm (average) thick cement mortar 1:3 (One cement : Three coarse sand) and jointed with grey cement slurry mixed with pigment to match the shade of the slabs, including rubbing and polishing complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	3.94	Square metres	1084.70	Rupees One thousand eighty four and paise seventy only.	Per square metre	4274.00
12	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 litr/ 10 sqm (Zero point ninety liter / Ten square metre) over an under coat of primer applied @ 0.80 litr/ 10 sqm (Zero point eighty liter / Ten square metre) of approved brand and manufacture complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	15.53	Square metres	76.19	Rupees Seventy six and paise nineteen only.	Per Square metre	1183.00
13	Providing and fixing garden bench (Deluxe Model) 1.60metre (One point sixty metre) long having capacity of four person with ornamental legs and arms of cast iron with back and feet rectangular hollow section 65x25mm of 8 Numbers strips and 50x25mm of 5 numbers strips including welding and painting complete of approved brand and manufacture complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	2	Numbers	8500.00	Rupees Eight thousand five hundred and paise Nil only.	Each	17000.00
Total :-							134068.00

Quoted rates percentage in figure
Quoted rates percentage in words

Executive Engineer,
H.P.P.W.D., Division,
Tanda at Nagrota Bagwala

SCHEDULE OF QUANTITY

ESTIMATED COST:- Rs. 99882.00
EARNEST MONEY :- Rs. 2000.00
TIME LIMIT : TWO MONTHS

NAME OF WORK :- Construction of link road Shamsanghat Machinder Mahadev in G.P. Mumta in District Kangra, (H.P.).
SUB-HEAD :- Construction of Retaining wall at RD 0/141 to 0/144.40 (R/side), 0/153.60 to 0/163 (L/side) & CC Pavement.

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within a any lead as directed by the Engineer-in-charge, within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, excluding GST and any other taxes imposed by the Government.	10.02 Cubic metres	262.71	Rupees Two hundred sixty two and paise seventy one only.	Per cubic metre	2632.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level cement concrete 1:5:10 (One cement; five sand; ten graded broken/crushed stone aggregate 40mm (Forty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, excluding GST and any other taxes imposed by the Government.	27.33 Cubic metres	3347.46	Rupees Three thousand three hundred forty seven and paise forty six only.	Per cubic metre	91486.00
3	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, excluding GST and any other taxes imposed by the Government.	8.67 Running metre	271.19	Rupees Two hundred seventy one and paise nineteen only.	Per running metre	2351.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8, complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, excluding GST and any other taxes imposed by the Government.	2.57 Cubic metres	635.59	Rupees Six hundred thirty five and paise fifty nine only.	Per cubic metre	1633.00

5	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level cement concrete 1:2:4 (One cement; two sand; four graded broken/crushed stone aggregate 20mm (Twenty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, excluding GST and any other taxes imposed by the Government.	0.35	5084.75	Rupees Five thousand eighty four and paise seventy five only.	Per cubic metre	1780.00
TOTAL :-						
99882.00						
Quoted rates percentage in figures						
Quoted rates percentage in word						


 Executive Engineer,
 H.P.P. W.D. Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

NAME OF WORK :- Providing way road side Amenities on Dehrian Charan Kandi road in Dist. Kangra (H.P.).
SUB-HEAD :- Providing and erection of Rain Shelter at Damao.

ESTIMATED COST:- ₹ 134234.00
EARNEST MONEY:- ₹ 2700.00
TIME LIMIT :- ₹ 7200.00

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Excavation work by mechanical means (Hydraulic excavator) manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within any lead complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	0.85 Cubic metres	262.71	Rupees Two hundred sixty two and paise seventy one only.	Per cubic metre	223.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (One cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimetres nominal size) complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	0.24 Cubic metres	3389.83	Rupees Three thousand three hundred eighty nine and paise eighty three only.	Per cubic metre	814.00
3	Providing and laying cement concrete 1:2:4 (One cement: two sand: four graded crushed stone aggregate 20mm (Twenty millimetres) nominal size mechanically mixed and curing complete excluding cost of forms work in foundation and plinth complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	0.47 Cubic metres	5084.75	Rupees Five thousand eighty four and paise seventy five only.	Per cubic metre	2390.00
4	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	474.87 Kilo gram	88.98	Rupees Eighty eight and paise ninety eight only.	Per kilo-gram	42254.00
5	Providing and fixing 0.60mm (Zero decimal Six Zero millimetres) thick pre-painted sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating to back coat of polyester of 5 (Five) microns over 5 (Five) microns primer coating including fixing with pre-painted iron J or L hooks, bolts and nuts 6mm (Six millimetres) diameters with pre-painted limpet and rubber washers complete with all accessories as required complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	16.89 Square metres	1101.69	Rupees One thousand one hundred one and paise sixty nine only.	Per square metre	18608.00
6	Providing and fixing ridges or hips 60cm (Sixty centimetres) over all with 0.60mm (Zero point Sixty millimetres) thick pre-painted sheet roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating to back coat of polyester of 5 (Five) microns over 5 (Five) microns primer coating including fixing with pre-painted iron J or L hooks, bolts and nuts 6mm (Six millimetres) diameters with pre-painted G.I. limpet and bitumen washers complete with all accessories as required complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	10.26 Running metres	713.56	Rupees Seven hundred thirteen and paise fifty six only.	Per running metre	7321.00

Handwritten signature/initials.

7	Providing and fixing M.S. B.P. sheet 1.66 mm to 2mm thick in eaves board/facia/soffits/ ceiling including cutting, Fixing and welding to seal roof members and applying a coat of red lead primer complete as per the instruction of Engineer-in-charge (Base members of steel work shall be measured & paid separately) complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	15.53	1396.31	Rupees One thousand three hundred ninety six and paise thirty one only.	Per square metre	21685.00
8	Supplying, filling, spreading & leveling stone boulders of size range 5 cm to 20 cm (Five centimetre to twenty centimetre) nominal size in recharge pit, in the required thickness complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	1.58	889.83	Rupees Eight hundred eighty nine and paise eighty three only.	Per cubic metre	1406.00
9	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering. Plain cement concrete 1:3:6 (One Cement : Three coarse sand : Ten graded stone aggregate 20 mm (Twenty millimetres) nominal size complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	1.58	3940.68	Rupees Three thousand nine hundred forty and paise sixty eight only.	Per cubic metre	6226.00
10	Providing and laying of 25mm (Twenty five millimeter) thick kota stone slab flooring 20mm (Twenty millimeter) average thick base of cement mortar of 1:4 (One cement:4 sand) laid over and jointed with grey cement slurry mixed with pigments of match the shade of the slab including rubbing and polishing complete (for all floor level) complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	10.530	1030.25	Rupees One thousand thirty and paise twenty five only.	Per square metre	10849.00
11	Kota stone slabs 20 mm (Twenty millimeter) thick in risers of steps, skirting, dado and pillars laid on 12 mm (average) thick cement mortar 1:3 (One cement : Three coarse sand) and jointed with grey cement slurry mixed with pigment to match the shade of the slabs, including rubbing and polishing complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	3.94	1084.70	Rupees One thousand eighty four and paise seventy only.	Per square metre	4274.00
12	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 litr/ 10 sqm (Zero point ninety liter / Ten square metre) over an under coat of primer applied @ 0.80 litr/ 10 sqm (Zero point eighty liter / Ten square metre) of approved brand and manufacture complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	15.54	76.19	Rupees Seventy six and paise nineteen only.	Per square metre	1184.00
13	Providing and fixing garden bench (Deluxe Model) 1.60metre (One point sixty metre) long having capacity of four person with ornamental legs and arms of cast iron with back and feet rectangular hollow section 65x25mm of 8 Numbers strips and 50x25mm of 5 numbers strips including welding and painting complete of approved brand and manufacture complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	2	8500.00	Rupees Eight thousand five hundred and paise Nil only.	Each	17000.00
Total :-						134234.00

Quoted rates percentage in figure
Quoted rates percentage in words

Executive Engineer,
H.P.W.D., Division,
Tanda at Nagrota Bagwan

SCHEDULE OF QUANTITY

NAME OF WORK :- Providing way road side Amenities on Sakreh Damchar road in Dist. Kangra (H.P.).
SUB-HEAD :- Providing and erection of Rain Shelter.

ESTIMATED COST:- ₹ 134200.00
EARNEST MONEY:- ₹ 2700.00
TIME LIMIT :- TWO MONTHS

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within any lead complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	3 0.85 Cubic metres	262.71	Rupees Two hundred sixty two and paise seventy one only.	Per cubic metre	223.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (One cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimetres nominal size) complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	0.23 Cubic metres	3389.83	Rupees Three thousand three hundred eighty nine and paise eighty three only.	Per cubic metre	780.00
3	Providing and laying cement concrete 1:2:4 (One cement: two sand: four graded crushed stone aggregate 20mm (Twenty millimetres) nominal size mechanically mixed and curing complete excluding cost of forms work in foundation and plinth complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	0.47 Cubic metres	5084.75	Rupees Five thousand eighty four and paise seventy five only.	Per cubic metre	2390.00
4	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	474.87 Kilo gram	88.98	Rupees Eighty eight and paise ninety eight only.	Per kilo-gram	42254.00
5	Providing and fixing 0.60mm (Zero decimal Six Zero millimetres) thick prepainted sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating to back coat of polyester of 5 (Five) microns over 5 (Five) microns primer coating including fixing with all accessories as required complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	16.89 Square metres	1101.69	Rupees One thousand one hundred one and paise sixty nine only.	Per square metre	18608.00
6	Providing and fixing ridges or hips 60cm (Sixty centimetres) over all with 0.60mm (Zero point Sixty millimetres) thick prepainted sheet roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating to back coat of polyester of 5 (Five) microns over 5 (Five) microns primer coating including fixing with all accessories as required complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	10.26 Running metres	713.56	Rupees Seven hundred thirteen and paise fifty six only.	Per running metre	7321.00

JP

7	Providing and fixing M.S. B.P. sheet 1.66 mm to 2mm thick in eaves board/facia/soffits/ ceiling including cutting, fixing and welding to seal roof members and applying a coat of red lead primer complete as per the instruction of Engineer-in-charge (Base members of steel work shall be measured & paid separately) complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	15.53	Square metres	1396.31	Rupees One thousand three hundred ninety six and paise thirty one only.	Per square metre	21685.00
8	Supplying, filling, spreading & leveling stone boulders of size range 5 cm to 20 cm (Five centimetre to twenty centimetre) nominal size in recharge pit, in the required thickness complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	1.58	Cubic metres	889.83	Rupees Eight hundred eighty nine and paise eighty three only.	Per cubic metre	1406.00
9	Providing and laying in position concrete of specified grade including the cost of centering and shuttering. Plain cement concrete 1:3:6 (One Cement : Three coarse sand : Ten graded stone aggregate 20 mm (Twenty millimetres) nominal size complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	1.58	Cubic metres	3940.68	Rupees Three thousand nine hundred forty and paise sixty eight only.	Per cubic metre	6226.00
10	Providing and laying of 25mm (Twenty five millimeter) thick kota stone slab flooring 20mm (Twenty millimeter) average thick base of cement mortar of 1:4 (One cement:4 sand) laid over and jointed with gray cement slurry mixed with pigments of match the shade of the slab including rubbing and polishing complete (for all floor level) complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	10.530	Square metres	1030.25	Rupees One thousand thirty and paise twenty five only.	Per square metre	10849.00
11	Kota stone slabs 20 mm (Twenty millimetre) thick in risers of steps, skirting, dado and pillars laid on 12 mm (average) thick cement mortar 1:3 (One cement : Three coarse sand) and jointed with grey cement slurry mixed with pigment to match the shade of the slabs, including rubbing and polishing complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	3.94	Square metres	1084.70	Rupees One thousand eighty four and paise seventy only.	Per square metre	4274.00
12	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm (Zero point ninety liter / Ten square metre) over an under coat of primer applied @ 0.80 ltr/ 10 sqm (Zero point eighty liter / Ten square metre) of approved brand and manufacture complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	15.54	Square metres	76.19	Rupees Seventy six and paise nineteen only.	Per Square metre	1184.00
13	Providing and fixing garden bench (Deluxe Model) 1.60metre (One point sixty metre) long having capacity of four person with ornamental legs and arms of cast iron with back and feet rectangular hollow section 65x25mm of 8 Numbers strips and 50x25mm of 5 numbers strips including welding and painting complete of approved brand and manufacture complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	2	Numbers	8500.00	Rupees Eight thousand five hundred and paise Nil only.	Each	17000.00
Total :-							134200.00

Quoted rates percentage in figure
Quoted rates percentage in words

Executive Engineer,
H.P.W.D., Division,
Tanda at Nagrota Bagwala

SCHEDULE OF QUANTITY

NAME OF WORK :- Providing way road side Amenities on Kerta Pandol Chowk in Dist. Kangra (H.P.).
SUB-HEAD :- Providing and erection of Rain Shelter.

ESTIMATED COST :- ₹ 134203.00
EARNEST MONEY :- ₹ 2700.00
TIME LIMIT :- TWO MONTHS

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within any lead complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	3 0.86 Cubic metres	262.71	Rupees Two hundred sixty two and paise seventy one only.	Per cubic metre	226.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (One cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimetres nominal size) complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	0.23 Cubic metres	3389.83	Rupees Three thousand three hundred eighty nine and paise eighty three only.	Per cubic metre	780.00
3	Providing and laying cement concrete 1:2:4 (One cement: two sand: four graded crushed stone aggregate 20mm (Twenty millimetres) nominal size mechanically mixed and curing complete excluding cost of forms work in foundation and plinth complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	0.47 Cubic metres	5084.75	Rupees Five thousand eighty four and paise seventy five only.	Per cubic metre	2390.00
4	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in girders, frames, guard bar, ladder, railings, brackets, gates and similar works complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	474.87 Kilo gram	88.98	Rupees Eighty eight and paise ninety eight only.	Per kilo-gram	42254.00
5	Providing and fixing 0.60mm (Zero decimal Six Zero millimetres) thick pre-painted sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating to back coat of polyester of 5 (Five) microns over 5 (Five) microns primer coating including fixing with pre-painted iron J or L hooks, bolts and nuts 6mm (Six millimetres) diameters with pre-painted limpet and rubber washers complete with all accessories as required complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	16.89 Square metres	1101.69	Rupees One thousand one hundred one and paise sixty nine only.	Per square metre	18608.00
6	Providing and fixing ridges or hips 60cm (Sixty centimetres) over all with 0.60mm (Zero point Sixty millimetres) thick pre-painted sheet roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating to back coat of polyester of 5 (Five) microns over 5 (Five) microns primer coating including fixing with pre-painted iron J or L hooks, bolts and nuts 6mm (Six millimetres) diameters with pre-painted G.I. limpet and bitumen washers complete with all accessories as required complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	10.26 Running metres	713.56	Rupees Seven hundred thirteen and paise fifty six only.	Per running metre	7321.00

7	Providing and fixing M.S. B.P. sheet 1.66 mm to 2mm thick in eaves board/facia/soffits/ ceiling including cutting, Fixing and welding to seal roof members and applying a coat of red lead primer complete as per the instruction of Engineer-in-charge (Base members of steel work shall be measured & paid separately) complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	15.53	1396.31	Rupees One thousand three hundred ninety six and paise thirty one only.	Per square metre	21685.00
8	Supplying, filling, spreading & leveling stone boulders of size range 5 cm to 20 cm (Five centimetre to twenty centimetre) nominal size in recharge pit, in the required thickness complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	1.58	889.83	Rupees Eight hundred eighty nine and paise eighty three only.	Per cubic metre	1406.00
9	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering. Plain cement concrete 1:3:6 (One Cement : Three coarse sand : Ten graded stone aggregate 20 mm (Twenty millimetres) nominal size complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	1.58	3940.68	Rupees Three thousand nine hundred forty and paise sixty eight only.	Per cubic metre	6226.00
10	Providing and laying of 25mm (Twenty five millimeter) thick kota stone slab flooring 20mm (Twenty millimeter) average thick base of cement mortar of 1:4 (One cement:4 sand) laid over and jointed with gray cement slurry mixed with pigments of match the shade of the slab including rubbing and polishing complete (for all floor level) complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	10.530	1030.25	Rupees One thousand thirty and paise twenty five only.	Per square metre	10849.00
11	Kota stone slabs 20 mm (Twenty millimeter) thick in risers of steps, skirting, dado and pillars laid on 12 mm (average) thick cement mortar 1:3 (One cement : Three coarse sand) and jointed with grey cement slurry mixed with pigment to match the shade of the slabs, including rubbing and polishing complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	3.94	1084.70	Rupees One thousand eighty four and paise seventy only.	Per square metre	4274.00
12	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 litr/ 10 sqm (Zero point ninety liter / Ten square metre) over an under coat of primer applied @ 0.80 litr/ 10 sqm (Zero point eighty liter / Ten square metre) of approved brand and manufacture complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	15.54	76.19	Rupees Seventy six and paise nineteen only.	Per Square metre	1184.00
13	Providing and fixing garden bench (Deluxe Model) 1.60metre (One point sixty metre) long having capacity of four person with ornamental legs and arms of cast iron with back and feet rectangular hollow section 65x25mm of 8 Numbers strips and 50x25mm of 5 numbers strips including welding and painting complete of approved brand and manufacture complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	2	8500.00	Rupees Eight thousand five hundred and paise Nil only.	Each	17000.00
Total :-						134203.00

Quoted rates percentage in figure
Quoted rates percentage in words

Executive Engineer,
H.P.W.D. Division,
Tanda at Nagrota Bagwan

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 169220.00
EARNEST MONEY :- ₹ 3400.00
TIME LIMIT :- TWO MONTHS

NAME OF WORK:- Restoration of rain damages on NH-154 to Govt. Primary School Kaisthwari road Km 0/000 to 1/500 in Distt Kangra (HP).
SUB HEAD: - Providing and laying cement concrete pavement in Km 1/150 to 1/220

Sr. No.	Description	Quantity	Rate		Unit	Amount
			In fig.	in words		
1	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:2:4 (One Cement : Two coarse sand : Four graded stone aggregate 20mm (Twenty millimetres) nominal size complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	33.28 Cubic metres	5084.75	Rupess Five thousand eight four and paise seventy five only.	Per cubic metre	169220.00
TOTAL: -						169220.00

Quoted rates percentage in figure
Quoted rates percentage in words

Executive Engineer,
H.P.R.W.D Division,
Tanda at Nagrota Bagwan

Schedule of Quantity

ESTIMATED COST:- ₹ 57402.00
 EARNEST MONEY :- ₹ 1150.00
 TIME LIMIT : ONE MONTH

NAME OF WORK :- Annual repair and maintenance of steel truss foot bridge on Sera to Chhanwar road in Tehsil Nagrota Bagwan, Distt. Kangra (H.P.)
SUB HEAD :- Providing and applying paint work of Bridge.

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig.	In words		
1	Painting with synthetic enamel paint one or more coats on old work of approved brand and manufacture to give an even any shade and colour complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government	822.02 Square metre	69.83	Rupees Sixty nine and paise eighty three only.	Per square metre	57402.00
TOTAL :-						57402.00

Quoted rates percentage in figure
Quoted rates percentage in words


 Executive Engineer,
 H.P.P.W.D., Division,
 Tanda at Nagrota Bagwan

Schedule of Quantity

ESTIMATED COST :- ₹ 121351.00
EARNEST MONEY :- ₹ 2450.00
TIME LIMIT :- ONE MONTH

NAME OF WORK :- Annual Repair and Maintenance of Rest House at Dadh in Distt. Kangra (H.P.).

SUB-HEAD :- Providing and Installation Air Conditioner, Photo Frames, A/mirrah and Looking Mirror etc;

S. No.	Description of Items	Quantity	Rate		Unit	Amount
			In fig	In words		
1	Providing, supplying, installing, testing and commissioning of air cooled Hi-Wall Split Type Air Conditioner of 1.5 TR capacity, inverter type, 5-Star BEE rated, cooling only, complete with indoor unit (IDU), outdoor unit (ODU), wireless remote control, suitable for operation on 230 V, 1 Phase, 50 Hz AC supply, including standard accessories, mounting brackets/stand, necessary copper refrigerant piping with insulation, drain pipe, interconnecting cable, clamps, fasteners, sealing and all other necessary materials including necessary fitting complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	3 1 Numbers	53590.30	Rupees Fifty three thousand five hundred ninety and paise thirty only.	Each	53590.00
2	Providing and fixing photo frames of various size of public figures/National Leaders of India, comprising good quality digitally printed/photographic portrait mounted on suitable backing board, covered with clear glass/acrylic sheet and fitted in good quality decorative wooden/MDF frame, including backing, hanging hooks, screws, clips, cutting, assembling, fixing in position and all materials, labour, T&P and incidental charges including necessary fitting complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	16 Numbers	2240.40	Rupees Two thousand two hundred forty and paise forty only.	Each	35846.00
3	Providing and fixing premium quality wooden almirah of size 1980 × 900 × 450 mm, made of 19 mm thick BWP/marine plywood for sides, top, bottom, partitions and doors, 19 mm thick waterproof commercial plywood for shelves, with 6 mm thick plywood back, teak wood/moulded wooden beading, laminate finish on exposed surfaces and suitable balancing laminate on inner surfaces, including premium quality brass/SS handles, hinges, mortise/central locking arrangement, magnetic catchers, shelf supports and all necessary hardware including necessary fitting complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	1 Number	25239.60	Rupees Twenty five thousand two hundred thirty nine and paise sixty only.	Each	25240.00
4	Providing and fixing mirror of superior glass (of approved quality) and of required shape and size with plastic moulded frame of approved make and shade with 6 mm thick hard board backing : Rectangular shape 1800x600 mm including necessary fitting complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	2 Numbers	3337.30	Rupees Three thousand three hundred thirty seven and paise thirty only.	Each	6675.00
TOTAL :-						121351.00

*Quoted rates percentage in figure
Quoted rates percentage in words*

Executive Engineer,
H.P.W.D., Division,
Tanda at Nagrota Bagwala

SCHEDULE OF QUANTITY

NAME OF WORK :-
SUB-HEAD :-

Special repair of Type-III Colony Residential Quarters at Nagrota Bagwan in District Kangra, (H.P.). Deposit work.
Providing and fixing glass panes, plaster work & paint work etc.

ESTIMATED COST :- Rs. 106988.00
EARNEST MONEY :- Rs. 2200.00
TIME LIMIT : TWO MONTHS

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing & fixing glass panes with putty and glazing clips in steel doors, windows, clerestory windows, all complete with 4.00 mm (Four point zero millimetres) thick glass panes complete and as directed by the Engineer-In-charge. including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, excluding GST and any other taxes imposed by the Government.	4.80 Square metres	762.71	Rupees Seven hundred sixty two and paise seventy one only.	Per Square metre	3661.00
2	Repairs to plaster of thickness 12 to 20 mm (Twelve to twenty millimetre) in patches of area 2.5 (Two point five) square meters and under, including utting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete With cement mortar 1:4 (one cement : four fine sand) complete as per drawing and HP.PWD technical specifications including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, excluding GST and any other taxes imposed by the Government.	113.68 Square metres	211.86	Rupees Two hundred eleven and paise eighty six only.	Per square metre	24084.00
3	Providing and applying white cement based putty of Birla / JK average thickness 1mm (One millimetres) thick, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete upto all floor level complete including carriage of material with in all leads, lifts and other incidentals as per drawing, design and specifications, as per the direction and entire satisfaction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, excluding GST and any other taxes imposed by the Government.	113.68 Square metres	50.85	0.00	Per square metre	5781.00
4	Wall painting two coats with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour complete including carriage of material with in all leads, lifts and other incidentals as per drawing, design and specifications, as per the direction and entire satisfaction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, excluding GST and any other taxes imposed by the Government.	783.84 Square metres	63.39	Rupees Sixty three and paise thirty nine only	Per square metre	49688.00

15

5	Providing and laying 300x300 mm (Three hundred into three hundred millimetres) ceramic glazed floor tiles of Premium Quality of Niteco/AGL/RAK/SIMPOLO/ Kajaria/Somany / Orient Bell /Johnson tiles as per approved shade (thickness to be specified by the manufacturer) of 1st quality conforming to IS: 15622 of approved make, in all colours and shades except white, Ivory, Grey, Fume red brown, laid on 20mm thick bed of cement mortar 1: 4 (One cement : four sand) jointing with grey cement slurry @ 3.3 (Three point three) kilogramm per square metre including pointing the joints with cement and matching pigments etcetra complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, excluding GST and any other taxes imposed by the Government.	29.53 Square metres	805.08	Rupees Eight hundred five and paise zero eight only.	Per Square metre	23774.00
Qouted Rates Percentage in figure						
Qouted Rates Percentage in word						
TOTAL :-						106988.00

Executive Engineer,
H.P.P.W.D. Division,
Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST:- Rs. 96463.00
EARNEST MONEY :- Rs. 2000.00
TIME LIMIT : ONE MONTH

NAME OF WORK:-

Construction of link road Shamshahat Machinder Mahadev in G.P. Mumta in District Kangra, (H.P.).

SUB-HEAD:-

Construction of Breast wall at RD 0/120 to 0/127 (R/side), & CC Pavement.

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within a any lead as directed by the Engineer-in-charge, within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, excluding GST and any other taxes imposed by the Government.	8.19 Cubic metres	262.71	Rupees Two hundred sixty two and paise seventy one only.	Per cubic metre	2152.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level cement concrete 1:5:10 (One cement; five sand; ten graded broken/crushed stone aggregate 40mm (Forty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, excluding GST and any other taxes imposed by the Government.	25.07 Cubic metres	3347.46	Rupees Three thousand three hundred forty seven and paise forty six only.	Per cubic metre	83921.00
3	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, excluding GST and any other taxes imposed by the Government.	10.00 Running metre	271.19	Rupees Two hundred seventy one and paise nineteen only.	Per running metre	2712.00
4	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level cement concrete 1:2:4 (One cement; two sand; four graded broken/crushed stone aggregate 20mm (Twenty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, excluding GST and any other taxes imposed by the Government.	1.51 Cubic metres	5084.75	Rupees Five thousand eighty four and paise seventy five only.	Per cubic metre	7678.00
TOTAL :-						96463.00
Quoted rates percentage in figures						
Quoted rates percentage in word						

Executive Engineer,
H.P.P.W.D. Division,
Tanda at Nagrota Bagwan.

Schedule of Quantity

NAME OF WORK :- Protection of existing MMV Workshop Building Govt. I.T.I. at Sarotari in Distt. Kangra (H.P.). DEPOSIT WORK.
SUB HEAD :- Balance work of Wire Crates work.

ESTIMATED COST :- ₹ 99026.00
EARNEST MONEY :- ₹ 2000.00
TIME LIMIT : TWO MONTHS

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig.	In words		
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government	22.96 Cubic metres	262.71	Rupees Two hundred sixty two and paise seventy only.	Per cubic metre	6032.00
2	Providing & making Gabion structure with Mechanically Woven Double Twisted Hexagonal Shaped Wire mesh Gabion Boxes as per IS 16014:2012, MORTH Clause 2500, of required size, Mesh Type 10x12 (D=100 mm with tolerance of ± 2%) Zinc coated, Mesh wire diameter 3.0 mm, mechanically edged/selvedged with partitions at every 1m interval and shall have minimum 10 numbers of openings per meter of mesh perpendicular to twist, tying with lacing wire of diameter 2.2mm, supplied @ 3% by weight of Gabion boxes, filled with boulders with least dimension of 200 mm, as per drawing, all complete as per direction of Engineer-in-charge including carriage of materials within all leads, lifts and other incidentals.	35.76 Cubic metres	2330.51	Rupees Two thousand three hundred thirty and paise fifty one only.	Per cubic metre	83339.00
3	Backfilling with granular material behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8, granular material as per drawing and HP.PWD technical specifications and as directed by Engineer-In-charge including carriage of material within all leads, lifts and other incidentals.	15.19 Cubic metres	635.59	Rupees Six hundred thirty five and paise fifty nine only.	Per cubic metre	9655.00
TOTAL :-						99026.00

Quoted rates percentage in figure
Quoted rates percentage in words

Executive Engineer,
H.P.P.W.D., Division,
Tanda at Nagrota Bagwan.

PROPOSED SCHEDULE OF QUANTITY

ESTIMATED COST:- Rs. 194174.00
EARNEST MONEY :- Rs. 3900.00

TIME LIMIT : THREE MONTH

NAME OF WORK:-

Restoration of rain damages on Paliyalkar to Kaled road Km 0/000 to 3/500 in Distt. Kangra (Himachal Pradeshn)

Under PDNA 2025

SUB-HEAD :-

Construction of U-Shape drain & Breast wall in between Km 3/450 TO 3/478. (4349-1)

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within a any lead as directed by the Engineer-in-charge, within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, excluding GST and any other taxes imposed by the Government.	38.30 Cubic metres	262.71	Rupees Two hundred sixty two and paise seventy one only.	Per cubic metre	10062.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level cement concrete 1:3:6 (One cement; three sand; six graded broken/crushed stone aggregate 40mm (Forty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, excluding GST and any other taxes imposed by the Government.	3.89 Cubic metres	3940.68	Rupees Three thousand nine hundred forty and paise sixty eight only.	Per cubic metre	15329.00
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level cement concrete 1:5:10 (One cement; five sand; ten graded broken/crushed stone aggregate 40mm (Forty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, excluding GST and any other taxes imposed by the Government.	48.72 Cubic metres	3347.46	Rupees Three thousand three hundred forty seven and paise forty six only.	Per cubic metre	163088.00
4	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, excluding GST and any other taxes imposed by the Government.	21.00 Running metre	271.19	Rupees Two hundred seventy one and paise nineteen only.	Per running metre	5695.00
TOTAL :-						194174.00

Quoted rates percentage in figures
Quoted rates percentage in word

Executive Engineer,
H.P.P.W.D. Division,
Tanda at Nagrota Bagwan

SCHEDULE OF QUANTITY

ESTIMATED COST:- Rs. 111564.00
EARNEST MONEY :- Rs. 2300.00
TIME LIMIT : TWO MONTH

NAME OF WORK:-

Restoration of rain damages on Chandni Chowk to Rin road Km 0/000 to 2/200 in Distt. Kangra (Himachal Pradesh) Under PDNA 2025

SUB-HEAD:-

Construction of Toe wall & Providing and laying Cement Concrete Pavement over Hume pipe. (4355-1)

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within a any lead as directed by the Engineer-in-charge, within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, excluding GST and any other taxes imposed by the Government.	20.93 Cubic metres	262.71	Rupees Two hundred sixty two and paise seventy one only.	Per cubic metre	5499.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level cement concrete 1:3:6 (One cement; three sand; six graded broken/crushed stone aggregate 40mm (Forty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, excluding GST and any other taxes imposed by the Government.	1.40 Cubic metres	3940.68	Rupees Three thousand nine hundred forty and paise sixty eight only.	Per cubic metre	5517.00
3	Providing, laying, spreading and compacting stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm (seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specifications Clause No. 405 and as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, excluding GST and any other taxes imposed by the Government.	2.53 Cubic metres	1737.29	Rupees One thousand seven hundred thirty seven and paise twenty nine only	Per cubic metre	4395.00

AP

4	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level cement concrete 1:2:4 (One cement, two sand; four graded broken/crushed stone aggregate 20mm (Twenty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, excluding GST and any other taxes imposed by the Government.	18.91 Cubic metres	5084.75	Rupees Five thousand eighty four and paise seventy five only.	Per cubic metre	96153.00
TOTAL :- 111564.00						
Quoted rates percentage in figures						
Quoted rates percentage in word						


 Executive Engineer,
 H.P.P.W.D. Division,
 Tanda at Nagrota Bagwan

DRAFT SCHEDULE OF QUANTITY

NAME OF WORK :-

Construction of link road from Dhaloon road to Dhaloon Society Km 0/000 to 0/800 in District Kangra, (H.P.).

SUB-HEAD :-

Providing and laying Cement Concrete Pavement in Km 0/000 to 0/100. (DEPOSIT 8443 MNP)

ESTIMATED COST :- Rs. 170381.00
EARNEST MONEY :- Rs. 3500.00
TIME LIMIT : TWO MONTHS

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Stone soling with hard stone of approved quality under floors including watering, ramming, consolidating and dressing complete including carriage of material within all leads, lifts and other incidentals as per approved drawing, design, specifications and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, excluding GST and any other taxes imposed by the Government.	17.82 Cubic metres	805.08	Rupees Eight hundred five and paise zero eight only.	Per cubic metre	14347.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level cement concrete 1:2:4 (One cement; two sand; four graded broken/crushed stone aggregate 20mm (Twenty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, excluding GST and any other taxes imposed by the Government.	26.72 Cubic metres	5084.75	Rupees Five thousand eighty four and paise seventy five only.	Per cubic metre	135865.00
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level cement concrete 1:4:8 (One cement; four sand; eight graded broken/crushed stone aggregate 20mm (Twenty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, excluding GST and any other taxes imposed by the Government.	4.86 Cubic metres	4150.00	Rupees Four thousand one hundred fifty and paise nil only	Per cubic metre	20169.00
TOTAL :-						170381.00
Quoted rates percentage in figures						
Quoted rates percentage in word						

Executive Engineer,
H.P.P.W.D. Division,
Tanda at Nagrota Bagwan

DRAFT SCHEDULE OF QUANTITY

ESTIMATED COST :- Rs. 169026.00
EARNEST MONEY :- Rs. 3400.00

TIME LIMIT : ONE MONTH

NAME OF WORK :-

Restoration of rain damages on link road from Sera to Chhanwar including bridge over Daroon khad in G.P Sera Thana in Dist. Kangra (Himachal Pradesh)

SUB-HEAD :-

Providing and laying Cement Concrete Pavement.

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting stone aggregate size 53mm to 22.4mm (fifty three millimeter to twenty two point four millimeter) Grading-III size [75mm (seventy five millimeters) compacted thickness] to water bound macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven point two millimetres) nominal size at the rate of 0.18cum (zero point eighteen) cubic metres per 10 Sqm (per ten square metres) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specifications Clause No. 405 and as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, excluding GST and any other taxes imposed by the Government.	14.20	1737.29	Rupees One thousand seven hundred thirty seven and paise twenty nine only	Per cubic metre	24670.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level cement concrete 1:2:4 (One cement; two sand; four graded broken/crushed stone aggregate 20mm (Twenty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, excluding GST and any other taxes imposed by the Government.	28.39	5084.75	Rupees Five thousand eighty four and paise seventy five only.	Per cubic metre	144356.00
TOTAL :-						169026.00
Quoted rates percentage in figures						
Quoted rates percentage in word						

Executive Engineer,
H.P.P.W.D. Division,
Tanda at Nagrota Bagwan