

Himachal Pradesh
Public Works Department

No. PW-KD- CTR- Tender-NIT/2026-2027-

Dated:-

18937-38

01/10/26

To


The Executive Engineer (IT Cell)
Nigam Vihar Shimla.

Subject :- Publication of Tender Notice.

Jai Hind


Enclosed please find herewith the tender Notice of work as given in the Notice Inviting tender for uploading on department website as per notification Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW (B)A(3)1/2024 dated Shimla-2 the 03-01-2024 and PWD-B-A0(3)/8/2025- 300858 dated 09-10-2025 as the works mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender & Schedule of Quantity and Certificate.


Executive Engineer,
HPPWD, Division Kasumpti
Shimla.

Copy forwarded to for further necessary action please.

1. The Superintending Engineer 4th Circle HPPWD Shimla .


Executive Engineer,
HPPWD, Division Kasumpti
Shimla.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDERS**

Executive Engineer B&R Division Kasumpti HPPWD Shimla for the following works on behalf of the Government of Himachal Pradesh from the eligible contractors enlisted in HPPWD, so as to reach in the office as per time schedule given below:-

- | | |
|--|-----------------------------------|
| 1. Date of receipt of application for tender forms:- | 08-10-2026 10:00 AM upto 12:00 PM |
| 2. Dated of Issue /sale of tender forms:- | 08-10-2026 12:00 PM upto 4:00 PM |
| 3. Date of receipt of tender:- | 09-10-2026 .up to 10:30 AM |
| 4. Date of opening of tender:- | 09-10-2026 up to 11:00 AM |

Sr. No.	Name of Work	Estimated cost	EMD(Rs.)	Cost of Tender (Rs.)	Time Limit	Eligible class of Contractor
1	Restoration of rain damages various roads under AIMSS section (SH:- Removal of slips various RDs Between) (Excluding GST)(Under PDNA)	61075/-	1300/-	350	30 days	Class-D
2	A/R & M/O various Type-I & Type-VI GAD at Kasumpti Shimla-9 (SH:- Covering of Balcony of Type-III Set No.115,116,117 and Type-IV set No. 57 under Kasumpti Sub-Division)(Excluding GST).	84141/-	1700/-	350/-	30 days	Class-D
3	A/R & M/O various Type-I & Type-VI GAD at Kasumpti Shimla-9 (SH:- P/F Cupboard in Type-II Set No. 22,21 and white washing / distemping under Mehli Section)(Excluding GST).	83301/-	1700/-	350/-	30 days	Class-D
4	Restoration of rain damages on Mashobra to Bhaikalty road Km. 0/000 to 18/000 (SH:- C/O R/Wall between RD 15/225 to 15/238.50) (Under PDNA) (Excluding GST).	409725/-	8200/-	350/-	30 days	Class-D
5	Restoration of rain damages on Shoghi Mehli Junga Sadhupul road Km. 12/375 to 48/925. (SH:- C/O PCC R/Wall at R/D 24/420 to 24/428.5) (under PDMA) (Excluding GST).	411457/-	8300/-	350/-	30 days	Class-D
6	Restoration of rain damages on Nauti to Thaila road Km. 0/00 to 7/350 (SH:- C/O R/Wall at RD 5/915 to 5/930) (Under PDNA) (Excluding GST).	410254/-	8200/-	350/-	30 days	Class-D
7	Restoration of rain damages on Eversunny to Pagog road Km. 0/00 to 5/00 (SH:- Removal of slips various RDs) (Excluding GST) (Under PDNA).	420793/-	8500/-	350/-	30 days	Class-D
8	Preparation of detailed project report Detail estimate/ working estimate along with Justification with detailed Analysis of various works of building under Kasumpti Division Shimla -3 Sub-Davison No.VIII (Excluding GST).	33898/-	700/-	350/-	30 days	Class-D
9	Regarding Maintenance / Renovation Work at Nalدهhra Golf Course. (SH:- Reshuffling full size chair & single seat Sofa with foom cushion fiber etc) (Excluding GST).	83051/-	1700/-	350/-	30 days	Class-D
10	Regarding / Renovation work at Nalدهhra Golf Course. (SH:- Reshuffling Chair sets & sofa sets etc) (Excluding GST).	83262/-	1700/-	350/-	30 days	Class-D
11	Regarding / Renovation work at Nalدهhra Golf Course. (SH:- Reshuffling of outdoor moulded lawn sofa cum chair plastic UV etc) (Excluding GST).	83898/-	1700/-	350/-	30 days	Class-D
12	Regarding / Renovation work at Nalدهhra Golf Course. (SH:- Reshuffling of full size Chair & five seats sofa & plastic chair UV resistance etc) (Excluding GST).	81525/-	1700/-	350	30 days	Class-D
13	Restoration of rain damages on Shimla to Mandi road Km. 6/00 to 22/00 (SH:- C/O wall at RD. 12/700 to 12/716) (Under PDNA) (Excluding GST).	404634/-	8100/-	350	30 days	Class-D
14	Restoration of rain damages on Shimla to Mandi road Km. 6/00 to 22/00 (SH:- C/O wall at RD. 20/050 to 20/060) (Under PDNA) (Excluding GST).	370521/-	7400/-	350/-	30 days	Class-D
15	Restoration of rain damages on Nauti to Thaila road Km. 0/00 to 7/300 (SH:- C/O R/Wall at RD 2/200 to 2/225) (Under PDNA) (Excluding GST).	394216/-	7900/-	350	30 days	Class-D
16	Restoration of rain damages on Mashobra to Bhakhality road Km. 0/00 to 18/00 (SH:- Removal of slips/ Road side Muck between RD's) (Excluding GST).	83644/-	1700/-	350/-	30 days	Class-D
17	Restoration of rain damages on Mashobra Section (SH:- Removal of slip/ road side Muck between Roads (1) Purani Koti to Ghorna road in Km. 0/00 to 3/00 Mashobra to sepur road in Km. 0/00 to 2/720 and Dak bangle to Gharech road in Km. 0/00 to 7/615) (Excluding GST).	83941/-	1700/-	350/-	30 days	Class-D
18	R/O & R/D Shoghi Mehli Junga Sadhupul Road Km. 12/375 to 48/925 (SH:- Removal of slips between RD 25/000 to 39/000) (Under PDNA) (Excluding GST).	409335/-	8200/-	350 days	30 days	Class-D
19	R/O & R/D on Shoghi Mehli Junga Sadhupul Road Km. 12/375 to 48/925 (SH:- Removal of slips between RD 22/000 to 25/000) (Under PDNA) (Excluding GST).	408159/-	8200/-	350/-	30 days	Class-D

It is certified that the above works are required to be carried out immediately being emergent nature of work in public interest.

The tender documents shall be issued only to those contractor/Firm who fulfill the following documents with the application.

1. The valid enlistment/registration of contractor in appropriate class.
2. Permanent account No. (PAN NO).
3. G.S.T No.
4. Earnest Money in the shape of National saving certificate/time deposit account in the any of the post office in HP. F.D.R from any Nationalized Bank duly pleaded in favour of the Executive Engineer Division Kasumpti HPPWD Shimla.
5. The earnest & cost of tender form for the above works should be submitted with the application for the purchase of the tender form. The application received without earnest money & cost of tender form shall summarily be rejected.
6. The officer of the tender shall remain valid up to 75 days after the opening of tender.
7. Ambiguous/telephonic /conditional tenders or tender by fax/E mail shall not be considered and will be summarily be rejected.
8. Executive Engineer reserve the right to reject or cancel any or all tenders without assigning any reasons.
9. If the date given above happens to be holiday the same shall be processed on next working day.
10. The Contractor/firms must quote their rates in words as well as in figures failing which EXN reserve the right to accept/reject any or all tenders.
11. The tender forms shall not be issued to those contractors/firms whose previous performance is not found satisfactory and who have not executed the previous awarded works within the stipulated period of completion.
12. One contractor shall not have more than two major works in hand at a time.
13. Work should be completed by the contractor within stipulated period.

Executive Engineer,
Division Kasumpti.,
HPPWD. Shimla-3.

Dated :- 01-10-2026

No.PW-SD-I/CB-Tender/2026-2027-
Copy forwarded to:-

18939-52

1. Copy to the Deputy Commissioner Shimla Distt. Shimla.
2. Copy to the Executive Engineer Shimla Division No-III HPPWD Shimla.
3. Copy to the Sub Divisional Magistrate (U) Shimla.
4. Copy to the Sub Divisional Magistrate (R) Shimla.
5. Copy to Municipal committee Shimla Distt. Shimla.
6. Copy to Block Development officer Mashobra Distt. Shimla.
7. All the Assistant Engineers under this Division, HPPWD Shimla-3.
8. Superintendent / HDM /DAO.
9. Notice Board.

Executive Engineer,
Division Kasumpti.,
HPPWD. Shimla.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D.,					Estimated Cost:-61,075.00		
Name of Work :- Restoration of rain damages various roads under AIMSS section (SH :-Removal of Slips various Rds Between) (Excluding GST))UNDER PDNA					Earnest Money :1300.00		
					Time:- One Month		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Removal of land slides/slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal responsibility by the contractor with all leads & lift. . The work shall be executed as per the direction of the Engineer-in-Charge. (Excluding GST)	205.91	Cum	296.61	Rupees Two Hundred Ninety Six and Paise Sixty One Only	Per Cubic Meter	61075.00
						Total	61075.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer,
B&R Division Kasumpti,
HPPWD, Winter Field Shimla-3

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-					Estimated Cost:- 84,141.00		
Name of Work :- A/R & M/O various Type-I & Type-VI GAD at Kasumpti, Shimla-9. (SH: Covering of Balcony of Type-III Set no. 115 , 116, 117 and Type- IV Set no. 57, under Kasumpti Sub-Division.) (Excluding GST)					Earnest Money :- 1,700.00		
					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount (Excluding GST)
				In figures	In words		
1	Steel work welded in built up sections, trusses and framed work including cutting hoisting fixing in position and applying a priming coat of red lead paint including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) In gratings , frames , guard bar , lasser, railing , brackets , gates and similar works. (Excluding GST)	174.00	Kgs	97.46	Rupees Ninety Seven and Paise Forty Five Only	Per Kilo-gramme	16958.00
2	Supplying and fixing welded mesh to wood or steel members in partition etc including one coat of priming coat , including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) Size 25x25x3mm (Excluding GST)	14.10	Sqm	508.47	Rupees Five Hundred Eight and Paise Forty Seven Only	Per Square metre	7169.00
3	Painting two coats(excluding priming coat on new steel and metal surface with enamel paint brushing to give an even shade including cleaning the surface of dirt,dust and other foreign matter,sand papering & stoping including carriage of materials in all leads as per directions of the Engineer-in-Charge.(i) Enemal paint other than white (Excluding GST)	14.10	Sqm	55.08	Rupees Fifty Five and Paise Eight Only	Per Square metre	777.00
4	Providing and fixing Copper oxidised fittings (iron) including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.(i)But things:75x47x1.70mm (Excluding GST)	2.00	Nos	84.75	Rupees Eighty Four and Paise Seventy Four Only	Each	169.00
5	Providing and fixing oxidised M.S sliding door bolts with nuts and screw etc, including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (i) 250x16mm. (Excluding GST)	2.00	Nos	211.86	Rupees Two Hundred Eleven and Paise Eighty Six Only	Each	424.00

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-					Estimated Cost:- 83,301.00		
Name of Work :- A/R & M/O various Type-I and Type-VI GAD Qtrs at, Kasumpti, Shimla-9. (SH:- P/F Cupboard in Type-II Set no. 22 , 21 and White washing / Distemping under Mehli Section.) (Excluding GST)					Earnest Money :- 1,700.00		
					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount (Excluding GST)
				In figures	In words		
1	Providing and fixing 19mm thick water proof commercial board in shelves/shutters box for cup board with butt joints & fixing with nails & screws etc complete) including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge. (Excluding GST)	12.21	Sqm	1228.81	Rupees One Thousand Two Hundred Twenty Eight and Paise Eighty One Only	Per Square Meter	15004.00
2	Providing and fixing 0.80mm thick coloured or plain lamination sheet (sunmica) on boards/ply wood sheets with approved adhesive and nails etc. complete including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (Excluding GST)	5.41	Sqm	847.46	Rupees Eight Hundred Forty Seven and Paise Forty Five Only	Per Square meter	4585.00
3	Providing and fixing ply wood lining with butt jointing and nails (frame work and cove fillets to be measured and paid for separately) including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge. (i) 6mm (six milimetre)thick (Excluding GST)	12.44	Sqm	720.34	Rupees Seven Hundred Twenty and Paise Thirty Three Only	Per Square Meter	8961.00
4	Providing and fixing square edges cover fillets (beading) 19mmx6mm(Nineteen milimetre into six milimetre) section i/c mitring at junctions with wood screws and nails complete including carriage of materials in all leads and lifts as per directions of the Engineer-In-Charge.(i)1st class deodar wood.	78.85	Rmt	72.03	Rupees Seventy Two and Paise Three Only	Per Running Meter	5680.00
5	Providing and fixing bright finished brass ball catcher 10 mm dia including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (Excluding GST)	40.00	Nos	55.08	Rupees Fifty Five and Paise Eight Only	Each	2203.00

661

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D.,					Estimated Cost:- 4,10,254.00		
Name of Work :- Restoration of rain damages on Nauti to Thala Road Km. 0/00 to 7/350.					Earnest Money :-8,200 .00		
(SH:- C/O R/Wall at RD 5/915 to 5/930). (Under PDNA) (Excluding GST)					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount (Excluding GST)
				In figures	In words		
1	Cutting in Earth work in excavation by mechanical means (Hydraulic excavator/manual means over areas (exceeding 30 cm (Thirty centimetre) in depth, 1.5 m (One point five metre) in width as well as 10 sqm (ten Square Metre) on plan) including getting out and disposal of excavated earth all lead and lift as directed by Engineer-in-charge and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site (To be arranged by the contractor) as per satisfaction of Engineer- in -charge through all modes of transportation including head load ,animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required) Any loss to the public and private propriety, human being, machinery during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges. (i)All kinds of soil. (Excluding GST)	50.00	Cum	275.42	Rupees Two Hundred Seventy Five and Paise Forty Two Only	Per Cubic Metre	13771.00

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER KASUMPTI DIVISION , H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 83051.00	
Name of Work :- Regarding Maintenance / Renovation Work at Naldehra Golf Course. (SH:- Restuffing full size chair & single seat Sofa with foam cushion fiber etc). (Excluding GST)						Earnest Money :- 1700.00	
						Time:- Two Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Restuffing of fullsize chair seat and back with form and cloth (Leatherite) fiber and with labour charge and all small material complete with GST included, including carriage of materials in all leads as per directions of the Engineer-in-Charge. (Excluding GST)	25.00	Nos	2440.68	Rupees Two Thousand Four Hundred Forty and Paise Sixty Seven Only	Per Each	61017.00
2	Restuffing of Single seater sofa with foam cushion fiber including all work and all respect and labour charge and with GST included, including carriage of materials in all leads as per directions of the Engineer-in-Charge. (Excluding GST)	4.00	Nos	5508.47	Rupees Five Thousand Five Hundred Eight and Paise Forty Seven Only	Per Each	22034.00
					Total		83051.00

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer,
HPPWD Division,
Kasumpti Shimla

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER KASUMPTI DIVISION , H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 83898.00	
Name of Work :- Regarding Maintenance / Renovation Work at Naldehra Golf Course. (SH:- Re-stuffing of Out door moulded lawn Sofa cum chair plastic UV etc). (Excluding GST)						Earnest Money :- 1700.00	
						Time:- Two Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Outdoor moulded furniture lawn Sofa cum chair Plastic UV resistance set has on modern look chair and suitable for outdoors Neel Kamal Company dark brown chair with cushion i/c all lift and leads included, including carriage of materials in all leads as per directions of the Engineer-in-Charge. (Excluding GST)	11.00	Nos	7627.11	Rupees Seven Thousand Six Hundred Twenty Seven and Paise Eleven Only	Per Each	83898.00
					Total		83898.00

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer,
HPPWD Division,
Kasumpti Shimla

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER KASUMPTI DIVISION , H.P.P.W.D., SHIMLA-3.						Estimated Cost:- .81525.00	
Name of Work :- Regarding Maintenance / Renovation Work at Naldehra Golf Course. (SH:- Restuffing of full size Chair & five seats Sofa & Plastic chair UV resistance etc) (Excluding GST)						Earnest Money :- 1700.00	
						Time:- Two Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Outdoor lawn chair Plastic UV resistance set has on modern look chair and suitable for outdoors Neel Kamal Company dark brown chair with cushion i/c all lift and leads included, including carriage of materials in all leads as per directions of the Engineer-in-Charge. (Excluding GST)	6.00	Nos	4661.02	Rupees Four Thousand Six Hundred Sixty One and One Paise Only	Per Each	27966.00
2	Outdoor lawn chair Plastic UV resistance material and with Glass standard size over it i/c all lift and leads included, including carriage of materials in all leads as per directions of the Engineer-in-Charge. (Excluding GST)	4.00	Nos	5762.71	Rupees Five Thousand Seven Hundred Sixty Two and Paise Seventy One Only	Per Each	23051.00
3	Outdoor moulded furniture lawn Sofa cum chair Plastic UV resistance set has on modern look chair and suitable for outdoors Neel Kamal Company dark brown chair with cushion i/c all lift and leads included, including carriage of materials in all leads as per directions of the Engineer-in-Charge. (Excluding GST)	4.00	Nos	7627.12	Rupees Seven Thousand Six Hundred Twenty Seven and Paise Eleven Only	Per Each	30508.00
					Total		81525.00

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer,
HPPWD Division,
Kasumpti Shimla


SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D.,						Estimated Cost:- 4,04,634.00	
Name of Work :- Restoration of rain damages on Shimla to Mandi Road Km. 6/00 to 22/00.						Earnest Money :- 8,100.00	
(SH:- C/O wall at RD 12/700 to 12/716) Under PNDA (Excluding GST)						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Cutting in Earth work in excavation by mechanical means (Hydraulic excavator/manual means over areas (exceeding 30 cm (Thirty centimetre) in depth, 1.5 m (One point five metre) in width as well as 10 sqm (ten Square Metre) on plan) including getting out and disposal of excavated earth all lead and lift as directed by Engineer-in-charge and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site (To be arranged by the contractor) as per satisfaction of Engineer- in -charge through all modes of transportation including head load ,animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required) Any loss to the public and private propriety, human being, machinery during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges. (i)All kinds of soil. (Excluding GST)	71.20	Cum	275.42	Rupees Two Hundred Seventy Five and Paise Forty Two Only	Per Cubic Metre	19610.00

4	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.(a) Cement Mortar 1:4:8(One cement:Four sand:Eight graded stone aggregate 40 mm(40 milimetre) nominal size). (Excluding GST)	94.56	Cum	3728.81	Rupees Three Thousand Seven Hundred Twenty Eight and Paise Eighty One Only	Per Cubic Metre	352597.00
5	Backfilling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Granular material. (Excluding GST)	2.24	Cum	1016.95	Rupees One Thousand Sixteen and Paise Ninety Four Only	Per Cubic Metre	2278.00
6	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm(One hundred milimetre) dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge. (Excluding GST)	25.00	Rmt	169.49	Rupees One Hundred Sixty Nine and Paise Forty Nine Only	Per Running meter	4237.00
						Total	404634.00
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standards.


 Executive Engineer,
 B& R Division Kasumpti
 HPPWD Winter Field Shimla -3

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D.,					Estimated Cost:- 3,70,521.00		
Name of Work :- Restoration of rain damages on Shimla to Mandi Road Km. 6/00 to 22/00.					Earnest Money :- 7,400.00		
(SH:- C/O wall at RD 20/050 to 20/060) Under PNDA (Excluding GST)					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Cutting in Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (Thirty centimetre) in depth, 1.5 m (One point five metre) in width as well as 10 sqm (ten Square Metre) on plan) including getting out and disposal of excavated earth all lead and lift as directed by Engineer-in-charge and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site (To be arranged by the contractor) as per satisfaction of Engineer- in -charge through all modes of transportation including head load ,animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required) Any loss to the public and private propriety, human being, machinery during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges. (i)All kinds of soil. (Excluding GST)	67.80	Cum	275.42	Rupees Two Hundred Seventy Five and Paise Forty Two Only	Per Cubic Metre	18674.00

2	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and back filling with approved material. Hard Roack blasting prohibited and their intermediate classification of soils including, dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer -in-charge at site, according to the HP.PWD. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site (To be arranged by the contractor) including payment of prescribed charges of dumping to the owner of dumping site as per satisfaction of Engineer-in-Charge through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required).All useful material such as stones, shingles aggregate and slates shall be properly stacked at site to the maximum possible extent in all leads and lifts through all modes of transportation the usefull stones as per the direction of the Engineer-in-Charge. Any loss to the public and private propriety during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges. (Excluding GST)	5.80	Cum	338.98	Rupees Three Hundred Thirty Eight and Paise Ninety Eight Only	Per Cubic Metre	1966.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Cement Mortar 1:6:12(One cement: six sand: twelve graded stone agg.40mm nominal size). (Excluding GST)	5.80	Cum	2966.10	Rupees Two Thousand Nine Hundred Sixty Six and Paise Ten Only	Per Cubic Metre	17203.00

4	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge.(a) Cement Mortar 1:4:8(One cement:Four sand:Eight graded stone aggregate 40 mm(40 millimetre) nominal size). (Excluding GST)	87.70	Cum	3728.81	Rupees Three Thousand Seven Hundred Twenty Eight and Paise Eighty One Only	Per Cubic Metre	327017.00
5	Backfilling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Granular material. (Excluding GST)	1.40	Cum	1016.95	Rupees One Thousand Sixteen and Paise Ninety Four Only	Per Cubic Metre	1424.00
6	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm(One hundred milimetre) dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge. (Excluding GST)	25.00	Rmt	169.49	Rupees One Hundred Sixty Nine and Paise Forty Nine Only	Per Running meter	4237.00
						Total	370521.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer,
B& R Division Kasumpti
HPPWD Winter Field Shimla -3


SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.					Estimated Cost:- 3,94,216.00		
Name of Work :- Restoration of rain damages on Nauti to Thala Road Km. 0/00 to 7/300.					Earnest Money :- 7,900.00		
(SH:- C/O R/Wall at RD 2/200 to 2/225). (Under PDNA) (Excluding GST)					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount (Excluding GST)
				In figures	In words		
1	Cutting in Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (Thirty centimetre) in depth, 1.5 m (One point five metre) in width as well as 10 sqm (ten Square Metre) on plan) including getting out and disposal of excavated earth all lead and lift as directed by Engineer-in-charge and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site (To be arranged by the contractor) as per satisfaction of Engineer- in -charge through all modes of transportation including head load ,animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required) Any loss to the public and private propriety, human being, machinery during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges. (i)All kinds of soil. (Excluding GST)	59.00	Cum	275.42	Rupees Two Hundred Seventy Five and Paise Forty Two Only	Per Cubic Metre	16250.00

2	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and back filling with approved material. Hard Roack blasting prohibited and their intermediate classification of soils including, dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer -in-charge at site, according to the HP.PWD. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site (To be arranged by the contractor) including payment of prescribed charges of dumping to the owner of dumping site as per satisfaction of Engineer-in-Charge through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required).All useful material such as stones, shingles aggregate and slates shall be properly stacked at site to the maximum possible extent in all leads and lifts through all modes of transportation the usefull stones as per the direction of the Engineer-in-Charge. Any loss to the public and private propriety during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges. (Excluding GST)	12.00	Cum	338.98	Rupees Three Hundred Thirty Eight and Paise Ninety Eight Only	Per Cubic Metre	4068.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Cement Mortar 1:6:12(1one cement: six sand: twelve graded stone agg.40mm nominal size). (Excluding GST)	12.00	Cum	2966.10	Rupees Two Thousand Nine Hundred Sixty Six and Paise Ten Only	Per Cubic Metre	35593.00

4	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Cement Mortar 1:4:8 (one cement : four sand: Eight graded stone aggregate 40 mm(Forty milimetre) nominal size). (Excluding GST)	88.00	Cum	3728.81	Rupees Three Thousand Seven Hundred Twenty Eight and Paise Eighty One Only	Per Cubic Metre	328136.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm(One hundred milimetre) dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge. (Excluding GST)	60.00	Rmt	169.49	Rupees One Hundred Sixty Nine and Paise Forty Nine Only	Per Running meter	10169.00
						Total	394216.00
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.


 Executive Engineer
 B & R Division Kasumpti
 HPPWD Winter Field Shimla -3

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.						Estimated Cost:- 83,644.00	
NAME OF WORK:- Restoration of Rain Damages on Mashobra to Bhakhality road km 0/00 to 18/00 (SH:- Removal of slip / Road side Muck between RD's) (Excluding GST)						Earnest Money :- 1,700.00	
						Time:- One Month.	
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount (Excluding GST)
				In figures	In words		
1	Hiring of JCB excavator-cum-loader for removal of slip Debris and dressing of Beams including coat of fuel oil lubricants wages of operational staffs any repair package during operation will be carried out at his risk and cost at required location actual working will be accounted for payment and proper disposal slips/ debris by the contractor will be insured and dumping site will be arranged by the contractor at his own cost of tripper or carriage out as per instructions, including carriage of materials in all leads as per directions of the Engineer-in-Charge. (Excluding GST)	282.00	Cum	296.61	Rupees Two Hundred Ninety Six and Paise Sixty One Only	Per Cubic Metre	83644.00
						Total	83644.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

CONDITION:-


1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer
B& R Division Kasumpti
HPPWD Winter Field Shimla -3

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.					Estimated Cost:- 83,941.00		
NAME OF WORK:- Restoration of Rain Damages on Mashobra Section (SH:- Removal of slip / Road side Muck between Roads (1) Purani Koti to Ghorna road in Km 0/00 to 3/00 ,Mashobra to Sipur road in Km 0/00 to 2/720 and Dak Bangla to Gharech road in Km 0/00 to 7/615.) (Excluding GST)					Earnest Money :- 1,700.00		
					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount (Excluding GST)
				In figures	In words		
1	Hiring of JCB excavator-cum-loader for removal of slip Debris and dressing of Beams including coat of fuel oil lubricants wages of operational staffs any repair package during operation will be carried out at his risk and cost at required location actual working will be accounted for payment and proper disposal slips/ debris by the contractor will be insured and dumping site will be arranged by the contractor at his own cost of tripper or carriage out as per instructions, including carriage of materials in all leads as per directions of the Engineer-in-Charge. (Excluding GST).	283.00	Cum	296.61	Rupees Two Hundred Ninety Six and Paise Sixty One Only	Per Cubic Metre	83941.00
						Total	83941.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

CONDITION:-


1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of Indian standards.


 Executive Engineer,
 B& R Division Kasumpti
 HPPWD Winter Field Shimla -3

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D.,					Estimated Cost:- 4,09,335.00		
Name of Work :- R/O & R/D Shoghi Mehli Junga Sadhupul road km 12/375 to 48/925 (SH:- Removal of Slips between RD 25/000 to 39/000). (Under PDNA) (Excluding GST)					Earnest Money :- 8,200.00		
					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount (Excluding GST)
				In figures	In words		
1	Removal of land slides/slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a lift. The work shall be executed as per the direction of the Engineer-in-Charge. (Excluding GST)	1610.05	Cum	254.24	Rupees Two Hundred Fifty Four and Paise Twenty Three Only	Per Cubic Meter	409335.00
						Total	409335.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

CONDITION:-


1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.


 Executive Engineer,
 B& R Division Kasumpti
 HPPWD Winter Field Shimla -3

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D.,					Estimated Cost:- 4,08,159.00		
Name of Work :- R/O & R/D on Shoghi Mehli Junga Sadhupul Road Km. 12/375 to 48/925. (SH:- Removal of Slips between RD 22/000 to 25/000). Under PDNA (Excluding GST)					Earnest Money :- 8,200.00		
					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount (Excluding GST)
				In figures	In words		
1	Removal of land slides/slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in a lift. The work shall be executed as per the direction of the Engineer-in-Charge. (Excluding GST)	860.05	Cum	474.58	Rupees Four Hundred Seventy Four and Paise Fifty Seven Only	Per Cubic Meter	408159.00
						Total	408159.00
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.


 Executive Engineer,
 B& R Division Kasumpti
 HPPWD Winter Field Shimla -3