

## H.P P W D NOTICE INVITING TENDER

Sealed percentage rate tender on the form 6&8 are invited by the Executive Engineer, Sarkaghat Division, HPPWD Sarkaghat on behalf of Governor of HP for the following works from the approved and eligible contractor enlisted in HPPWD.

### **TENDER SCHEDULE:**

- 1 Date and time of receipt of application for the tender form :
- 2 Date and time of issue of tender form :
- 3 Date and time of receipt of tenders:
- 4 Date and time of opening of tenders:

21.10.2026 upto 4.00 PM

22.10.2026 upto 4.00 PM

23.10.2026 upto 11.00 AM

23.10.2026 upto 12.30 AM

The tender form will be issued against cash payment (non refundable), the earnest money in the shape of NSC/FDR/Deposit at call of any Post Office/Bank in H.P duly pledged in the name of the Executive Engineer, Sarkaghat Division, HPPWD Sarkaghat must accompany with each tender. Conditional tender and tender received without earnest money will summarily be rejected.

| Sr.No | Name of work                                                                                                                                                         | Estimated cost (In Ra.) | Earnest Money (In Rs.) | Time      |
|-------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------|------------------------|-----------|
| 1     | Restoration of rain damages on Patrighat Goverta road KM 0/00 to 6/00 (SH: Construction of edge wall in PCC 1:5:10 at RD 0/910 to 0/616) Under PDNA                  | 113343/-                | 2270/-                 | 15 Days   |
| 2     | Restoration of rain damages on Ratti Kalkhar Bhambla Una road KM 38/700 to 41/300 (SH: C/o R/Wall in PCC 1:5:10 at RD 38/990 to 39/993) Under PDNA                   | 100933/-                | 2020/-                 | 15 Days   |
| 3     | Restoration of rain damages on Patrighat Jawali Gehra road KM 0/00 to 14/00 (SH: C/o edge wall in PCC 1:5:10 at RD 3/680 to 3/686) Under PDNA                        | 246093/-                | 4925/-                 | 15 Days   |
| 4     | Restoration of rain damages on Kalthari Tikkari Ropa Thathar Batail road KM 0/00 to 7/300 (SH: Construction of R/Wall in PCC 1:5:10 at RD 4/875 to 4/878) Under PDNA | 150965/-                | 3019/-                 | 15 Days   |
| 5     | Restoration of rain damages on Khudla Sears Samloun Kalthar road KM 0/00 to 5/500 (SH: C/o R/Wall in PCC 1:5:10 at RD 5/010 to 5/013) Under PDNA                     | 128309/-                | 2566/-                 | 15 Days   |
| 6     | Restoration of rain damages on Dhalwan Masyani Bhanu Baldwara road KM 0/00 to 9/300 (SH: Construction of R/Wall in PCC 1:5:10 at RD 1/180 to 1/186) Under PDNA       | 167918/-                | 3358/-                 | 15 Days   |
| 7     | Restoration of rain damages on JNSG road KM 76/00 to 81/00 (SH: Construction of R/Wall in PCC 1:5:10 at RD 76/330 to 76/333) Under PDNA                              | 184005/-                | 3680/-                 | 15 Days   |
| 8     | Restoration of rain damages on Fithu Ka Parua Kumardha road KM 0/00 to 1/300 (SH: Construction of R/Wall in PCC 1:5:10 at RD 0/060 to 0/063) Under PDNA              | 68837/-                 | 1377/-                 | One Month |
| 9     | Restoration of rain damages on Chandesh Kolni Dhalwan road AKM 0/00 to 14/00 (SH: Construction of edge wall in PCC 1:5:10 at RD 13/230 to 13/236) Under PDNA         | 246093/-                | 4925/-                 | 15 Days   |
| 10    | Restoration of rain damages on Bharnal Nalla Ra Gehra Kolni road KM 0/00 to 3/500 (SH: Construction of edge wall in PCC 1:5:10 at RD 1/620 to 1/626) Under PDNA      | 83843/-                 | 1680/-                 | One Month |
| 11    | Restoration of rain damages on Goverta to Kass road KM 0/00 to 6/00 (SH: Construction of edge wall in PCC 1:5:10 at RD 3/340 to 3/346) Under PDNA                    | 113343/-                | 2270/-                 | 15 Days   |
| 12    | Restoration of rain damages on Amblagaloo Chowh Andhrara road KM 0/00 to 8/500 (SH: Construction of edge wall in PCC 1:5:10 at RD 1/160 to 1/166) Under PDNA         | 145793/-                | 2920/-                 | 15 Days   |
| 13    | Restoration of damages on Kalthari Tikkari Ropa Thathar road KM 0/00 to 6/00 (SH: Strengthening of berms in KM 0/500 to 0/880) Under PDNA                            | 484490/-                | 9690/-                 | One Month |
| 14    | Restoration of rain damages on Patti Kukain via Jajar road KM 0/00 to 3/765 (SH: Construction of wire crate R/Wall at KM 3/300 to 3/320) Under PDNA                  | 349440/-                | 7000/-                 | One Month |
| 15    | Restoration of rain damages on Patti Kukain via Jajar road KM 0/00 to 3/765 (SH: Construction of 900 mm dia HPC with both side wing wall at KM 3/300) Under PDNA     | 263639/-                | 5300/-                 | One Month |

Executive Engineer,  
Sarkaghat Division,  
HP PWD, Sarkaghat

No.PW-SKT-CB-Tender/2026-27 :-

Copy forwarded to the following for information and necessary action:-

1. The Superintending Engineer, Dharampur Circle, HP PWD for information please.
2. Notice Board.

Dated:- 13-10-2026

Executive Engineer,  
Sarkaghat Division,  
HP.PWD, Sarkaghat,

**HIMACHAL PRADESH**

**PUBLIC WORKS DEPARTMENT**

**No. PW-SKT-CB-Tender/2026-27-**

14674-75

**Dated:-** 13-10-2026

**To**

The Chief Engineer,  
Hamirpur Zone,  
HP PWD Hamirpur.


**Subject:**

**Publication of Tender.**

Sir,

Enclosed please find herewith the Tender Notice of works as given in the notice inviting tender for uploading on department website as per notification Principal Secretary (PW) to the Govt. of HP letter No. PBW(B)A(3)1/2024 dated Shimla-2 the 03.01.2024 and No. PBW (B)A(3) 8/2025-300858 dated 13<sup>th</sup> Nov, 2025 as the works mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice inviting Tender.

  
Executive Engineer,  
Sarkaghat Division,  
HP.PWD. Sarkaghat.

Copy along with N.I.T. to the Superintending Engineer, Dharampur Circle, HPPWD Dharampur for information please.

  
Executive Engineer,  
Sarkaghat Division,  
HP.PWD. Sarkaghat.

19/08/24

101082

# Draft Schedule of Quantity

Name of work:-Resoration of rain damages on Patrighat Goverta Road km 0/00 to 6/0 (Sh:-Construction of edge wall in PCC 1:5:10 at RD 0/910 to 0/916) UNDER PDNA

| Sr. No. | Description of item                                                                                                                                                                                                                                                                                                                                                                                                                                    | Quantity | Rate (excluding GST) |                                                     | Unit            | Amount |
|---------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|----------------------|-----------------------------------------------------|-----------------|--------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                        |          | In figure            | In words                                            |                 |        |
| 1       | Trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical sepecification Clause 1914 and direction of Engineer-in-charge.                                                                                                                                                                                                                                                                 | 12500    | 5.90                 | Rupees five and paise ninetyonly                    | Per sqm         | 73750  |
| 2       | Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (Thirty centimetre) in depth, 1.5 m (One point five five) metrein width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge All kinds of soil including carriage of materials with in all leads and lifts and direction of Engineer-in- | 1.50     | 170.00               | Rupees one hundred seventy and paise nil only       | Per cubic metre | 255    |
| 3       | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:5:10 One Cement : five coarse sand : 10 graded stone aggregate 40 mm(Forty millimetre) nominal size including carriage of materials with in all leads and lifts and direction of Engineer- in- Charge.                                                                                             | 9.67     | 4068.00              | Rupees four thousand sixty eight and paise nil only | Per Cubic Metre | 39338  |
| Total:- |                                                                                                                                                                                                                                                                                                                                                                                                                                                        |          |                      |                                                     |                 | 113343 |

DNIT NO 518 for the year 2026-27  
 approved for Rs 113343/-only

Executive Engineer  
 B&R Division HPTMD  
 Sarnarhat

Page 18

(2)

**Draft Schedule of Quantity**

Name of work:-Resoration of rain damages on Ratti Kalkhar Bhambla Una Road km 38/700 to 41/300 (Sh:-  
Construction of R/ wall in PCC 1:5:10 at RD 38/990 to 39/993) UNDER PDNA

Estimated Cost:- Rs.100933/-

Earnest money:- Rs.2020/-

Time allowed:- fifteen Days

| Sr. No. | Description of item                                                                                                                                                                                                                                                                                                                                                                                                                                            | Quantity | Rate (excluding GST) |                                                     | Unit            | Amount |
|---------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|----------------------|-----------------------------------------------------|-----------------|--------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                |          | In figure            | In words                                            |                 |        |
| 1       | Trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical sepecification Clause 1914 and direction of Engineer-in-charge.                                                                                                                                                                                                                                                                         | 8320     | 5.90                 | Rupees five and paise ninetyonly                    | Per sqm         | 49088  |
| 2       | Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (Thirty centimetre) in depth, 1.5 m (One point five five) metrein width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge All kinds of soil including carriage of materials with in all leads and lifts and direction of Engineer-in- Charge. | 7.29     | 170.00               | Rupees one hundred seventy and paise nil only       | Per cubic metre | 1239   |
| 3       | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:5:10 One Cement : five coarse sand : 10 graded stone aggregate 40 mm(Forty millimetre) nominal size including carriage of materials with in all leads and lifts and direction of Engineer-in- Charge.                                                                                                      | 12.44    | 4068.00              | Rupees four thousand sixty eight and paise nil only | Per Cubic Metre | 50606  |
| Total:- |                                                                                                                                                                                                                                                                                                                                                                                                                                                                |          |                      |                                                     |                 | 100933 |

DNT NO S20 for the year 2026-27  
approved for RS 100933/- only

Executive Engineer  
BAR Division HPP/ID  
Sarkisheer

Page 1/1

(3)

### Draft Schedule of Quantity

Name of work:-Resoration of rain damages on Patrighat Jawali Gehra Road km 0/00 to 14/0 (Sh:-Construction of edge wall in PCC 1:5:10 at RD 3/680 to 3/686) UNDER PDNA

| Sr. No. | Description of item                                                                                                                                                                                                                                                                                                                                                                                                                                           | Quantity | Rate (excluding GST) |                                                     | Unit            | Amount |
|---------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|----------------------|-----------------------------------------------------|-----------------|--------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                               |          | In figure            | In words                                            |                 |        |
| 1       | Trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical specification Clause 1914 and direction of Engineer-in-charge.                                                                                                                                                                                                                                                                         | 35000    | 5.90                 | Rupees five and paise ninety only                   | Per sqm         | 206500 |
| 2       | Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (Thirty centimetre) in depth, 1.5 m (One point five five) metre in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge All kinds of soil including carriage of materials with in all leads and lifts and direction of Engineer-in-charge | 1.50     | 170.00               | Rupees one hundred seventy and paise nil only       | Per cubic metre | 255    |
| 3       | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 One Cement : five coarse sand : 10 graded stone aggregate 40 mm(Forty millimetre) nominal size including carriage of materials with in all leads and lifts and direction of Engineer-in-charge.                                                                                                     | 9.67     | 4068.00              | Rupees four thousand sixty eight and paise nil only | Per Cubic Metre | 39338  |
| Total:- |                                                                                                                                                                                                                                                                                                                                                                                                                                                               |          |                      |                                                     |                 | 246093 |

DNR NO 526 for the year 2026-27  
approved for Rs 246093/- only

Executive Engineer  
B&R Division HPPW  
Sardar

# Draft Schedule of Quantity

Name of work:-Resoration of rain damages on Kalthari Tikkari Ropa Thathar Batail Road km 0/00 to 7/300 (Sh:-  
Construction of R/ wall in PCC 1:5:10 at RD 4/875 to 4/878) UNDER PDNA

Estimated Cost:- Rs. 150965/-/-

Earnest money:- Rs. 3019/-/-

Time allowed:- fifteen Days

| Sr. No. | Description of item                                                                                                                                                                                                                                                                                                                                                                                                                                          | Quantity | Rate (excluding GST) |                                                     | Unit            | Amount        |
|---------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|----------------------|-----------------------------------------------------|-----------------|---------------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                              |          | In figure            | In words                                            |                 |               |
| 1       | Trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical sepecification Clause 1914 and direction of Engineer-in-charge.                                                                                                                                                                                                                                                                       | 16800    | 5.90                 | Rupees five and paise ninetyonly                    | Per sqm         | 99120         |
| 2       | Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (Thirty centimetre) in depth, 1.5 m (One point five five) metrein width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge All kinds of soil including carriage of materials with in all leads and lifts and direction of Engineer-in-charge | 7.29     | 170.00               | Rupees one hundred seventy and paise nil only       | Per cubic metre | 1239          |
| 3       | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1.5:10 One Cement : five coarse sand : 10 graded stone aggregate 40 mm(Forty millimetre) nominal size including carriage of materials with in all leads and lifts and direction of Engineer-in- Charge.                                                                                                    | 12.44    | 4068.00              | Rupees four thousand sixty eight and paise nil only | Per Cubic Metre | 50606         |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                              |          |                      |                                                     | <b>Total:-</b>  | <b>150965</b> |

DNR NO 519 for the year 2026-27  
approved for Rs 150965/-only

Executive Engineer  
B&R Division HPWD  
Sarkar

**Draft Schedule of Quantity**

Name of work:- Restoration of rain damages on Khudla Sears Samloun Kathnar Road km 0/0 to 5/500(Sh:-  
Construction of R/ wall in PCC 1:5:10 at RD 5/010 to 5/013) UNDER PDNA

| Sr. No. | Description of item                                                                                                                                                                                                                                                                                                                                                                                                                                          | Quantity | Rate (excluding GST) |                                                     | Unit            | Amount | Estimated Cost:-         |
|---------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|----------------------|-----------------------------------------------------|-----------------|--------|--------------------------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                              |          | In figure            | In words                                            |                 |        | Earnest money:-          |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                              |          |                      |                                                     |                 |        | Time allowed:-           |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                              |          |                      |                                                     |                 |        | fifteen Days             |
| 1       | Trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical sepecification Clause 1914 and direction of Engineer-in-charge.                                                                                                                                                                                                                                                                       | 12960    | 5.90                 | Rupees five and paise ninetyonly                    | Per sqm         | 76464  | Rs.128309/-<br>Rs.2566/- |
| 2       | Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (Thirty centimetre) in depth, 1.5 m (One point five five) metrein width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge All kinds of soil including carriage of materials with in all leads and lifts and direction of Engineer-in-charge | 7.29     | 170.00               | Rupees one hundred seventy and paise nil only       | Per cubic metre | 1239   |                          |
| 3       | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 One Cement : five coarse sand : 10 graded stone aggregate 40 mm(Forty millimetre) nominal size including carriage of materials with in all leads and lifts and direction of Engineer- in- Charge.                                                                                                  | 12.44    | 4068.00              | Rupees four thousand sixty eight and paise nil only | Per Cubic Metre | 50606  |                          |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                              |          |                      |                                                     | Total:-         | 128309 |                          |

*DRAFT NO 521 for the year 2026-27  
approved for RS 128308/- only*

*Executive Engineer  
B&R Division HPPWD  
Sardar*

## Draft Schedule of Quantity

|                                                                                                      |  |  |  |                  |  |               |
|------------------------------------------------------------------------------------------------------|--|--|--|------------------|--|---------------|
| Name of work:-Resoration of rain damages on Dhalwan Masyani Bhanu Baldwara Road km 0/0 to 9/300/Sh:- |  |  |  | Estimated Cost:- |  | Rs.167918/-/- |
| Construction of R/ wall in PCC 1:5:10 at RD 1/180 to 1/186) UNDER PDNA                               |  |  |  | Earnest money:-  |  | Rs.3358/-     |
|                                                                                                      |  |  |  | Time allowed:-   |  | fifteen Days  |

| Sr. No. | Description of item                                                                                                                                                                                                                                                                                                                                                                                                                                    | Quantity | Rate      |                                                     | Unit            | Amount |
|---------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----------|-----------------------------------------------------|-----------------|--------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                        |          | In figure | In words                                            |                 |        |
| 1       | Trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical sepecification Clause 1914 and direction of Engineer-in-charge.                                                                                                                                                                                                                                                                 | 21750    | 5.90      | Rupees five and paise ninetyonly                    | Per sqm         | 128325 |
| 2       | Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (Thirty centimetre) in depth, 1.5 m (One point five five) metrein width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge All kinds of soil including carriage of materials with in all leads and lifts and direction of Engineer-in- | 1.50     | 170.00    | Rupees one hundred seventy and paise nil only       | Per cubic metre | 255    |
| 3       | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 One Cement : five coarse sand : 10 graded stone aggregate 40 mm(Forty millimetre) nominal size including carriage of materials with in all leads and lifts and direction of Engineer-in- Charge.                                                                                             | 9.67     | 4068.00   | Rupees four thousand sixty eight and paise nil only | Per Cubic Metre | 39338  |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                        |          |           |                                                     | Total:-         | 167918 |

DNIT NO 592 for the year 2026-27  
approved for Rs 167918/-

Executive Engineer  
B&R Division HPPWD  
Sarkarabari

## Draft Schedule of Quantity

Name of work:- Restoration of rain damages on JNSG Road km 76/0 to 81/0(Sh):-Construction of R/ wall in PCC  
1:5:10 at RD 76/330 to 76/333) UNDER PDNA

| Sr. No. | Description of item                                                                                                                                                                                                                                                                                                                                                                                                                                          | Quantity | Rate (excluding GST) |                                                     | Unit            | Amount        |
|---------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|----------------------|-----------------------------------------------------|-----------------|---------------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                              |          | In figure            | In words                                            |                 |               |
| 1       | Trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical sepecification Clause 1914 and direction of Engineer-in-charge.                                                                                                                                                                                                                                                                       | 22389.9  | 5.90                 | Rupees five and paise ninetyonly                    | Per sqm         | 132159        |
| 2       | Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (Thirty centimetre) in depth, 1.5 m (One point five five) metrein width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge All kinds of soil including carriage of materials with in all leads and lifts and direction of Engineer-in-charge | 7.29     | 170.00               | Rupees one hundred seventy and paise nil only       | Per cubic metre | 1239          |
| 3       | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:5:10 One Cement : five coarse sand : 10 graded stone aggregate 40 mm(Forty millimetre) nominal size including carriage of materials with in all leads and lifts and direction of Engineer-in- Charge.                                                                                                    | 12.44    | 4068.00              | Rupees four thousand sixty eight and paise nil only | Per Cubic Metre | 50606         |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                              |          |                      |                                                     | <b>Total:-</b>  | <b>184005</b> |

DNT NO 523 for the Year 2026-27  
approved for Rs 184005/-

~~Executive Engineer  
B&R Division HPT/ID  
Santosh~~

## Draft Schedule of Quantity

Name of work:- Resoration of rain damages on Fithu Ka Parua Kumardha Road km 0/0 to 1/300 (Sh:- Construction of R/ wall in FCC 1:5:10 at RD 0/060 to 0/063) UNDER PDNA

Estimated Cost:- Rs. 68837/-

Earnest money:- Rs. 1377/-

Time allowed:- fifteen Days

| Sr. No. | Description of item                                                                                                                                                                                                                                                                                                                                                                                                                                            | Quantity | Rate      |                                                     | Unit            | Amount |
|---------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----------|-----------------------------------------------------|-----------------|--------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                |          | In figure | In words                                            |                 |        |
| 1       | Trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical specification Clause 1914 and direction of Engineer-in-charge.                                                                                                                                                                                                                                                                          | 2880     | 5.90      | Rupees five and paise ninetyonly                    | Per sqm         | 16992  |
| 2       | Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (Thirty centimetre) in depth, 1.5 m (One point five five) metre in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge All kinds of soil including carriage of materials with in all leads and lifts and direction of Engineer-in-charge. | 7.29     | 170.00    | Rupees one hundred seventy and paise nil only       | Per cubic metre | 1239   |
| 3       | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 One Cement : five coarse sand : 10 graded stone aggregate 40 mm (Forty millimetre) nominal size including carriage of materials with in all leads and lifts and direction of Engineer-in-charge.                                                                                                     | 12.44    | 4068.00   | Rupees four thousand sixty eight and paise nil only | Per Cubic Metre | 50606  |
| Total:- |                                                                                                                                                                                                                                                                                                                                                                                                                                                                |          |           |                                                     |                 | 68837  |

DNIT NO 524 for the year 2026-27  
approved for Rs 68837/- only

  
 Executive Engineer  
 P&R Division HPPWD  
 Saranath

9

# Draft Schedule of Quantity

Name of work:-Resoration of rain damages on Chandesh Kolni Dhalwan Road km 0/00 to 14/0 (Sh:-Construction of edge wall in PCC 1:5:10 at RD 13/230 to 13/236) UNDER PDNA

| Sr. No. | Description of item                                                                                                                                                                                                                                                                                                                                                                                                                                          | Quantity | Rate (excluding GST) |                                                     | Unit            | Amount |
|---------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|----------------------|-----------------------------------------------------|-----------------|--------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                              |          | In figure            | In words                                            |                 |        |
| 1       | Trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical sepecification Clause 1914 and direction of Engineer-in-charge.                                                                                                                                                                                                                                                                       | 35000    | 5.90                 | Rupees five and paise ninetyonly                    | Per sqm         | 206500 |
| 2       | Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (Thirty centimetre) in depth, 1.5 m (One point five five) metrein width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge All kinds of soil including carriage of materials with in all leads and lifts and direction of Engineer-in-charge | 1.50     | 170.00               | Rupees one hundred seventy and paise nil only       | Per cubic metre | 255    |
| 3       | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:5:10 One Cement : five coarse sand : 10 graded stone aggregate 40 mm(Forty millimetre) nominal size including carriage of materials with in all leads and lifts and direction of Engineer-in- Charge.                                                                                                    | 9.67     | 4068.00              | Rupees four thousand sixty eight and paise nil only | Per Cubic Metre | 39338  |
| Total:- |                                                                                                                                                                                                                                                                                                                                                                                                                                                              |          |                      |                                                     |                 | 246093 |

DNR NO 525 for the year 2026-27  
approved for RS 246093/- only

Executive Engineer  
B&R Division HPPWD  
Sardar

# **Draft Schedule of Quantity**

**Name of work:-Resoration of rain damages on Bharnal Nalla Ra Gehra Kolni Road km 0/00 to3/500**  
**(Sh:-Construction of edge wall in PCC 1:5:10 at RD 1/620 to 1/626) UNDER PDNA**

| Name of work:-Resoration of rain damages on Bharnal Nalla Ra Gehra Kolni Road km 0/00 to3/500 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |          |                      |                                                     |                 |        | Estimated Cost:- |  |
|-----------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|----------------------|-----------------------------------------------------|-----------------|--------|------------------|--|
| (Sh:-Construction of edge wall in PCC 1:5:10 at RD 1/620 to 1/626) UNDER PDNA                 |                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |          |                      |                                                     |                 |        | Earnest money:-  |  |
|                                                                                               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |          |                      |                                                     |                 |        | Rs.1680/-        |  |
| Sr. No.                                                                                       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |          |                      |                                                     |                 |        | Time allowed:-   |  |
| Description of item                                                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |          |                      |                                                     |                 |        | one months.      |  |
| Sr. No.                                                                                       | Description of item                                                                                                                                                                                                                                                                                                                                                                                                                                             | Quantity | Rate (excluding GST) |                                                     | Unit            | Amount |                  |  |
|                                                                                               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |          | In figure            | In words                                            |                 |        |                  |  |
| 1                                                                                             | Trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical sepecification Clause 1914 and direction of Engineer-in-charge.                                                                                                                                                                                                                                                                          | 7500     | 5.90                 | Rupees five and paise ninetyonly                    | Per sqm         | 44250  |                  |  |
| 2                                                                                             | Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (Thirty centimetre) in depth, 1.5 m (One point five five) metrein width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge All kinds of soil including carriage of materials with in all leads and lifts and direction of Engineer- in- Charge. | 1.50     | 170.00               | Rupees one hundred seventy and paise nil only       | Per cubic metre | 255    |                  |  |
| 3                                                                                             | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:5:10 One Cement : five coarse sand : 10 graded stone aggregate 40 mm(Forty millimetre) nominal size including carriage of materials with in all leads and lifts and direction of Engineer- in- Charge.                                                                                                      | 9.67     | 4068.00              | Rupees four thousand sixty eight and paise nil only | Per Cubic Metre | 39338  |                  |  |
|                                                                                               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |          |                      |                                                     | Total:-         | 83843  |                  |  |

*Duit no set for the year 2026.27  
 approved for Rs 83843/-only*

*Executive Engineer  
 BAR DIVISION HPPND  
 Sarangpur*

# Draft Schedule of Quantity

Name of work:- Resoration of rain damages on Goverta to Kass Road km 0/0 to 6/00(Sh:-Construction of edge wall in PCC 1:5:10 at RD 3/340 to 3/346) UNDER PDNA

| Sr. No. |                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Description of item | Quantity | Rate                                                |                 | Unit  | Amount | Estimated Cost:-            |  |
|---------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------|----------|-----------------------------------------------------|-----------------|-------|--------|-----------------------------|--|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                               |                     |          | In figure                                           | In words        |       |        | Earnest money:-             |  |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                               |                     |          |                                                     |                 |       |        | Rs.2270/-                   |  |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                               |                     |          |                                                     |                 |       |        | Time allowed:- fifteen Days |  |
| 1       | Trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical sepecification Clause 1914 and direction of Engineer-in-charge.                                                                                                                                                                                                                                                                        | 12500               | 5.90     | Rupees five and paise ninetyonly                    | Per sqm         | 73750 |        | Rs.113343/-                 |  |
| 2       | Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (Thirty centimetre) in depth, 1.5 m (One point five five) metrein width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge All kinds of soil including carriage of materials with in all leads and lifts and direction of Engineer-in-charge. | 1.50                | 170.00   | Rupees one hundred seventy and paise nil only       | Per cubic metre | 255   |        |                             |  |
| 3       | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:5:10 One Cement : five coarse sand : 10 graded stone aggregate 40 mm(Forty millimetre) nominal size including carriage of materials with in all leads and lifts and direction of Engineer-in- Charge.                                                                                                     | 9.67                | 4068.00  | Rupees four thousand sixty eight and paise nil only | Per Cubic Mete  | 39338 |        |                             |  |
| Total:- |                                                                                                                                                                                                                                                                                                                                                                                                                                                               |                     |          |                                                     |                 |       | 113343 |                             |  |

DNIT NO 528 for the year 2026-27  
approved for Rs 113,343/-only


Executive Engineer  
B&R Division HPTND  
Sarkar

### Draft Schedule of Quantity

Name of work:-Resoration of rain damages on Amblagaloo Chowk Andhrara Road km 0/00 to 8/500 (Sh.-  
Construction of edge wall in PCC 1:5:10 at RD 1/160 toll/66) UNDER PDNA

| Sr. No. | Description of item                                                                                                                                                                                                                                                                                                                                                                                                                                             | Quantity | Rate      |                                                     | Unit            | Amount |
|---------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----------|-----------------------------------------------------|-----------------|--------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |          | In figure | (excluding GST)                                     |                 |        |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |          |           | In words                                            |                 |        |
| 1       | Trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical specification Clause 1914 and direction of Engineer-in-charge.                                                                                                                                                                                                                                                                           | 18000    | 5.90      | Rupees five and paise ninetyonly                    | Per sqm         | 106200 |
| 2       | Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (Thirty centimetre) in depth, 1.5 m (One point five five) metrein width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge All kinds of soil including carriage of materials with in all leads and lifts and direction of Engineer- in- Charge. | 1.50     | 170.00    | Rupees one hundred seventy and paise nil only       | Per cubic metre | 255    |
| 3       | Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 One Cement : five coarse sand : 10 graded stone aggregate 40 mm(Forty millimetre) nominal size including carriage of materials with in all leads and lifts and direction of Engineer- in- Charge.                                                                                                     | 9.67     | 4068.00   | Rupees four thousand sixty eight and paise nil only | Per Cubic Metre | 39338  |
| Total:- |                                                                                                                                                                                                                                                                                                                                                                                                                                                                 |          |           |                                                     |                 | 145793 |

DNIT NO 529 for the year 2026-27  
Approved for Rs 145793/- only

  
 Executive Engineer  
 B&R Division HPPWD  
 Saranath

# Draft Schedule of Quantity

Name of work :- Restoration of damages on Kalthari Tikkari Ropa Thathar road km 0/0 to 6/0 (SH:- Strengthening of berms in km 0/500 to 0/880) UNDER PDNA

| Name of work :-Restoration of damages on Kalthari Tikkari Ropa Thathar road km 0/0 to 6/0(Sh:- Strengthening of berms in km 0/500 to 0/880) UNDER PDNA |  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |          |                      |                                                               |                   |           |                |  |
|--------------------------------------------------------------------------------------------------------------------------------------------------------|--|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|----------------------|---------------------------------------------------------------|-------------------|-----------|----------------|--|
| Sr. No.                                                                                                                                                |  | Description of item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | Quantity | Rate (excluding GST) |                                                               | Estimated cost :- |           | Time allowed:- |  |
|                                                                                                                                                        |  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |          | In figure            | In words                                                      | Earnest money:-   | One month |                |  |
| 1                                                                                                                                                      |  | Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm ( Thirty centimetre) in depth, 1.5 m ( One point five metre) in width as well as 10 sqm ( Ten square metre) on plan) including getting out and disposal of excavated earth lead upto 50 m fifty metre) and lift upto 1.5 m( One point five metre), including all leads and lifts and as per the direction of Engineer- in-Charge.                                                                                                                  | 38.00    | 170.00               | Rupees one hundred seventy and paise nil only                 | Per cubic metre   | 6460      |                |  |
| 2                                                                                                                                                      |  | Providing, laying, spreading and compacting stone aggregates of 63mm to 45mm (sixty three millimetre to forty five millimetre) nominal size to water bound macadam specifications including in uniform thickness, hand packing, rolling with smooth wheel roller 80-100kN ( eighty to hundred kN ) in stages to proper grade and camber, applying and brooming, stone screening and binding materials to fillup the interstices of coarse aggregate, watering and compacting to the required density grading-III as per technical specifications clause 405 by | 28.50    | 2373.00              | Rupees two thousand nine hundred sixty six and paise nil only | Per cubic metre   | 67630     |                |  |
| 3                                                                                                                                                      |  | Providing and laying cement concrete of specified grade including the cost of centering and shuttering -All work up to plinth level: 1:1:5:3 (1cement :1.5 coarse sand) :3 graded stone aggregate 20 millimetre nominal size as per drawing and HP, PWD technical specification including carriage of materials with in all leads and lifts and direction of Engineer-in-Charge.                                                                                                                                                                               | 68.4     | 6000.00              | Rupees seven hundred twenty and paise nil only                | Per cubic metre   | 410400    |                |  |
|                                                                                                                                                        |  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |          |                      |                                                               | Total:-           | 484490    |                |  |

DNR NO 530 for the year 2026-27  
approved for Rs 484490/- only

Executive Engineer  
B&R Division HPTMD  
Sarkar

## Draft Schedule of Quantity

of work:-Restoration of rain damages on Patti Kukain via Jaljar road Km 0/0to 3/765 (SH:Construction of wire crate Rwall  
m 3/300 to 3/320) Under PDNA

Estimated Cost:- Rs 3,49,440/-  
Earnest money:- Rs. 7000/-  
Time allowed:- One Month

| Sl. No. | Description of item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | Quantity | Rate      |                                                                | Unit            | Amount |
|---------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----------|----------------------------------------------------------------|-----------------|--------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |          | In figure | In words                                                       |                 |        |
| 1       | Earth work in excavation in all kind of classification of soil in foundation of structures upto all depth/ height as per drawing and technical specification Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and back filling with approved material and disposal of all surplus excavated earth in specified site and direction of Engineer-in-charge complete.                                                                                                                | 24.60    | 170.00    | Rupees one hundred seventy and paise zero only                 | Per cubic metre | 4182   |
| 2       | Providing and laying of boulder apron laid in wire crates made with 4 mm(four millimetre) dia GI wire conforming to IS:280 (IS : Two hundred eighty) and IS : 4826 (IS : four thousand eight hundred twenty six) in 100mm x100mm (one hundred millimetre into one hundred millimetre) mesh (weaved diagonally) including 10% (ten per cent) extra for laps and joints laid with stone boulders weighting not less than 25 kg (Twenty five kilogramme) including carriage of materials with in all leads and lifts complete in all respects as per the direction Engineer -in- charge. | 112.40   | 2966.00   | Rupees two thousand nine hundred sixty six and paise zero only | Per cubic metre | 333378 |
| 3       | Back filling behind retaining walls, breast walls, abutments, wing walls and return walls complete as per drawing and technical specifications clause 1204.3.8 in all leads and lifts and carriage of materials by all modes of transportation and as per direction of Engineer-in-Charge.                                                                                                                                                                                                                                                                                            | 16.50    | 720.00    | Rupees seven hundred twenty and paise zero only                | Per cubic metre | 11880  |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |          |           |                                                                |                 | 349440 |

BRI No-5/6 for the year 2026-27  
approved for amounting to Rs. 349440/-

Execd: Engineer  
B&R Division H.P.PWD  
Sarkaphor

**Draft Schedule of Quantity**  
**of work:- Restoration of rain damages on Patti Kukain via Jajjar road Km 0/0 to 3/765 (SH:Construction of 900**  
**dia HPC with both side wing wall at Km 3/300) Under PDNA**

Estimated cost :- Rs. 2,63,639/-

Earnest money:- Rs. 5300/-  
 Time allowed:- One months

| Sr.No | Description of item/Sub Head                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | Quantity | Rates     |                                                                   | Unit              | Amount |
|-------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----------|-------------------------------------------------------------------|-------------------|--------|
|       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |          | In Figure | In words                                                          |                   |        |
| 1     | Earth work in excavation in all kind of classification of soil in foundation of structures upto all depth/ height as per drawing and technical specification Clause 1104 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and back filling with approved material and disposal of all surplus excavated earth in specified site and direction of Engineer-in-charge complete.                                                      | 50.85    | 170.00    | Rupees one hundred seventy and paise zero only                    | Per cubic metre   | 8645   |
| 2     | Providing and laying cement concrete plain/ reinforced concrete 1:4:8 (one cement : four sand : eight graded crushed stone aggregate 40mm ( forty millimetre) nominal size) in open foundation complete as per drawing and technical specification clause 802,803,1202 and 1203 including form work for plain/ reinforced concrete work as per drawing and HP,PWD technical specification including carriage of materials with in all leads and lifts and direction of Engineer- in- Charge.                               | 6.28     | 4406.00   | Rupees four thousand four hundred six and paise zero only         | Per cubic metre   | 27670  |
| 3     | Providing and laying cement concrete plain/ reinforced concrete 1:3:6 (one cement : three sand : six graded crushed stone aggregate 40mm ( forty millimetre) nominal size) in open foundation complete as per drawing and technical specification clause 802,803,1202 and 1203 including form work for plain/ reinforced concrete work as per drawing and HP,PWD technical specification including carriage of materials with in all leads and lifts and direction of Engineer- in- Charge.                                | 12.38    | 4661.00   | Rupees four thousand six hundred sixty one and paise zero only    | Per cubic metre   | 57703  |
| 4     | Providing and laying cement concrete 1:5:10 ( One cement: Five sand: Ten graded crushed stone aggregate 40mm (Forty millimeters) Nominal size with 15% plum(fifteen percent) the size of plums shall usually be 150mm to 300mm (One hundred fifty to three hundred millimetres) as per PWD specification in all heights and curing complete including cost of form work in retaining wall/ breast walls including entire carriage of materials with in all leads and lifts complete.                                       | 32.80    | 4067.00   | Rupees four thousand sixty seven and paise zero only              | Per cubic metre   | 133398 |
| 5     | Providing and laying 900mm dia (nine hundred millimetre diameter) reinforced cement concrete pipe NP-2 for culverts in first class bedding of granular material in single row if fixing collar with cement mortar 1:2 One cement :Two Mortar) but including excavation protection work back filling concrete and masonry work in heas walls and parapets clause 1108 in all heights/depth a technical specification 1108 including carriage of materials with in all leads and lifts and direction of Engineer-in- Charge. | 7.50     | 3559.00   | Rupees three thousand five hundred fifty nine and paise zero only | Per running metre | 26693  |

|   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |      |        |                                                 |                 |        |
|---|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|--------|-------------------------------------------------|-----------------|--------|
|   | Back filling behind retaining walls, breast walls, abutments, wing walls and return walls complete as per drawing and technical specifications clause 1204.3.8 in all leads and lifts and carriage of materials by all modes of transportation and as per direction of Engineer-in-Charge.                                                                                                                                                                                                       | 9.72 | 720.00 | Rupees seven hundred twenty and paise zero only | Per cubic metre | 6998   |
| 7 | Providing weep holes in brick masonry / Stone masonry / plain/reinforced concrete in retaining walls, breast walls and the like with 100mm ( One hundred ) dia PVC pipe extending through the full width of the structure with slope of 1 vertical : 20 horizontal towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 in all leads and lifts and carriage of material by all modes of transportation as per the direction of Engineer- in-Charge. | 12   | 211.00 | Rupees two hundred eleven and paise zero only   | Each            | 2532   |
|   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |      |        |                                                 | Total:-         | 263639 |

AMT No 517 for the year 2026-27  
 approved for amounting to Rs. 263639 only

~~Executive Engineer~~  
 B & R Division H.P.P.W.D  
 Sarkaghat