



HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NO:-PW-SD-CB/Tender/NIT/2020-Vol-XI-
To

4788-94

Dated:- 13/10/2026

The Executive Engineer (IT) Cell,
HP. PWD, Nirman Bhawan, Nigam Vihar,
HP. PWD, Shimla -2.

Subject: - Regarding publication of Tender notice on departmental website.
Sir,

With reference to the notification issued by the Secretary (PW) to the Government of Himachal Pradesh No. PWD-A0(3) 1/2024-241828 dt. Shimla-2 the 18/09/2025. Enclosed please find herewith the copy of tender notice for the publishing on departmental website.

Certified that the work mentioned in the Tender Notice are urgent in nature.

Encl:-As above.


Executive Engineer,
Spiti B&R Division,
HP. PWD, Kaza.

Copy forwarded to the following for information and necessary action to :-

1. The Additional Deputy Commissioner, Spiti at Kaza District Lahaul & Spiti.
2. The Chief Engineer (SZ), HP.PWD., Nirman Bhawan Nigam Vihar Shimla.
3. The Superintending Engineer, 11th Circle HP.PWD., Rampur District Shimla.
4. All the Assistant Engineer, working under this Division.
5. The Drawing Branch of this Office.
6. Notice Board.


Executive Engineer,
Spiti B&R Division,
HP. PWD, Kaza.

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDER

Sealed rate/percentage rate tenders are hereby invited by the Executive Engineer, Spiti B&R Division, HP.PWD; Kaza on behalf of the Governor of Himachal Pradesh for the below noted works from eligible Contractors registered in H.P.P.W.D. in appropriate class so as to reach in this office on or before **24/10/2026 up to 11:00 AM** and the same shall be opened on the same day at **11.30 AM** in the presence of the Contractors or their authorized representatives who may be present. The tender forms can be had from this office against cash payment (Non Refundable) on **23/10/2026 up to 4:00 PM** and the application for issue of tender form shall be received on **22/10/2026 up to 4:00 PM**.


The tender shall accompany with earnest Money which should be in the shape of NSC/Time Deposit/Saving Bank account in the Post Office/bank in H.P. duly pledged in the favour of undersigned. Conditional tenders, telegraphic and tender without earnest money will not be entertained. The Executive Engineer, Spiti B&R Division, HP.PWD; Kaza reserves the right to accept or reject the tenders. The tender shall remain valid for 75 days from the date of opening of the tenders.

Sr. No	Name of Work	Estimated Cost	Earnest Money	Time
1.	C/O ASMB Road km 0/00 to 62/00 (SH: Formation Cutting 5/7 meter wide at Km 56/120 to 56/225.	4,98,844/-	10,000/-	Two Months
2.	C/O ASMB Road km 0/00 to 62/00 (SH: Formation Cutting 5/7 meter wide at Km 56/225 to 56/450.	4,95,030/-	10,000/-	Two Months
3.	C/O ASMB Road km 0/00 to 62/00 (SH: Formation Cutting 5/7 meter wide at Km 56/450 to 56/795.	4,97,833/-	10,000/-	Two Months
4.	C/O ASMB Road km 0/00 to 62/00 (SH: Formation Cutting 5/7 meter wide at Km 56/795 to 57/230.	4,97,557	10,000/-	Two Months
5.	C/O ASMB Road km 0/00 to 62/00 (SH: Formation Cutting 5/7 meter wide at Km 57/230 to 57/575.	4,96,547	10,000/-	Two months
6.	C/O ASMB Road km 0/00 to 62/00 (SH: Formation Cutting 5/7 meter wide at Km 57/575 to 57/890.	4,95,490/-	10,000/-	Two months


Executive Engineer,
Spiti B&R Division,
HP. PWD, Kaza.

TERMS AND CONDITIONS:-

1. The Contractor/Firm shall have his/their PAN, GST No. & copy of the same be attached with the application.
2. The intending Contractor/Firm Should have attached copy of registration/renewal, copy of registration under EPF & miscellaneous provision Act-1952 with application.
3. The intending Contractors are requested to see the site of the work before submitting the tender.
4. Tender forms for two works only shall be issued to each Contractor who has no previous pending works.
5. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reasons.


Executive Engineer,
Spiti B&R Division,
HP. PWD, Kaza.

DRAFT SCHEDULE OF QUANTITY

Name of work:- C/O ASMB Road km 0/00 to 62/00 (SH: Formation Cutting 5/7 meter wide at Km 56/120 to 56/225

Estimated Cost: - 498844
Earnest Money: - 10000

Time: - Two Months

Sr. No.	Description of Item	Qty	Unit	Rate	In Figure	Amount
1	Cutting in earth work by mechanical means in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including, dewatering where ever required, setting to the required line, grades, side slopes trimming bottoms and level as shown on the drawing as directed by the Engineer-in-Charge at site according to HP.PWD specifications of 1990 (One thousand Nine hundred Ninety) Volume-1 Any loss to the public and private property during the course of execution and disposal of. Recovery for useful stone of 162.84 cubic metre @ Rs.300/- cum.(Rupees Three hundred per cubic metre) amounting to Rs.48852/- only, which shall be done on prorata basis for the quantity of cutting in earth work effected. serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects, including all incidental charges	1628.40	Per cubic metre	306.34	Rupees Three Hundred & Six Paise Thirty Four Only	498844.00
Total						498844

Sr.No. For the year 2026-27
In Words:- Rupees Four Lakh Ninety Eight Thousand Eight Hundred & Fourty
Draft Schedule of Quantity approved for Rs. 498844 / Only


Executive Engineer,
Spiti B&R Division,
H.P.P.W.D. Kara.

DRAFT SCHEDULE OF QUANTITY

					Estimated Cost: -	495030
					Earnest Money: -	10000
					Time: -	Two Months
Name of work:- C/O ASMB Road km 0/00 to 62/00 (SH: Formation Cutting 5/7 meter wide at Km 56/225 to 56/450)						
Sr. No.	Description of Item	Qty	Unit	Rate	In Figure	Amount
1	Cutting in earth work by mechanical means in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including, dewatering where ever required, setting to the required line, grades, side slopes trimming bottoms and level as shown on the drawing as directed by the Engineer-in-Charge at site according to HP.PWD specifications of 1990 (One thousand Nine hundred Ninety) Volume-1 Any loss to the public and private property during the course of execution and disposal of. Recovery for useful stone of 161.6 cubic metre @ Rs.300/- cum. (Rupees Three hundred per cubic metre) amounting to Rs.48479 /- only, which shall be done on prorata basis for the quantity of cutting in earth work effected. serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects, including all incidental charges	1615.95	Per cubic metre	306.34	Rupees Three Hundred & Six Paise Thirty Four Only	495030.00
Total						495030

Sr.No. _____ For the year 2026-27
 In Words:- Rupees Four Lakh Ninety Five Thousand & Thirty Only
 Draft Schedule of Quantity approved for Rs. 495030 / Only


 Executive Engineer,
 Spiti B&R Division,
 H.P.P.W. B. Kaza.

(3)

DRAFT SCHEDULE OF QUANTITY

DRAFT SCHEDULE OF QUANTITY						
Name of work:-C/O ASMB Road km 0/00 to 62/00 (SH: Formation Cutting 5/7 meter wide at Km 56/450 to 56/795)				Estimated Cost:-		497833
				Earnest Money:-		10000
				Time:-		Two Months
Sr. No.	Description of Item	Qty	Unit	Rate	In Figure	Amount
1	Cutting in earth work by mechanical means in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including, dewatering where ever required, setting to the required line, grades, side slopes trimming bottoms and level as shown on the drawing as directed by the Engineer-in-Charge at site according to HP.PWD specifications of 1990 (One thousand Nine hundred Ninety) Volume-1 Any loss to the public and private property during the course of execution and disposal of. Recovery for useful stone of 162.51 cubic metre @ Rs.300/- cum.(Rupees Three hundred per cubic metre) amounting to Rs.48753/- only, which shall be done on prorata basis for the quantity of cutting in earth work effected. serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects, including all incidental charges.	1625.10	Per cubic metre	306.34	Rupees Three Hundred & Six Paise Thirty Four Only	497833.00
Total						497833

Sr.No. _____ For the year 2026-27
 In Words:- Rupees Four Lakh Ninety Seven Thousand Eight Hundred & Thirty
 Draft Schedule of Quantity approved for Rs. 497833 / Only

[Signature]
 Executive Engineer,
 Spiti B&R Division,
 H.P.P.W.D. Kaza.


(4)

DRAFT SCHEDULE OF QUANTITY

Name of work:- C/O ASMB Road km 0/00 to 62/00 (SH: Formation Cutting 5/7 meter wide at Km 56/795 to 57/230)						Estimated Cost:-	497557
						Earnest Money:-	10000
						Time:-	Two Months
Sr. No.	Description of Item	Qty	Unit	Rate	In Figure	Amount	
1	Cutting in earth work by mechanical means in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including, dewatering where ever required, setting to the required line, grades, side slopes trimming bottoms and level as shown on the drawing as directed by the Engineer-in-Charge at site according to HP.PWD specifications of 1990 (One thousand Nine hundred Ninety) Volume-1 Any loss to the public and private property during the course of execution and disposal of. Recovery for useful stone of 162.42 cubic metre @ Rs.300/- cum.(Rupees Three hundred per cubic metre) amounting to Rs.48726/- only, which shall be done on prorata basis for the quantity of cutting in earth work effected. serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects, including all incidental charges.	1624.20	Per cubic metre	306.34	Rupees Three Hundred & Six Paise Thirty Four Only	497557.00	
Total						497557	

Sr.No. For the year 2026-27

In Words:- Rupees Four Lakh Ninety Seven Thousand Five Hundred & Fifty Seven
Draft Schedule of Quantity approved for Rs. 497557 / Only


Executive Engineer,
Spiti B&R Division,
H.P.P.W.D. Kaza.


DRAFT SCHEDULE OF QUANTITY

Name of work:- C/O ASMB Road km 0/00 to 62/00 (SH: Formation Cutting 5/7 meter wide at Km 57/230 to 57/575)

Estimated Cost:-	496547
Earnest Money:-	10000
Time:-	Two Month

Sr. No.	Description of Item	Qty	Unit	Rate	In Figure	Amount
1	Cutting in earth work by mechanical means in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including, dewatering where ever required, setting to the required line, grades, side slopes trimming bottoms and level as shown on the drawing as directed by the Engineer-in-Charge at site according to HP.PWD specifications of 1990 (One thousand Nine hundred Ninety) Volume-1 Any loss to the public and private property during the course of execution and disposal of. Recovery for usefull stone of 162.09 cubic metre @ Rs.300/- cum.(Rupees Three hundred per cubic metre) amounting to Rs.48627/- only, which shall be done on prorata basis for the quantity of cutting in earth work effected. serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects, including all incidental charges.	1620.90	Per cubic metre	306.34	Rupees Three Hundred & Six Paise Thirty Four Only	496547.00
Total						496547

Sr.No. _____ For the year 2026-27
In Words:- Rupees Four Lakh Ninety Six Thousand Five Hundred & Fourty Seven
Draft Schedule of Quantity approved for Rs. 496547 / Only


Executive Engineer,
Spiti B&R Division,
H.P.P.W.D. Kaza.

DRAFT SCHEDULE OF QUANTITY

Name of work:-C/O ASMB Road km 0/00 to 62/00 (SH: Formation Cutting 5/7 meter wide at Km 57/575 to 57/890)					Estimated Cost: -	465490
					Earnest Money: -	10000
					Time: -	Two Months
Sr. No.	Description of Item	Qty	Unit	Rate	In Figure	Amount
1	Cutting in earth work by mechanical means in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including, dewatering where ever required, setting to the required line, grades, side slopes trimming bottoms and level as shown on the drawing as directed by the Engineer-in-Charge at site according to HP.PWD specifications of 1990 (One thousand Nine hundred Ninety) Volume-1 Any loss to the public and private property during the course of execution and disposal of. Recovery for useful stone of 161.75 cubic metre @ Rs.300/- cum.(Rupees Three hundred per cubic metre) amounting to Rs.48524 /- only , which shall be done on prorata basis for the quantity of cutting in earth work effected. serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects, including all incidental charges.	1617.45	Per cubic metre	306.34	Rupees Three Hundred & Six Paise Thirty Four Only	495490.00
					Total	495490

In Words:- Rupees Four Lakh Ninety Five Thousand Four Hundred & Ninety
Draft Schedule of Quantity approved for Rs. 495490 / Only


Executive Engineer,
Spiti B&R Division,
H.P.P.W.D, Kaza.