

Himachal Pradesh
Public Works Department

No PW/DD/CB/Tender/2026-27:-

5600 - 06

Dated:- 7/10/2026

To

✓
The Chief Engineer (KZ),
HPPWD. Dharamshala.

Subject: -

Publication of Tender Notice.

Sir,

Enclosed please find herewith the Tender Notice of work as given in the Notice Inviting Tender for uploading on department website as per notification Pr. Sect. (PW) to the Govt. of Himachal Pradesh letter No PBW(B)A(3)1/2024 dated Shimla-2 the 03.01.2024 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA/ Notice Inviting Tender.

Chandrasekhar
Executive Engineer,
Dharamshala Division,
HPPWD Dharamshala.

Copy forwarded for information to:-

1. The Superintending Engineer 5th Circle HPPWD Palampur.
2. All the Assistant Engineer working under this Division.
3. Copy to AB/ DB of this Division.
4. Notice Board.

1
Executive Engineer,
Dharamshala Division,
HPPWD Dharamshala.



Office of Executive Engineer Dharamshala Division HPPWD Dharamshala
Himachal Pradesh Public Works Department Dharamshala -176215
Phone No.01892-224946 Fax 222065 E-mail ee-dha-hp@nic.in

"NOTICE INVITING TENDERS"

Sealed percentage rate tenders on forms 6 & 8 are hereby invited by the Executive Engineer, Dharamshala Division, HPPWD Dharamshala on emergent basis for the below mentioned works from the approved and eligible contractors enlisted in HPPWD so as to reach in his office on or before **13.10.2026** upto **11:00 AM** and the same shall be opened on the same day at **11:30 AM** in the presence of the tender opening committee and intending contractors/firms or their authorized representatives. The tender documents can be had from this office against cash payment/Non refundable) on **12.10.2026** between **2:00 PM to 5:00 PM** and the applications for issue of tender forms shall be received upto **12:30 PM on 12.10.2026**.

The Earnest Money in the shape of NSC's / FDR's Deposit/Bank Guarantee at Call of any of the Post office/Bank duly pledged in favour of XEN HPPWD, Dharamshala must be accompanied with the tender documents. Please note that no exemption orders of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will summarily be rejected. The offer of the tenders shall be kept open for 75 days. The Executive Engineer reserves the right to reject any tender or all tenders without assigning any reasons. The contractors should be registered as a dealer GST Tax Act.2018 and also produce the clearance certificate from the Excise and Taxation department and the contractor will also have to attach the labour employer licence from the labour office with the application. The tender documents shall only be issued to those contractors/firms who will produce the photo copy of their enlistment/renewal, if happens to be a holiday on the day of opening of tenders the same will be opened on the next working day at the same time and venue:-

Sr. No.	Name of Work	Estimated cost in Rs.	EMD	Time limit	Cost of Tender form
1	Annual Repair and Maintenance of Vidhan Sabha building at Tapovan (Dharamshala) in Distt. Kangra H.P. (SH:- Exterior paint work in Ministerial block building)	79,224/-	1,600/-	15 Days	350/-
2	Annual Repair and Maintenance of Vidhan Sabha building at Tapovan (Dharamshala) in Distt. Kangra H.P. (SH:-Interior painting & distempering and wood work in Ministerial block building)	91,100/-	1,800/-	15 Days	350/-
3	Annual Repair and Maintenance of Vidhan Sabha building at Tapovan (Dharamshala) in Distt. Kangra H.P. (SH:- Painting and distempering on boundary wall from Main gate No.1 to C.M. gate)	78,254/-	1,600/-	15 Days	350/-
4	Annual Repair and Maintenance of Vidhan Sabha building at Tapovan (Dharamshala) in Distt. Kangra H.P. (SH:- Painting and distempering on boundary wall from near Reception block to main gate)	77,842/-	1,600/-	15 Days	350/-
5	Annual Repair and Maintenance of Vidhan Sabha building at Tapovan (Dharamshala) in Distt. Kangra H.P. (SH:-Exterior painting work in Main Entrance gate 1 & 2)	79,151/-	1,600/-	15 Days	350/-
6	Annual Repair and Maintenance of Vidhan Sabha building at Tapovan (Dharamshala) in Distt. Kangra H.P. (SH:-Exterior painting work in Gate No. 1,3 and 4 of Main House Building)	78,293/-	1,600/-	15 Days	350/-
7	Annual Repair and Maintenance of Vidhan Sabha building at Tapovan (Dharamshala) in Distt. Kangra H.P. (SH:-Exterior painting work in Gate No. 5 and 6 of Main House Building)	78,851/-	1,600/-	15 Days	350/-
8	Annual Repair and Maintenance of Vidhan Sabha building at Tapovan (Dharamshala) in Distt. Kangra H.P. (SH:-Interior paint / Polishing work in Main House Building)	91,902/-	1,800/-	15 Days	350/-
9	Annual Repair and Maintenance of Vidhan Sabha building at Tapovan (Dharamshala) in Distt. Kangra H.P. (SH:- Interior painting work in basement area)	99,450/-	2,000/-	15 Days	350/-
10	Annual Repair and Maintenance of Vidhan Sabha building at Tapovan (Dharamshala) in Distt. Kangra H.P. (SH:- P/F woven floor mat in Main House Building)	83,808/-	1,700/-	15 Days	350/-
11	Annual Repair and Maintenance of Vidhan Sabha building at Tapovan (Dharamshala) in Distt. Kangra H.P. (SH:-Cutting / uprooting of Vegetation, grass shrubs in the courtyard and parking area of the vehicles (Near Minister block)	84,533/-	1,700/-	15 Days	350/-
12	Annual Repair and Maintenance of Vidhan Sabha building at Tapovan (Dharamshala) in Distt. Kangra H.P. (SH:- Cutting of bushes in main campus of the building)	94,400/-	1,700/-	15 Days	350/-
13	Annual Repair and Maintenance of Vidhan Sabha building at Tapovan (Dharamshala) in Distt. Kangra H.P. (SH:- C/O Bunker for Security forces with sand filled Gunny bags at various location inside the Vidhan Sabha complex)	50,850/-	1,000/-	15 Days	350/-
14	Annual Repair and Maintenance of Vidhan Sabha building at Tapovan (Dharamshala) in Distt. Kangra H.P. (SH:-Cleaning of Manhole, inspection Chamber, Sewerage lines and similar works)	82,680/-	1,700/-	15 Days	350/-
15	Annual Repair and Maintenance of Vidhan Sabha building at Tapovan (Dharamshala) in Distt. Kangra H.P. (SH:- P/L tiles flooring, paint work, sanitary and water supply installation and other similar repair works etc. in Main House building & Ministerial block)	91,341/-	1,800/-	15 Days	350/-

Certified that above work for urgent nature and require immediate execution.

(Signature)
Executive Engineer,
Dharamshala Division,
HPPWD Dharamshala.

On behalf of Governor of Himachal Pradesh.

No. PWD-DD/CB/M-34/2026-27:-

5607-46

Dated: 7/10/2026

Copy to the following for information and necessary action:-

1. The Chief Engineer (KZ) HP.PWD Dharamshala.
2. The Superintending Engineer, 5th Circle HP.PWD, Palampur.
3. The Deputy Commissioner Kangra at Dharamshala.
4. The Commissioner Dharamshala Municipal Corporation.
5. All the Executive Engineer, working under Kangra Zone.
6. The SDM & Tehsildar Dharamshala.
7. The BDO Dharamshala /Rait.
8. All the Assistant Engineers working under this Division.
9. All the Head of the Branches in this office.
10. All the Contractors working under this Division.
11. Notice Board.


Executive Engineer,
Dharamshala Division,
HPPWD Dharamshala.

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 79224.00
 EARNEST MONEY :- ₹ 1600.00
 TIME LIMIT : Fifteen days

NAME OF WORK :- Annual Repair and maintenance of Vidhan Sabha building at Tapovan Dharamshala in Distt. Kangra H.P.

SUB-HEAD :- Exterior paint work in Ministerial block building

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2 Finishing walls with Acrylic Smooth weather proof exterior paint of Asian / Dulax / Berger / Nerolac Suraksha paint of required shade old work (Two or more coat applied @ 1.67 ltr/10 sqm (one decimal sixty seven litre per ten squaremetre) over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm (two decimal twenty kilogram per ten squaremetre) , as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax or any other taxes imposed by the Government. But Excluding GST.	3	4 115.00	5 Rupees One Hundred Fifteen Only	6 Per square metre	7 79224.00
TOTAL :-						79224.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Dharamshala
 Executive Engineer,

Dharamshala Division,
 HPPWD Dharamshala

SCHEDULE OF QUANTITY

ESTIMATED COST:- ₹ 91100.00
 EARNEST MONEY :- ₹ 1800.00
 TIME LIMIT : Fifteen days

NAME OF WORK :- Annual Repair and maintenance of Vidhan Sabha building at Tapovan Dharamshala in Distt. Kangra H.P.

SUB-HEAD :- Interior Painting & distempering and wood work in Ministerial block building

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Wall painting with acrylic emulsion paint of Asian / Dulux / Berger / Nerolac Suraksha paints of approved interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour two or more coats, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax or any other taxes imposed by the Government. But Excluding GST.	483.23 Square metres	90.00	Rupees Ninety Only	Per square metre	43491.00
2	Providing and applying white cement based putty of Birla / JK average thickness 1 mm (one millimetre) over the plastered wall surface to prepare the surface even and smooth complete, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax or any other taxes imposed by the Government. But Excluding GST.	182.50 Square metres	65.00	Rupees Sixty Five Only	Per square metre	11863.00
3	Providing and fixing 18mm (Eighteen millimetre) thick Phenol Bonded (Both Sides) Prelaminated BWP Grade Partical Board in Matt Finish Flat pressed three layer or graded wood partical board conforming to IS No. 12823 of action Tesa/ Greenlam/ Merinolam/Kitlam/Vista as per ISI and approved shade Grade-I type-II in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etcetra complete as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax or any other taxes imposed by the Government. But Excluding GST.	5.13 Square metres	1150.00	Rupees One Thousand One Hundred Fifty Only	5900.00	5900.00

1	2	3	4	5	6	7
4	Painting with synthetic enamel paint Asian / Dulux / Berger / Nerolac Suraksha paints of approved brand and manufacture of required colour to give an even shade One or more coats on old work, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax or any other taxes imposed by the Government. But Excluding GST.	130.79 Square metres	80.00	Rupees Eighty Only	Per square metre	10463.00
5	Finishing walls with Acrylic Smooth weather proof exterior paint of Asian / Dulux / Berger / Nerolac Suraksha paint of required shade old work (Two or more coat applied @ 1.67 ltr/10 sqm (one decimal sixty seven litre per ten squaremetre) over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm (two decimal twenty kilogram per ten squaremetre) , as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikhana, toll tax, sale tax or any other taxes imposed by the Government. But Excluding GST.	168.55 Square metres	115.00	Rupees One Hundred Fifteen Only	Per Square metre	19383.00
TOTAL :-						91100.00
(Amount to be quoted by the contractor in Figure)						
(Amount to be quoted by the contractor in words)						
Quoted Rate in Figure (%)						
Quoted Rate in Words (%)						


 Executive Engineer,
 Dharamshala Division,
 HPPWD Dharamshala

69

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 78254.00
 EARNEST MONEY :- ₹ 1600.00
 TIME LIMIT : Fifteen days

NAME OF WORK :-

Annual Repair and maintenance of Vidhan Sabha building at Tapovan Dharamshala in Distt. Kangra H.P.

SUB-HEAD :-

Painting and distemping on boundary wall from Main gate No.1 to C.M. gate

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Finishing walls with Acrylic Smooth weather proof exterior paint of Asian / Dulax / Berger / Nerolac Suraksha paint of required shade old work (Two or more coat applied @ 1.67 ltr/10 sqm (one decimal sixty seven litre per ten squaremetre) over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm (two decimal twenty kilogram per ten squaremetre) as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax or any other taxes imposed by the Government. But Excluding GST.	680.47 Square metres	115.00	Rupees One Hundred Fifteen Only	Per square metre	78254.00
TOTAL :-						78254.00
Quoted Rate in Figure (%)						(Amount to be quoted by the contractor in Figure)
Quoted Rate in Words (%)						(Amount to be quoted by the contractor in words)

Chander Sheel
 Executive Engineer,

Dharamshala Division,
 HPPWD Dharamshala



SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 77842.00
 EARNEST MONEY :- ₹ 1600.00
 TIME LIMIT : Fifteen days

NAME OF WORK :- Annual Repair and maintenance of Vidhan Sabha building at Tapovan Dharamshala in Distt. Kangra H.P.

SUB-HEAD :- Painting and distemper on boundary wall from near Reception block to Main gate

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Finishing walls with Acrylic Smooth weather proof exterior paint of Asian / Dulax / Berger / Nerolac Suraksha paint of required shade old work (Two or more coat applied @ 1.67 ltr/10 sqm (one decimal sixty seven litre per ten squaremetre) over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm (two decimal twenty kilogram per ten squaremetre) , as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax or any other taxes imposed by the Government. But Excluding GST.	676.89 Square metres	115.00	Rupees One Hundred Fifteen Only	Per square metre	77842.00
					TOTAL :-	77842.00
Quoted Rate in Figure (%)						(Amount to be quoted by the contractor in Figure)
Quoted Rate in Words (%)						(Amount to be quoted by the contractor in words)

Chandrasekhar
 Executive Engineer,
 Dharamshala Division,
 HPPWD Dharamshala

71

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 79151.00
EARNEST MONEY :- ₹ 1600.00
TIME LIMIT : Fifteen days

NAME OF WORK :- Annual Repair and maintenance of Vidhan Sabha building at Tapovan Dharamshala in Distt. Kangra H.P.

SUB-HEAD :- Exterior painting work in Main Entrance gate 1 & 2

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Finishing walls with Acrylic Smooth weather proof exterior paint of Asian / Dulux / Berger / Nerolac Suraksha paint of required shade old work (Two or more coat applied @ 1.67 ltr/10 sqm (one decimal sixty seven litre per ten squaremetre) over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm (two decimal twenty kilogram per ten squaremetre) , as per approved drawing, design and specifications and as per directions, and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax or any other taxes imposed by the Government. But Excluding GST.	688.27 Square metres	115.00	Rupees One Hundred Fifteen Only	Per square metre	79151.00
TOTAL :-						79151.00
Quoted Rate in Figure (%)						(Amount to be quoted by the contractor in Figure)
Quoted Rate in Words (%)						(Amount to be quoted by the contractor in words)

Chander Singh
Executive Engineer,
Dharamshala Division,
HPPWD Dharamshala

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 78293.00
 EARNEST MONEY :- ₹ 1600.00
 TIME LIMIT : Fifteen days

NAME OF WORK :- Annual Repair and maintenance of Vidhan Sabha building at Tapovan Dharamshala in Distt. Kangra H.P.

SUB-HEAD :- Exterior painting work in Gate No. 1,3 and 4 of Main House Building

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	finishing walls with Acrylic Smooth weather proof exterior paint of Asian / Dulax / Berger / Nerolac Suraksha paint of required shade old work (Two or more coat applied @ 1.67 ltr/10 sqm (one decimal sixty seven litre per ten squaremetre) over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm (two decimal twenty kilogram per ten squaremetre) , as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax or any other taxes imposed by the Government. But Excluding GST.	680.81 Square metres	115.00	Rupees One Hundred Fifteen Only	Per square metre	78293.00
TOTAL :-						78293.00
<u>Quoted Rate in Figure (%)</u>		(Amount to be quoted by the contractor in Figure)				
<u>Quoted Rate in Words (%)</u>		(Amount to be quoted by the contractor in words)				

Chanderkumar
 Executive Engineer,
 Dharamshala Division,
 HPPWD Dharamshala

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 78851.00
 EARNEST MONEY :- ₹ 1600.00
 TIME LIMIT : Fifteen days

NAME OF WORK :- Annual Repair and maintenance of Vidhan Sabha building at Tapovan Dharamshala in Distt. Kangra H.P.

SUB-HEAD :- Exterior painting work in Gate No. 5 and 6 of Main House Building

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Finishing walls with Acrylic Smooth weather proof exterior paint of Asian / Dulax / Berger / Nerolac Suraksha paint of required shade old work (Two or more coat applied @ 1.67 ltr/10 sqm (one decimal sixty seven litre per ten squaremetre) over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm (two decimal twenty kilogram per ten squaremetre) , as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax or any other taxes imposed by the Government. But Excluding GST.	685.66 Square metres	115.00	Rupees One Hundred Fifteen Only	Per square metre	78851.00
TOTAL :-						78851.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure)				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in words)				

Chandrasekhar
 Executive Engineer,
 Dharamshala Division,
 HPPWD Dharamshala

74

SCHEDULE OF QUANTITY

ESTIMATED COST: ₹ 91902.00
EARNEST MONEY ₹ 1800.00
TIME LIMIT Fifteen days

NAME OF WORK :- Annual Repair and maintenance of Vidhan Sabha building at Tapovan Dharamshala in Distt. Kangra H.P.

SUB-HEAD :- Interior paint / Polishing work in Main House Building

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Wall painting with acrylic emulsion paint of Asian / Dulux / Berger / Nerolac Suraksha paints of approved interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour two or more coats, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax or any other taxes imposed by the Government. But Excluding GST.	844.92 Square metres	90.00	Rupees Ninety Only	Per square metre	76043.00
2	Polishing two coats with french polish spirit on previously wood and wood based surfaces to give an even surface including cleaning the surface of all dirt, dust, and sand papered smooth and including a coat of wood filler, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax or any other taxes imposed by the Government. But Excluding GST.	89.60 Square metres	177.00	Rupees One Hundred Seventy Seven Only	Per Square metre	15859.00
TOTAL :-						91902.00
	Quoted Rate in Figure (%)	(Amount to be quoted by the contractor in Figure				
	Quoted Rate in Words (%)	(Amount to be quoted by the contractor in				

Chandrasekhar
Executive Engineer,
Dharamshala Division,
HPPWD Dharamshala

75

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 99450.00
 EARNEST MONEY :- ₹ 2000.00
 TIME LIMIT : Fifteen days

NAME OF WORK :- Annual Repair and maintenance of Vidhan Sabha building at Tapovan Dharamshala in Distt. Kangra H.P.

SUB-HEAD :- Interior painting work in basement area

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Wall painting with acrylic emulsion paint of Asian / Dulux / Berger / Nerolac Suraksha paints of approved interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour two or more coats, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax or any other taxes imposed by the Government. But Excluding GST.	1105.00 Square metres	90.00	Rupees Ninety Only	Per square metre	99450.00
TOTAL :-						99450.00
Quoted Rate in Figure (%)		(Amount to be quoted by the contractor in Figure)				
Quoted Rate in Words (%)		(Amount to be quoted by the contractor in words)				

Chanderkumar
 Executive Engineer,
 Dharamshala Division,
 HPPWD Dharamshala

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 83808.00
 EARNEST MONEY :- ₹ 1700.00
 TIME LIMIT : Fifteen days

NAME OF WORK :- Annual Repair and Maintenance of Vidhan Sabha building at Tapovan Dharamshala in Distt. Kangra H.P.

SUB-HEAD :- Providing and fixing woven floor mat in Main-House Building

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Providing and fixing woven Floor Matt in green shade including adhesive complete in all respect as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malikana, toll tax, sale tax or any other taxes imposed by the Government. But Excluding GST.	77.60 Square metres	1080.00	Rupees One Thousand Eighty Only	Per square metre	83808.00
TOTAL :-						83808.00
(Amount to be quoted by the contractor in Figure)						
(Amount to be quoted by the contractor in words)						

Chandrasekhar
 Executive Engineer,
 Dharamshala Division,
 HPPWD-Dharamshala

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 84533.00
EARNEST MONEY :- ₹ 1700.00
TIME LIMIT : Fifteen days

NAME OF WORK :- Annual Repair and Maintenance of Vidhan Sabha building at Tapovan Dharamshala in Distt. Kangra H.P.

SUB-HEAD :- Cutting / uprooting of Vegetation, grass shrubs in the courtyard and parking area of the vehicles (Near Minister block)

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Clearing jungle including uprooting of rank vegetation, grass, bushes, brush wood, tree and saplings of girth upto 30 cm (thirty centimetre) measured at a height of 1 m (one metre) above ground and removal of rubbish upto any distance or outside the periphery of the area cleared and as per specification, approved drawing, design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana and all type of taxes imposed by the Government. But Excluding GST.	11050.00 Square metres	7.65	Rupees Seven And Paise Sixty Five Only	Per square metre	84533.00
TOTAL :-						84533.00
Quoted Rate in Figure (%)						(Amount to be quoted by the contractor in Figure)
Quoted Rate in Words (%)						(Amount to be quoted by the contractor in words)

Chandrasekhar
Executive Engineer,
Dharamshala Division,
HPPWD, Dharamshala

SCHEDULE OF QUANTITY

ESTIMATED COST :- Rs. 94400.00
 EARNEST MONEY :- Rs. 1700.00
 TIME LIMIT : Fifteen days

NAME OF WORK :- Annual Repair and Maintenance of Vidhan Sabha building at Tapovan Dharamshala in Distt. Kangra H.P.

SUB-HEAD :- Cutting of bushes in main campus of the building

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Trimming of grass and weeds from the shoulders/ berms and disposing off the same to suitable locations as per Technical clause 1914, as per direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax or other taxes imposed by the Government. But excluding GST.	4200.00 Square metres	4.50	Rupees Four And Paise Fifty Only	Per Square metre	18900.00
2	Cutting of shrubs from the road way or with in Row and disposal of the shrubs to the suitable location as per technical specification clause 1914 and as per direction of Engineer-in-Charge. including carriage of materials within all leads, lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax or other taxes imposed by the Government. But excluding GST.	15100.00 Square metres	5.00	Rupees Five Only	Per Square metre	75500.00
TOTAL :-						94400.00
<u>Quoted Rate in Figure (%)</u>						(Amount to be quoted by the contractor in Figure)
<u>Quoted Rate in Words (%)</u>						(Amount to be quoted by the contractor in words)

Chandrasekhar
 Executive Engineer,
 Dharamshala Division,
 HPPWD Dharamshala

SCHEDULE OF QUANTITY

ESTIMATED COST :- Rs. 50850.00
 EARNEST MONEY :- Rs. 1000.00
 TIME LIMIT : Fifteen days

NAME OF WORK :- Annual Repair and Maintenance of Vidhan Sabha building at Tapovan Dharanshala in Distt. Kangra H.P.

SUB-HEAD :- Construction of Bunker for Security forces with sand filled Gunny bags at various location inside the Vidhan Sabha complex

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Construction of Bunker for Security forces with sand filled Gunny bags at various location inside the Vidhan Sabha Complex, as per direction of Engineer-in-Charge. including cartage of materials within all leads, lifts and other incidentals. The rate including octroi, royalty, Malkana, toll tax or other taxes imposed by the Government. But excluding GST.	6.00 Job	8475.00	Rupees Eight Thousand Four Hundred Seventy Five Only	Per Job	50850.00
TOTAL :-						50850.00
<u>Quoted Rate in Figure (%)</u>						(Amount to be quoted by the contractor in Figure)
<u>Quoted Rate in Words (%)</u>						(Amount to be quoted by the contractor in words)

Chander Shukla
 Executive Engineer,
 Dharanshala Division,
 HPPWD Dharanshala

SCHEDULE OF QUANTITY

ESTIMATED COST :- Rs. 82680.00
 EARNEST MONEY :- Rs. 1700.00
 TIME LIMIT : Fifteen days

NAME OF WORK :- Annual Repair and maintenance of Vidhan Sabha building at Tapovan Dharamshala in Distt. Kangra H.P.,
SUB-HEAD :- Cleaning of Manhole, inspection Chamber, Sewerage lines and similar works

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Cleaning of manholes / Chambers, as per specification, approved drawing, design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana and all type of taxes imposed by the Government. But Excluding GST.	15 Numbers	4240.00	Rupees Four Thousand Two Hundred Forty Only	Each	63600.00
2	Cleaning of Inspection Chambers and water Closet, as per specification, approved drawing, design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana and all type of taxes imposed by the Government. But Excluding GST.	9 Numbers	2120.00	Rupees Two Thousand One Hundred Twenty Only	Each	19080.00
TOTAL :-						82680.00
Quoted Rate in Figure (%)						(Amount to be quoted by the contractor in Figure)
Quoted Rate in Words (%)						(Amount to be quoted by the contractor in words)

Chandrasekhar
 Executive Engineer,
 Dharamshala Division,
 HPPWD Dharamshala

SCHEDULE OF QUANTITY

ESTIMATED COST:- Rs. 91341.00
 EARNEST MONEY :- Rs. 1800.00
 TIME LIMIT : Fifteen days

NAME OF WORK :- Annual Repair and maintenance of Vidhan Sabha building at Tapovan Dharamshala in Distt. Kangra H.P.

SUB-HEAD :- Providing and Laying tiles flooring, paint work, sanitary and water supply installation and other similar repair works etc. in Main House Building & Ministerial block

S. No.	Description of Items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead for thickness of tiles 10mm to 25mm (ten millimetres to twenty five millimetres), as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana and all type of taxes imposed by the Government. But Excluding GST.	21.75 Square metres	105.00	Rupees One Hundred Five Only	Per Square metres	2284.00
2	Providing and laying 600x600 mm (six hundred millimetre) vitrified floor tiles of Restile/ Johnson/ Nitco/ Rak / Kajaria / AGL / Simpolo / Somany / Orient Bell as per approved shade and design of the office (thickness to be specified by the manufacturer) with water absorption less than 0.08% (zero decimal zero eight percentage) and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm (twenty millimetre) thick cement mortar 1:4 (one cement isto four coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm (three decimal three kilogram per squaremetre) including grouting the joints with white cement and matching pigments etcetera complete, as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana and all type of taxes imposed by the Government. But Excluding GST.	21.75 Square metres	1260.00	Rupees One Thousand Two Hundred Sixty Only	Per square metre	27405.00
3	Wall painting with acrylic emulsion paint of Asian / Dulux / Berger / Nerolac Suraksha paints of approved interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour two or more coats, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax or any other taxes imposed by the Government. But Excluding GST.	100.96 Square metres	90.00	Rupees Ninety Only	Per square metre	9086.00
4	Providing and fixing 32 mm (thirty two millimetres) dia P.V.C. flexible waste pipe of Finolex . Reipipe (Reliance) , Vectus for sink or wash basin including P.V.C. waste fittings complete, as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana and all type of taxes imposed by the Government. But Excluding GST.	20 Numbers	160.00	Rupees One Hundred Sixty Only	Each	3200.00

5	Providing and fixing aluminium extruded section body tubular type universal hydraulic door closer (having brand logo with ISI, IS : 3564, embossed on the body, door weight upto 35 Kg (thirty five kilogram) and door width upto 700mm (seven hundred millimetre) with necessary accessories and screws etcetera complete, of Dorma in three categories i.e. Commercial, standard and Premium complete, including cost and carriage of material, as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana and all type of taxes imposed by the Government. But Excluding GST.	10 Number	805.00	Rupees Eight Hundred Five Only	Each	8050.00
6	Providing and fixing 15 mm (fifteen millimetres) nominal bore C.P. brass angle valve of Continental series of Jaquar / Classic series of Hindware / Floral series of Cera / Vintage series of Kerovite & Hindon series of Jal for basin mixer and geyser points of approved quality conforming to IS-8931, including cost and carriage of material, as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana and all type of taxes imposed by the Government. But Excluding GST.	15 Numbers	980.00	Rupees Nine Hundred Eighty Only	Each	14700.00
7	Providing and fixing 15mm (Fifteen millimetres) nominal bore uplasticated PVC connection pipe with brass union 45cm (Forty five Centimetres) length of Finolex , Relpipe (Reliance) , Vectus including cost and carriage of material, as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana and all type of taxes imposed by the Government. But Excluding GST.	15 Numbers	130.00	Rupees One Hundred Thirty Only	Each	1950.00
8	Providing and fixing magnetic catcher for cup board shutters with necessary screws etcetera including cost and carriage of material, as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana and all type of taxes imposed by the Government. But Excluding GST.	6.00 Numbers	85.00	Rupees Eighty Five Only	Each	510.00
9	Providing and fixing Lock for cup board shutters with necessary screws etcetera including cost and carriage of material, as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana and all type of taxes imposed by the Government. But Excluding GST.	6.00 Numbers	220.00	Rupees Two Hundred Twenty Only	Each	1320.00
10	Providing and fixing bright finished brass hanging type rubber floor door stopper ISI marked, transparent or dyed to required colour and shade, with necessary screws etcetera complete as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkana and all type of taxes imposed by the Government. But Excluding GST.	10.00 Numbers	105.00	Rupees One Hundred Five Only	Each	1050.00

11	Repairs to plaster of thickness 12 mm to 20 mm (twelve millimetres to twenty millimetres) in patches of area 2.5 (two decimal five) sq.meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge With cement mortar 1:4 (one cement isto four fine sand) as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana and all type of taxes imposed by the Government. But Excluding GST.	33.00 Square metres	245.00	Rupees Two Hundred Forty Five Only	Per Square metre	8085.00
12	Providing and applying white cement based putty of Birla / JK average thickness 1 mm (one millimetre) over the plastered wall surface to prepare the surface even and smooth complete, as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax or any other taxes imposed by the Government. But Excluding GST.	33.00 Square metres	65.00	Rupees Sixty Five Only	Per Square metre	2145.00
13	Providing and laying cement concrete 1:4:8 (One cement isto Four sand isto Eight graded broken/crushed stone aggregate 40mm (Forty millimetres) nominal size and down gauge) mechanically mixed and curing complete excluding cost of forms work in foundation and plinth as per approved drawing, design and specifications and as per directions and entire satisfaction of the Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, malkhana, toll tax, sale tax or any other taxes imposed by the Government. But Excluding GST.	2.70 Cubic metres	4280.00	Rupees Four Thousand Two Hundred Eighty Only	Per cubic metre	11556.00
TOTAL :-						91341.00
Quoted Rate in Figure (%)						(Amount to be quoted by the contractor in Figure)
Quoted Rate in Words (%)						(Amount to be quoted by the contractor in words)


 Executive Engineer,
 Dharamshala Division,
 HPPWD Dharamshala