



Office of
Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur Himachal Pradesh
Works Department Jaisinghpur 176095 Phone No. 01894-228030
Email ee-jaipwd-hp@gov.in

No.PWD/JSPR/CB/Tenders/2026-27-
To,

8170-78

Dated:- 03/10/2026

The Chief Engineer (KZ),
Himachal Pradesh, PWD,
Dharamshala (HP).


Subject:- Publication of Tender Notice on departmental website.

Sir,

Enclosed please find herewith tender notice for publication of the same on departmental website as per Notification issued by the worthy Principal Secretary (PW) to the Govt. of HP letter No. PBW-(B) A-(3) 1/2024 dated Shimla-2 dated 03.01.2025 and instructions issued by the worthy E-in-C, HPPWD Shimla letter No. PWD/ ICT Wing/ Website dated 22.05.2026.


It is certified that the works for which tenders invited are of urgent nature and in public interest.

DA/ As above.


Executive Engineer,
Jaisinghpur Division,
HPPWD Jaisinghpur.

Copy forwarded to the following for information and necessary please:-

1. The Superintending Engineer, 5th Circle. HPPWD, Palampur.
- 2-4. All the Assistant Engineers working under this Division.
- 5-6. The Drawings Branch and Accounts Branch in this office.
7. Notice Board.
8. N.I.T. Register


Executive Engineer
Jaisinghpur Division,
HP.PWD., Jaisinghpur.

"NOTICE INVITING TENDERS"


Sealed percentage rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, HP.PWD., Division Jaisinghpur on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **12.10.2026 up to 11:00 A.M.** and the same shall be opened on the same day at **11:30 A.M.** in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **09.10.2026 up to 4:00 PM** and the application for issue of tender form shall be received on or before **09.10.2026 up to 1:00 PM**. The applications for issue of tender forms should accompanied with enlistment letter or renewal letter and the Earnest Money in the shape of National Saving Certificates / Saving Account of the Post Office / Time Deposit account / FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP.PWD., Division Jaisinghpur.

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for **75 days**:-

Sr. No.	Name of Work	Estimated Cost (Rs.)	EMD	Time limit	Cost of tender form
1	Preparation of DPR and CBR Test for various roads under HPPWD Sub Division Jaisinghpur Tehsil Jaisinghpur Distt. Kangra (H.P). Construction of Link road to village Dandel kms 0/00 to 3/500 (Portion 1/500 to 2/500)	60000/-	2000/-	Two Month	350/-
2	Restoration of rain damages on Keru Kelan to Kotlu road Km 0/00 to 1/700 (SH:- C/O R/wall at RD 1/468 to 1/489) Deposit	392900/-	7900/-	Two Month	350/-
3	Preparation of DPR and CBR Test for various roads under HPPWD Sub-Division Jaisinghpur Tehsil Jaisinghpur Distt. Kangra (H.P). Construction of Link Road From Kohala to Lower Ganguhi Kms 0/00 to 2/500 (Portion 1/500 to 2/500)	60000/-	2000/-	Two Month	350/-

Terms & Conditions:-

1. The contractors will have to produce a copy of enlistment / renewal of valid class at time of application / tender form.
2. The contractors will have to produce a copy of GST, EPF and PAN.
3. The contractors are directed to insert the rate / percentage both in figures and words.
4. The tenders forms will not be issued to those contractors who have not completed their previous works / commitments or whose performance is not found satisfactory.
5. The Executive Engineer reserves the right to reject / cancel any or all the tenders without assigning any reason.



Executive Engineer
Jaisinghpur Division
HP.PWD., Jaisinghpur.
(On behalf of Governor of Himachal Pradesh)

①

SCHEDULE OF QUANTITY

Name of work :-Preparation of DPR and CBR Test for various roads under HPPWD Sub-Division Jaisinghpur Tehsil Jaisinghpur Distt. Kangra (H.P).Construction of Link road to village Dandel kms 0/00 to 3/500 (Portion 1/500 to 2/500)

S. N.	Description of Item	Quantity	Time Limits		Unit	Two month
			In Figures	In Word		Amount
1	Preparation of detailed project report which include the following provision as given Topography Survey by Digital Total Station with two second accuracy, showing all features on survey plan like trees, culverts, bridge, electric pole, telephone poles, hand pump, schools, Haditatnts Villages etc. Draw cross-sections at 15 m (fifteen metre) intervals, L-Section & calculate the quantity of earth work in standard format of autocad showing all layer of pavement components as applicable Preparation of survey plan showing all provisions and preparation of detailed project report as per PMGSY Guidelines. Preliminary Project Reports including all test reports, coloured Photographs at every 100.00 mtr of road and at prominent points. Reports of 3 days traffic count survey along with soft copy as per requirement of MoRD/NRIDA. Test reports must include at least following field test per km (i) C.B.R of soil soaked & un-soaked (ii) Plastic Limit/Liquid Limit (iii)Optimum Moisture Content (iv)Maximum Dry Density (v) Grain size Analysis. Detailed Project Report and working drawings (Draft and final).Technical Sanction as per Approved DPR. Bid Documents with BOQ and three set of approved DPR copy (soft & Hard copy) and as per the direction and entire satisfaction of Engineer-in_charge complete.The rate is including octroi, royalty, toll tax, or any other taxes imposed by the government excluding GST.(GST Shall be Paid Extra)	1.000	60000.00	Rupees Sixty Thousand Only	Per Kilometre	60000.00



Executive Engineer,
Jaisinghpur Division,
H.P.PWD Jaisinghpur


52

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain damages on Keru Kelan to Kotlu road Km 0/00 to 1/700 (SH:- C/O R/wall at RD 1/468 to 1/489) DEPOSIT						Estimated cost Rs.		392900.00	
						Earnest Money Rs.		7900.00	
						Time Limits		Two month	
S. N.	Description of Item	Quantity	Rate		Unit	Amount			
			In Figures	In Word					
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	49.35	200.00	Rupees Two Hundred Only	Per Cubic Metre	9870.00			
2	Providing and laying in position cement concrete 1:4:8 (One cement isto four sand isto eight graded broken/crushed stone aggregate 40mm (Forty millimetres) nominal size mechanically mixed and vibrated curing complete excluding the cost of centering and shuttering in foundation and plinth including carriage of material within all leads, lifts and other incidentals as per approved drawing, design, specifications and as directed by the Engineer-In-Charge. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	98.07	3650.00	Rupees Three Thousand Six Hundred Fifty Only	Per Cubic Metre	357956.00			




3	Construction of embankment with approved materials obtained from borrow pits any lift transporting to site to spreading, grading to required slope and compacting to meet the requirement of table 300.1 and 300.2 as per MORD technical specification clause 301.5 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidentals . The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	7.77	200.00	Rupees Two Hundred Only	Per Cubic Metre	1554.00
4	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700, 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	42.00	200.00	Rupees Two Hundred Only	Per Running Metre	8400.00
5	Back filling with granular materials behind abutment, Retaining wall/Breast wall, Wing walls and the like complete as per drawings and MORD technical specification section 1200, 1600 and as per direction and entire satisfaction of the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	18.90	800.00	Rupees Eight Hundred Only	Per cubic Metre	15120.00
Total						392900.00
Quoted Rate (in Figures) Percentage		Excess (+)			%	
		Less (-)			%	
G.Total in Figures						
G.Total in Words						


 Executive Engineer,
 Jaisinghpur Division,
 HP.PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Preparation of DPR and CBR Test for various roads under HPPWD Sub-Division Jaisinghpur Tehsil Jaisinghpur Distt. Kangra (H.P).Construction of Link Road From Kohala to Lower Ganguhi Kms 0/00 to 2/500. (Portion 1/500 to 2/500)						Estimated cost Rs.		60000.00		
						Earnest Money Rs.		2000.00		
						Time Limits		Two month		
S. N.	Description of Item					Quantity	Rate		Unit	Amount
							In Figures	In Word		
1	Preparation of detailed project report which include the following provision as given Topography Survey by Digital Total Station with two second accuracy, showing all features on survey plan like trees, culverts, bridge, electric pole, telephone poles, hand pump, schools, Haditatnts Villages etc. Draw cross-sections at 15 m (fifteen metre) intervals, L-Section & calculate the quantity of earth work in standard format of autocad showing all layer of pavement components as applicable Preparation of survey plan showing all provisions and preparation of detailed project report as per PMGSY Guidelines. Preliminary Project Reports including all test reports, coloured Photographs at every 100.00 mtr of road and at prominent points. Reports of 3 days traffic count survey along with soft copy as per requirement of MoRD/NRIDA. Test reports must include at least following field test per km (i) C.B.R of soil soaked & un-soaked (ii) Plastic Limit/Liquid Limit (iii)Optimum Moisture Content (iv)Maximum Dry Density (v) Grain size Analysis. Detailed Project Report and working drawings (Draft and final).Technical Sanction as per Approved DPR. Bid Documents with BOQ and three set of approved DPR copy (soft & Hard copy) and as per the direction and entire satisfaction of Engineer-in-charge complete.The rate is including octroi, royalty, toll tax, or any other taxes imposed by the government excluding GST. (GST Shall be Paid Extra)					1.000	60000.00	Rupees Sixty Thousand Only	Per Kilometre	60000.00
	Total									60000.00
	Quoted Rate (in Figures) Percentage					Excess (+)			%	
						Less (-)			%	
	G.Total in Figures									
	G.Total in Words									


 Executive Engineer,
 Jaisinghpur Division,
 H.P.PWD Jaisinghpur