

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

“CORRIGENDUM”

The Notice Inviting Tender for the work “R/R damages on Hiranagar Sharog road km.0/00 to 5/500 (SH:-C/O B/Wall at Rd. 0/211 to 0/236). Was called vide this office letter No. PW-SRDD-CB-CTR-NIT-2026-27-15282-15311 dated 07.10.2026., due to an inadvertent error, the Name of work of the above mentioned work was uploaded incorrectly. Now, the same may be read as under:-

Sr. No.	Name of Work may be read	Estimated Cost (In Rs.)	EMD (In Rs.)	Instead of	Estimate d Cost (In Rs.)	EMD (In Rs.)
1	May be Read as “R/R damages on Hiranagar Sharog road km.0/00 to 5/500 (SH:-C/O R/Wall at Rd. 0/860 to 0/876.20).	418334.00	8000.00	Instead of “R/R damages on Hiranagar Sharog road km.0/00 to 5/500 (SH:-C/O B/Wall at Rd. 0/211 to 0/236).	316981.00	6000.00

Other terms & condition shall be remain un-changed

Executive Engineer,
Shimla Rural Division,
H.P.PWD., Dharni.

No. PW-SRDD-CB-CTR-NIT-2026-27- 15637-46 Dated:- 08/10/2026

Copy forwarded for the following for information and necessary action to:-

1. SE 4th Circle HPPWD Shimla.
2. The Executive Engineer I.T Cell O/O Engineer –in-Chief, HPPWD Nigam Vihar Shimla for information please.
3. All AE working under this division.
4. The Account Branch/Drawing Branch of this office.
5. Notice Board.

Executive Engineer,
Shimla Rural Division,
H.P.PWD., Dharni

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Hiranagar Sharog Road Km. 0/000 to 5/00 (Sri: Construction of R-wall at Rd. 0/860 to 0/876.20)

Estimated Cost:- Rs 418334 /- only
Earnest Money :- Rs. 8000 /- only
Time:- One Month

S. No.	Sub head and items of work	Qty.	Rate			Unit	Amount
			4	5	figures		
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge	31.10 Cum	197.80	Rupees One Hundred Ninety Seven and Paise Eighty Only		Per cubic metre	6152.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	38.88 Cum	302.12	Rupees Three Hundred Two and Paise Twelve Only		Per cubic metre	11746.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	76.55 Cum	4067.80	Rupees Four Thousand Sixty Seven and Paise Eighty Only		Per cubic metre	311390.00
4	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203, P.C.C grade M 10, (i) Nominal Mix 1:3:6, including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	14.02 Cum	4788.14	Rupees Four Thousand Seven Hundred Eighty Eight and Paise Fourteen		Per cubic metre	67130.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	31.80 Rmt.	144.07	Rupees One Hundred Forty Four and Paise Seven Only		Per Running Metre	4581.00
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (i) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	24.30 Cum	713.39	Rupees Seven Hundred Thirteen and Paise Thirty Nine Only		Per cubic metre	17335.00
0						Total:-	418334.00

Amount Quoted by the Contractor in Percentage excluding GST

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami