

REGISTERED

Office of the Executive Engineer, B&R Division, HP PWD Kalpa District Kinnaur (HP)

Web:- www.hppwd.gov.in E mail:- hp-kin@nic.in

Phone No:- 01786-226027 Fax:- 01786-226027.

No:- PW/KNR-E-Tender/2026- **9861-63**

Dated:- **30-9-2026**

To

The Executive Engineer (IT Cell),
HP.PWD. Shimla-2.

Subject:-

Publication of Tender Notice (OFFLINE)

Enclosed please find herewith the Tender of works costing above 1 upto 5.00 Lakh as given in the Notice Inviting Tender for uploading on the departmental website as per notification vide Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW(B) 1/2020 dated 16-07-2021 and even file No. 1/2024 dated 03-01-2024, 03-01-2025 and 1/2024-241828 dated 17-07-2025 and PWD-B-A 0(3)/8/2025-300858 dated 09-10-2025, even file No. 300858 dated 13-11-2025, 08-12-2025 and even file No. 241828 dated 02-02-2026. The works mentioned in the tender notice are urgent in nature and public interest.

Encl:- NIT, Schedule of Quantity
& Certificate.


Executive Engineer,
Kalpa Division,
HP.PWD. Kalpa.

Copy forwarded for information to:-

1. The Superintending Engineer, 11th Circle, HP.PWD. Rampur Bushahr.
2. Copy to Drawing Branch in this office.


Executive Engineer,
Kalpa Division,
HP. PWD, Kalpa.

HP.P.W.D. TENDER NOTICE (offline)

Sealed item rate offline tender on form PWD-6 & 8 are hereby invited on behalf of Governor of Himachal Pradesh by the Executive Engineer, Kalpa Division, HP.PWD; Kalpa for the following works from the approved and eligible contractors enlisted in HP.PWD; so as to reach in the office of the Executive Engineer Kalpa Division HP.PWD. Kalpa on or before **07-10-2026 up to 10.30 A.M.** and shall be opened on the same day at **11:00 AM** in presence of intending contractors or their authorized representatives. The tender form documents can be had from this office (Kalpa Division, HPPWD Kalpa) against cash payment (Non-refundable) on **06-10-2026 upto 4:00 P.M.** No application for issue of tender forms will be received on **06-10-2026 after 4:00 PM.** If the office happens to be closed on the above mentioned dates, the tenders will be sold/opened on the next working day at the same time and venue. The Earnest Money in the shape of National Saving Certificate, F.D.R.s any Post office/Bank in H.P. duly pledged in the name of Executive Engineer, Kalpa Division, HP.PWD. Kalpa must accompany with each tenders. Conditional tenders and application (For purchase of tender forms) received without Earnest Money summarily be rejected. The officer of the tenders shall be kept open for 120 days. The Executive Engineer Reserves (Right to accept or to reject any) or all the tenders without assigning any reasons.

Sr. No	Name of work	Estimated cost	Earnest Money	Time allowed	Cost of form	Eligible class of contractor
1	C/O Primary School building at Kalpa in Distt Kinnaur H.P (SH:- Providing and fixing pre-painted sheet roof covering in Block -B).	4,22,905/-	8,500/-	One Month	350/-	"C" & "D" Class
2	C/O Link road from Village Sunam to Baro Kanda Km. 0/00 to 14/250 (Portion 0/00 to 4/00) (SH:- Formation cutting from Km. 1/305 to 1/435).	4,15,451/-	8,500/-	One Month	350/-	"C" & "D" Class
3	C/O Link road from Village Sunam to Baro Kanda Km. 0/00 to 14/250 (Portion 0/00 to 4/00) (SH:- Formation cutting from Km. 1/070 to 1/305).	4,11,190/-	8,500/-	One Month	350/-	"C" & "D" Class
4	Restoration of rain damages on NH-05 to Khadura road Km.0/00 to 5/00 (SH:- C/O B/Wall in G.I. wire crate at RD. 1/130 to 1/160).	1,79,384/-	4,000/-	One Month	350/-	"C" & "D" Class
5	C/O Play Ground at Govt. Sen. Sec. School Rarang in Distt. Kinnaur (H.P) (SH:- C/O Sitting steps near basket ball court at 0/00 to 0/020).	2,12,267/-	4,500/-	One Month	350/-	"C" & "D" Class
6	Restoration of rain damages (PDNA) on NH-22 to Taitty valley road km. 0/00 to 4/545 (SH:- Repair of pot holes from km. 0/00 to 1/00).	4,23,592/-	8,500/-	One Month	350/-	"C" & "D" Class
7	Restoration of rain damages (PDNA) on NH-22 to Taitty valley road km. 0/00 to 4/545 (SH:- Repair of pot holes from km. 1/00 to 2/00).	4,22,896/-	8,500/-	One Month	350/-	"C" & "D" Class
8	Restoration of rain damages (PDNA) on NH-22 to Taitty valley road km. 0/00 to 4/545 (SH:- Repair of pot holes from km. 2/00 to 3/00).	4,23,326/-	8,500/-	One Month	350/-	"C" & "D" Class
9	Restoration of rain damages (PDNA) on NH-22 to Taitty valley road km. 0/00 to 4/545 (SH:- Repair of pot holes from km. 3/00 to 4/00).	4,23,029/-	8,500/-	One Month	350/-	"C" & "D" Class

10	C/O Play Ground at Leo in Distt. Kinnaur (H.P) (SH:- C/O fencing in front side of gate at RD 0/00 to 0/036 and valley side at RD 0/00 to 0/004).	4,02,291/-	8,500/-	One Month	350/-	"C" & "D" Class
11	C/O Play Ground at Leo in Distt. Kinnaur (H.P) (SH:- C/O sitting step and fencing on hill side at RD. 0/00 to 0/028).	4,22,753/-	8,500/-	One Month	350/-	"C" & "D" Class
12	C/O Play Ground at Leo in Distt. Kinnaur (H.P) (SH:- C/O fencing in valley side at RD 0/004 to 0/045).	4,12,140/-	8,500/-	One Month	350/-	"C" & "D" Class

Terms and conditions:-

Following documents should accompany the application for tenders:-

1. Copy of valid enlistment/renewal order.
2. Copy of GST Registration No.
3. Proof of Valid E.P.F accounts Number allotted by the Provident Fund Commissioner Shimla and copy of PAN Number.
4. Ambiguous/Telegraphic/conditional tenders or tenders by fax/E-Mail shall not be entertained/considered in any case.
5. The contractors should quote the rates of each items in words as well as figures in the Schedule of quantity.
6. The earnest money must also accompany with the application for the tender documents.
7. The tender shall be issued to those contractors who have not more than two works in Hand.

No.:- PW/KNR-E-Tender/NIT/2026-

Copy forwarded for information to:-

1. The Engineer-in-Chief, HP.PWD. Shimla-2.
2. The Deputy Commissioner, Kinnaur District at Reckong Peo.
3. The Sub Divisional Officer (Civil) Kalpa at Reckong Peo.
4. The Superintending Engineer, 11th Circle, HP.PWD. Rampur Bushahr.
5. The Block Development Officer, Kalpa at Reckong Peo.
6. The Chairman, Zila Parishad, Kinnaur District at Reckong Peo.
7. The Chairman, Panchayat Samiti Kalpa at Reckong Peo.
8. Drawing Branch in this office.
9. All the Contractors under this Division.
10. Notice Board.


Executive Engineer,
Kalpa Division,
HP. PWD. Kalpa.

Dated:-

 30-9-2026


Executive Engineer,
Kalpa Division,
HP. PWD. Kalpa.

CERTIFICATE

Certified that the Tender for works called vide this office Letter No. PW/KNR/E-Tender/2026- 9845-60 dated 30-9-2026 and Twelve numbers of works are of urgent nature and essential for public safety or restoration of infrastructure and public interest.


Executive Engineer,
Kalpa Division,
HP.PWD, Kalpa.



**Executive Engineer
Kalpa Division
HP, PWD, Kalna**

SCHEDULE OF QUANTITY

Name of work:- C/O Link road from Village Sunam to Baro Kanda Km. 0/00 to 14/250 (Portion 0/00 to 4/00)				Estimated Cost	--	4,15,451/-
(SH:- Formation cutting from Km. 1/305 to 1/435).				Earnest Money	--	8,500/-
Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Cutting in earth work in all heights and depths and in all kinds of soils including saturated soil comprising of Pick, Jumper, blasting work both in soft and hard rock with chiseling, wedging-out of rock where blasting is prohibited, their intermediate classification of soil, setting-out true to the required lines, grades, side slopes, trimming bottoms to levels as shown on the drawing and as directed by the Engineer-in-charge at site according to HP.PWD, specification of 1990 Vol-I and sorting-out useful/ un-useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful/ un-useful materials for filling in road ways camber, embankments for grades, improvement and leveling to required grade and disposing of all surplus excavated earth in acquired width of the road or on approved dumping sites through all modes of transportation including head load or animal transport or mechanically means alongwith its leveling, fine dressing and all labour, machineries, tools, equipments and safety measures and other incidental, necessary to complete the work by mechanised means and labour if required. All useful materials such as stones, shingles, aggregates and slates shall be sorted- out and stacked along road side, the quantity of which shall not be less than 250.52 cum., failing which recovery @ Rupees 300/cum. (Three hundred per cubic metre) shall be effected from the bill of the contractor. Any loss of the public/ private property during the course of execution shall be absolute responsibility of the contractor which shall to be duly compensated by him in all respect, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge. The rates are excluding GST.	2017.90	₹ 205.88	Rupees Two Hundred Five Paise EightyEight Only	Per Cubic meter	₹ 415,451.00
Total in figures:-						₹ 415,451.00
Total in Words:-		Rupees Four Lakh Fifteen Thousand Four Hundred FiftyOne Only				
Quoted Percentage rate upto three Digits :-		(+)/(-)				


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD, Kalpa.

3

2

SCHEDULE OF QUANTITY

Name of work:- C/O Link road from Village Sunam to Baro Kanda Km. 0/00 to 14/250 (Portion 0/00 to 4/00)				Estimated Cost	--	4,11,190/-
(SH:- Formation cutting from Km. 1/070 to 1/305).				Earnest Money	--	8,500/-
Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Cutting in earth work in all heights and depths and in all kinds of soils including saturated soil comprising of Pick, Juniper, blasting work both in soft and hard rock with chiseling, wedging-out of rock where blasting is prohibited, their intermediate classification of soil, setting-out true to the required lines, grades, side slopes, trimming bottoms to levels as shown on the drawing and as directed by the Engineer-in-charge at site according to HP.PWD, specification of 1990 Vol-I and sorting-out useful/ un-useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful/ un-useful materials for filling in road ways camber, embankments for grades, improvement and leveling to required grade and disposing of all surplus excavated earth in acquired width of the road or on approved dumping sites through all modes of transportation including head load or animal transport or mechanically means alongwith its leveling, fine dressing and all labour, machineries, tools, equipments and safety measures and other incidental, necessary to complete the work by mechanised means and labour if required. All useful materials such as stones, shingles, aggregates and slates shall be sorted-out and stacked along road side, the quantity of which shall not be less than 238.85 cum., failing which recovery @ Rupees 300/cum. (Three hundred per cubic metre) shall be effected from the bill of the contractor. Any loss of the public/ private property during the course of execution shall be absolute responsibility of the contractor which shall to be duly compensated by him in all respect, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge. The rates are excluding GST.	2107.48	₹ 195.11	Rupees One Hundred NinetyFive Paise Eleven Only	Per Cubic meter	₹ 411,190.00
Total in figures:-						₹ 411,190.00
Total in Words:-			Rupees Four Lakh Eleven Thousand One Hundred Ninety Only			
Quoted Percentage rate upto three Digits :-		(+)/(-)				


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD, Kalpa.

SCHEDULE OF QUANTITIES

Name of Work: Restoration of rail bridges on All-India Road Km. 0/00 to 6/00
(Sls. C, D, B, Mad in G.L. where cost of Rs. 1/100 to 1/100).

Name of Work		Estimation of unit charges on Bill of Materials (see 0/00 to 0/00)		Estimated Cost		179,384/-	
(Sb. C/C/D, Wall in G.L. Wire crate of 100 x 100 to 1/100)				Per Unit		4,000/-	
Sr.No.	Description of Items	Qty.	In Pkg.	Rate	Unit	One Month Amount	
1	Reckoning behind abutment, wing wall and return wall complete as per drawings to technical specification clause 1204.3d with good earth, including carriage of materials through all modes of transportation with in all loads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	86.10	₹ 166.10	Rupees One Hundred Sixty Six Paise Ten Only	Per Cubic meter	₹ 14,351.66	
2	Excavating and laying of boulder apron laid in wire crates with 4mm (four millimeter) diameter (1) wire conforming to IS: 200 and IS: 4826 in 100mm x 100mm (Hundred millimeter into hundred millimeter) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogram each as per drawing and technical specification clause 1301), including carriage of materials through all modes of transportation with in all loads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	64.80	₹ 2,546.80	Rupees Two Thousand Five Hundred Forty Six Paise Eighty Only	Per Cubic meter	₹ 165,033.00	
Total in figures:-						₹ 179,384.66	
Total in Words:-				Rupees One Lakh Seventy Nine Thousand Three Hundred Eighty Four Only			
Quoted Percentage rate upto three Digits:-				(+)/(=)			


 Executive Engineer,
 Kalpa Division (B&R),
 MP.PWD, Kalpa.

SCHEDULE OF QUANTITY

Name of work: C/O Play Ground at Govt. Sen. Sec. School Rarang in Distt. Kinnaur (H.P.)				Estimated Cost	:-	2,12,267/-
(SH:- C/O Sitting steps near basket ball court at 0/00 to 0/020).				Earnest Money	:-	4,500/-
				Time	:-	One Month
Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Stone masonry in cement mortar for substructure complete as per drawing & technical specification Clauses 702, 704, 1202 and 1204. Random rubble masonry in cement mortar 1:6 (One cement: Six sand,) including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	30.84	₹ 4,465.00	Rupees Four Thousand Four Hundred SixtyFive Only	Per Cubic meter	₹ 137,701.00
2	Providing and laying Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1:4 (1cement : 4 coarse sand): 25mm thick, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	52.50	₹ 1,420.30	Rupees three hundred seventy only	Per Square meter	₹ 74,566.00
Total in figures:-						₹ 212,267.00
Total in Words:-			Rupees Two Lakh Twelve Thousand Two Hundred SixtySeven Only			
Quoted Percentage rate upto three Digits :-		(+)/(-)				

Executive Engineer,
Kalpa Division (B&R),
HP.PWD Kalpa.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages (PDNA) on NH-22 to Taily valley road Km. 0/00 to 4/545		Estimated Cost	4,23,592/-
(SH:- Repair of pot holes from Km. 0/00 to 1/00).		Earnest Money	8,500/-
		Time	One Month

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm (twenty millimetre) thick premix carpet and seal coat type B specification Clause 1904.2.503 and 508.1, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	762.50	₹ 532.95	Rupees Five Hundred ThirtyTwo NinetyFive Only	Per Square meter	₹ 406,374.00
2	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading-3 as per Technical Specification Clause 405. By manual means, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	5.72	₹ 3,010.10	Rupees Thousand Ten Ten Only	Per Cubic meter	₹ 17,218.00
Total in figures:-						₹ 423,592.00
Total in Words:-						
Quoted Percentage rate upto three Digits :-						


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD, Kalpa.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages (PDNA) on NH-22 to Taity valley road Km. 0/00 to 4/545		Estimated Cost	:- 4,22,896/-
(SH:- Repair of pot holes from Km. 1/00 to 2/00).		Earnest Money	:- 8,500/-
		Time	:- One Month

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm (twenty millimetre) thick premix carpet and seal coat type B specification Clause 1904.2.503 and 508.1, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	761.25	₹ 532.95	Rupees Five Hundred ThirtyTwo Paise NinetyFive Only	Per Square meter	₹ 405,708.00
2	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading-3 as per Technical Specification Clause 405. By manual means, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	5.71	₹ 3,010.10	Rupees Thousand Ten Paise Ten Only	Per Cubic meter	₹ 17,188.00
Total in figures:-						₹ 422,896.00
Total in Words:-		Rupees Four Lakh TwentyTwo Thousand Eight Hundred NinetySix Only				
Quoted Percentage rate upto three Digits :-		(+)/(-)				


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD, Kalpa.

SCHEDULE OF QUANTITY

Name of work:-	Restoration of rain damages (PBDNA) on NH-22 to Talty valley road Km. 0/00 to 4/545	Estimated Cost :-	4,23,326/-
(SH:- Repair of pot holes from Km. 2/00 to 3/00).		Earnest Money :-	8,500/-
		Time :-	One Month

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm (twenty millimetre) thick premix carpet and seal coat type B specification Clause 1904.2.503 and 508.1, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	762.00	₹ 532.95	Rupees Five Hundred ThirtyTwo Paise NinetyFive Only	Per Square meter	₹ 406,108.00
2	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading-3 as per Technical Specification Clause 405. By manual means, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	5.72	₹ 3,010.10	Rupees Thousand Ten Paise Ten Only	Per Cubic meter	₹ 17,218.00
Total in figures:-						₹ 423,326.00
Total in Words:-						
Quoted Percentage rate upto three Digits:-						

Executive Engineer,
Kalpa Division (B&R),
HP.PWD, Kalpa.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages (PDNA) on NH-22 to Taily valley road Km. 0/00 to 4/545

(SH:- Repair of pot holes from Km. 3/00 to 4/00).

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat 20 mm (twenty millimetre) thick premix carpet and seal coat type B specification Clause 1904.2.503 and 508.1, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government The rates are excluding GST.	761.50	₹ 532.95	Rupees Five Hundred ThirtyTwo Paise NineFive Only	Per Square meter	₹ 405,841.00
2	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading-3 as per Technical Specification Clause 405. By manual means, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	5.71	₹ 3,010.10	Rupees Thousand Ten Paise Ten Only	Per Cubic meter	₹ 17,188.00
Total in figures:-						
Total in Words:-			Rupees Four Lakh TwentyThree Thousand TwentyNine Only			
Quoted Percentage rate upto three Digits :-		(+)/(-)				₹ 423,029.00

Executive Engineer,
Kalpa Division (B&R),
HP.PWD Kalpa.

SCHEDULE OF QUANTITY

Estimated Cost :- 4,02,291/-

Name of work:- C/O Playground at Leo in Distt. Kinnaur (H.P.) (SI:- C/O fencing in front side of gate at RD 0/00 to 0/036 and valley side at RD 0/00 to 0/004).

Earnest Money :- 8500/-

Time:- One Month

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Coursed rubble masonry with hard stone (first or second sort) in superstructure above plinth level and upto floor five level. Masonry work (first sort), in cement mortar 1:6 (1 cement: 6 coarse sand) including carriage of materials through all modes of transportation with in all leads and lift, as per PWD specification and as per direction of Engineer-in-charge including all incidental. The rates are inclusive of octroi, royalty and Malkana, toll taxes, GST or other tax imposed by the government.	8.10	₹ 5,551.61	Five Thousand Five Hundred Fifty One Rupees and Sixty One Paise Only	per cum	₹ 44,968.00
2	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing: 1:2:4 (one Cement: two coarse sand: four graded stone) aggregate 20 mm (twenty millimeter) nominal including carriage of materials through all modes of transportation with in all leads and lift, as per PWD specification and as per direction of Engineer-in-charge including all incidental. The rates are inclusive of octroi, royalty and Malkana, toll taxes, GST or other tax imposed by the government.	3.65	₹ 6,022.97	Six Thousand Twenty Two Rupees and Ninety Six Paise Only	per cum	₹ 21,954.00
3	40 mm thick fine dressed stone flooring over 20 mm (average) thick base of cement mortar 1:5 (1 cement: 5 coarse sand), including pointing with cement mortar 1:2 (1 cement: 2 stone dust) with an admixture of pigment to match the shade of stone. Red sand stone including carriage of materials through all modes of transportation with in all leads and lift, as per PWD specification and as per direction of Engineer-in-charge including all incidental. The rates are inclusive of octroi, royalty and Malkana, toll taxes, GST or other tax imposed by the government.	18.00	₹ 695.68	Six Hundred Ninety Five Rupees and Sixty Seven Paise Only	Per Sqm.	₹ 12,522.00

4	Providing and fixing hard drawn steel wire fabric 75x25 mm mesh of weight not less than 7.75 Kg per sqm to window frames etc. including 62x19 mm beading of second class teak wood and priming coat with approved steel primer all complete including carriage of materials through all modes of transportation with in all leads and lift, as per PWD specification and as per direction of Engineer-in-charge including all incidental. The rates are inclusive of octroi, royalty and malkana, toll taxes, GST or other tax imposed by the government.	180.00	₹ 1,095.04	One Thousand Ninety Five Rupees and Four Paise Only	Per Sqm.	₹ 197,108.00
5	Steel work welded in built up sections/framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including carriage of materials through all modes of transportation with in all leads and lift, as per PWD specification and as per direction of Engineer-in-charge including all incidental. The rates are inclusive of octroi, royalty and malkana, toll taxes, GST or other tax imposed by the government.	1215.69	₹ 103.43	One Hundred Three Rupees and Forty Three Paise Only	Per kg.	₹ 125,739.00
Total in figures:-					Total =	402291.00
Total in Words:-		Four Lakh Two Thousand Two Hundred Ninety One Rupees Only				
Quoted percentage rate upto three Digits:-		(+)/(-)				


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD, Kalpa.

SCHEDULE OF QUANTITY

Name of work:- C/O Playground at Leo in Distt. Kinnaur (HP) (SH:- C/O Sitting step and fencing on hill side at RD. 0/00 to 0/028)

Estimated Cost :- 4,22,753-

Earnest Money :- 8500/-

Time:- One Month

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. including carriage of materials through all modes of transportation with in all leads and lift, as per PWD specification and as per direction of Engineer-in-charge including all incidental. The rates are inclusive of octroi, royalty and malkana, toll taxes, GST or other tax imposed by the government.	6.72	₹ 228.81	Two Hundred Twenty Eight Rupees and Eighty One Paise Only	per cum	₹ 1,538.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:5:10 (1 cement: 5 fine sand: 10 graded stone aggregate 40 mm nominal size). including carriage of materials through all modes of transportation with in all leads and lift, as per PWD specification and as per direction of Engineer-in-charge including all incidental. The rates are inclusive of octroi, royalty and malkana, toll taxes, GST or other tax imposed by the government.	6.72	₹ 4,237.29	Four Thousand Two Hundred Thirty Seven Rupees and Twenty Nine Paise Only	per cum	₹ 28,475.00
3	Coursed rubble masonry with hard stone (first or second sort) in Superstructure above plinth level and upto floor five level. Masonry work (first sort) in cement mortar 1:6 (1 Cement : 6 coarse sand) including carriage of materials through all modes of transportation with in all leads and lift, as per PWD specification and as per direction of Engineer-in-charge including all incidental. The rates are inclusive of octroi, royalty and malkana, toll taxes, GST or other tax imposed by the government.	18.48	₹ 5,551.61	Five Thousand Five Hundred Fifty One Rupees and Sixty One Paise Only	per cum	₹ 102,594.00

4	Providing and laying cement concrete in retaining wall return walls (any thickness) including attached pilasters, columns, piers, abutment pillars, posts, struts, buttresses, string or lacing courses, parapets, coping bed blocks anchor block plain window sills fillets subpen floor etc. up to floor five level, excluding the cost of centering shuttering and finishing 1:2:4 (One Cement: Two coarse sand: four graded stone) aggregate 20mm (Twenty millimeter) nominal size, including carriage of materials through all modes of transportation with in all leads and lift, as per PWD specification and as per direction of Engineer-in-charge including all incidental. The rates are inclusive of octroi, royalty and Malkana, toll taxes, GST or other tax imposed by the government.	2.57	₹ 6,022.97	Six Thousand Twenty Two Rupees and Ninety Seven Paise Only	per cum	₹ 15,479.00
5	40mm thick finished stone flooring over 20mm (average) thick base of cement mortar 1:5 (1 Cement: 5 Coarse sand) including pointing with cement mortar 1:2 (1 Cement: 2 stone dust) with an admixture of pigment to match the shade of stone red sand stone, including carriage of materials through all modes of transportation with in all leads and lift, as per PWD specification and as per direction of Engineer-in-charge including all incidental. The rates are inclusive of octroi, royalty and Malkana, toll taxes, GST or other tax imposed by the government.	56.00	₹ 695.68		per Sqm	₹ 38,958.00
6	Providing and fixing hard drawn steel wire fabric 75x25 (seventy five into twenty five millimeter) mesh of weight not less than 7.75 kg per sqm to window frames etc. including 62x19mm (sixty two into nineteen millimeter) beading of second class teak wood and priming coat with approved steel primer all complete including carriage of materials through all modes of transportation within all leads and lifts, as per PWD specification and as per direction of the Engineer-in-Charge.	126.00	₹ 1,095.04		per Sqm	₹ 137,975.00
7	Steel work welded in single sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint, including carriage of material through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-Charge.	944.93	₹ 103.43		Per kg.	₹ 97,734.00
Total in figures:-					Total =	422753.00

	Total in Words:-	Four Lakh Twenty Two Thousand Seven Hundred Fifty Three Rupees Only
	Quoted percentage rate upto three Digits:-	(+)/(-)


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD, Kalpa.

SCHEDULE OF QUANTITY

Estimated Cost :- 4,12,140-

Earnest Money :- 8500/-

Time:- One Month

Name of work:- C/O Playground at Leo in Distt. Kinnaur (H.P.) (SH:- C/O fencing in valley side at RD 0/004 to 0/045).

Sr. No.	Description of Items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Coursed rubble masonry with hard stone (first or second sort) in superstructure above plinth level and upto floor five level. Masonry work (first sort), in cement mortar 1:6 (1 cement: 6 coarse sand) including carriage of materials through all modes of transportation with in all leads and lift, as per PWD specification and as per direction of Engineer-in-charge including all incidental. The rates are inclusive of octroi, royalty and malkana, toll taxes, GST or other tax imposed by the government.	8.30	₹ 5,551.61	Five Thousand Five Hundred Fifty One Rupees and Sixty One Paise Only	per cum	₹ 46,078.00
2	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc, up to floor five level, excluding the cost of centering, shuttering and finishing: 1:2:4 (one Cement: two coarse sand: four graded stone) aggregate 20 mm (twenty millimeter) nominal including carriage of materials through all modes of transportation with in all leads and lift, as per PWD specification and as per direction of Engineer-in-charge including all incidental. The rates are inclusive of octroi, royalty and malkana, toll taxes, GST or other tax imposed by the government.	3.78	₹ 6,022.97	Six Thousand Twenty Two Rupees and Ninety Six Paise Only	per cum	₹ 22,767.00
3	40 mm thick fine dressed stone flooring over 20 mm (average) thick base of cement mortar 1:5 (1 cement: 5 coarse sand), including pointing with cement mortar 1:2 (1 cement: 2 stone dust) with an admixture of pigment to match the shade of stone. Red sand stone including carriage of materials through all modes of transportation with in all leads and lift, as per PWD specification and as per direction of Engineer-in-charge including all incidental. The rates are inclusive of octroi, royalty and malkana, toll taxes, GST or other tax imposed by the government.	18.45	₹ 695.68	Six Hundred Ninety Five Rupees and Sixty Seven Paise Only	Per Sqm.	₹ 12,835.00

4	Providing and fixing hard drawn steel wire fabric 75x25 mm mesh of weight not less than 7.75 Kg per sqm to window frames etc. Including 62x19 mm beading of second class teak wood and priming coat with approved steel primer all complete including carriage of materials through all modes of transportation with in all leads and lift, as per PWD specification and as per direction of Engineer-in-charge including all incidental. The rates are inclusive of octroi, royalty and malkana, toll taxes, GST or other tax imposed by the government.	184.50	₹ 1,095.04	One Thousand Ninety Five Rupees and Four Paise Only	Per Sqm.	₹ 202,035.00
5	Steel work welded in built up sections/framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including carriage of materials through all modes of transportation with in all leads and lift, as per PWD specification and as per direction of Engineer-in-charge including all incidental. The rates are inclusive of octroi, royalty and malkana, toll taxes, GST or other tax imposed by the government.	1241.66	₹ 103.43	One Hundred Three Rupees and Forty Three Paise Only	Per kg.	₹ 128,425.00
Total in figures:-					Total =	412140.00
Total in Words:-		Four Lakh Twelve Thousand One Hundred Forty Rupees Only				
Quoted percentage rate upto three Digits:-		(+)/(-)				

Executive Engineer,
Kalpa Division (B&R),
HP.PWD, Kalpa.