



Public Works Department
Government of Himachal Pradesh, India

No. PW-MDI(P)E-Tender-NIT/2026-27-
To

13 098-108

Dated:-

9/10/2026

The Chief Engineer (MZ),
HPPWD, Mandi.

Subject: -

Publishing of tender notice.

Dear Sir,

Enclosed please find herewith the Tender Notice of works as given in the Notice Inviting Tender for uploading on department website as per notification Principal Secretary (PW) to the Govt. of H.P. letter No. PBW(B)A(3)1/2024 dated Shimla-2 the 03.01.2024 and No. PBW (B) A (3) 8/2025- 300858 dated 13th Nov., 2025 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender.


Executive Engineer,
Mandi Division No-I,
HP.PWD. Mandi

Copy alongwith copy of Tender Notice is forwarded to the following for information and necessary action:-

1. The Superintending Engineer, 1st Circle, HPPWD, Mandi H.P.
2. All the Assistant Engineers, Working under this Division.
3. The Drawing Branch of this office.
4. Notice Board.


Executive Engineer,
Mandi Division No-II,
HP.PWD. Mandi

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
"NOTICE INVITING TENDER"**

Sealed **Percentage rates** tender in emergent condition on form 6 & 7 are invited on behalf of Governor of Himachal Pradesh for the following work covered under emergent/inescapable nature from the approved and eligible contractors enlisted in H.P.PWD so as to reach in this office on or **22.10.2026 Up to 11.30 A.M.** and will be opened on the same day at 3.30 P.M. in the presence of interested contractors or their authorized representatives who may like to be present. If it happens to be holiday on the schedule date of opening of tender, the same will be opened on next working day. The application for obtaining the tender form will be received upto **01.00 PM & without EMD** tender form will not be accepted, moreover the tender form can be had from this office against cash payment (Nonrefundable) up to 5.00 P.M. on **21.10.2026**.

The earnest money in the shape of National Saving Certificate/ Time deposit accounts/Saving account in any of the Post Office and Banks of Himachal Pradesh duly pledged in favour of the Xen Mandi Division No. II must accompany with each tender. Conditional tender and the tender received without earnest money will summarily be rejected. The earnest money should be attached with application. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject the tender without assigning any reason.

Sr. No	Name of Work	Estimated Cost (Rs.)	Earnest Money Deposit (EMD) (Rs.)	Cost of Tender (Rs.)	Eligible Class of Contractor	Time Limit
1	RRD on road to Vnot via Yala road KM 0/00 to 4/00. (SH: C/O B/wall at RD 0/530 to 0/548 and 2/400 to 2/410)	4,86,170/-	9,800/-	350/-	Class "D"	One Month
2	RRD on road to Vnot via Yala road KM. 0/00 to 4/00. (SH: C/O R/wall at RD 0/500 to 0/519)	4,90,810/-	9,900/-	350/-	Class "D"	One Month
3	NDF/2026/61, R/O (Repair of) Restoration of Rain damages on Anna Kenchi Kushmal road Km 0/00 to 8/080 (SH: Hiring of JCB for removal of slips, dressing of berms, excavation of katcha drain etc 0/00 to 8/080) Deposit work	1,26,779/-	2,536/-	350/-	Class "D"	One Month
4	NDF/2026/62, R/O (Repair of) Restoration of Rain damages on Madan Ka Ghar Samrahan road Km 0/00 to 8/00 (SH: Hiring of JCB for removal of slips, dressing of berms, excavation of katcha drain etc 0/00 to 8/00) Deposit work	3,38,389/-	6,768/-	350/-	Class "D"	One Month
5	NDF/2026/58, R/O (Repair of) Restoration of Rain damages on Saigaloo to Nahlog road Km 0/00 to 6/00 (SH: Hiring of JCB for removal of slips, dressing of berms, excavation of katcha drain etc 1/120 to 1/414) Deposit work	1,26,779/-	2,536/-	350/-	Class "D"	One Month
6	R.R.D. on Jablahi barnota karkoh road KM. 0/00 to 5/500. (SH: P/L kharanja soling and PCC between KM. 0/310 to 0/345) under PDNA 2025	1,04,561/-	2,100/-	350/-	Class "D"	One Month
7	NDF/2026/55, R/O (Repair of) Restoration of Rain damages on Sain to Sadoh road Km 0/00 to 12/500 (SH: Hiring of JCB for removal of slips, dressing of berms, excavation of katcha drain etc 2/120 to 2/560) Deposit work	3,38,389/-	6,768/-	350/-	Class "D"	One Month
8	NDF/2026/57, R/O (Repair of) Restoration of Rain damages on Chambi to Kuther road Km 0/00 to 5/500 (SH: Hiring of JCB for removal of slips, dressing of berms, excavation of katcha drain etc 1/120 to 1/414) Deposit work	1,26,779/-	2,536/-	350/-	Class "D"	One Month
9	NDF/2026/51, R/O (Repair of) Restoration of Rain damages on Chanaun Galoo to Sadyana road Km 0/00 to 5/00 (SH: Hiring of JCB for removal of slips, dressing of berms, excavation of katcha drain etc 1/120 to 1/269) Deposit work	75,508/-	1,510/-	350/-	Class "D"	One Month
10	NDF/2026/50, R/O (Repair of) Restoration of Rain damages on Lag Kathwari road Km 0/00 to 2/00 (SH: Hiring of JCB for removal of slips, dressing of berms, excavation of katcha drain etc 1/120 to 1/268) Deposit work	75,508/-	1,510/-	350/-	Class "D"	One Month

1	Balance work of Co-Operative bank branch office building in Gandhi Bhawan Building Distt Mandi (HP) (Sub Head: Providing and fixing PVC panel ceiling work)	94,099/-	1,900/-	350/-	Class "D"	One Month
12	Annual repair and maintenance of residential building at jail road under Mandi Division No II Distt Mandi (HP) (Sub Head: Providing and laying painting cupboard & wood works etcetera in D-Block Qtr No 19)	98,497/-	2,000/-	350/-	Class "D"	One Month
13	Restoration of rain damages on various roads under Sub-Division No. IV HP PWD Mandi (Sub Head: Hiring of Tipper for carriage of mucks/debris/stone, boulders etcetera Job No. IV)	1,80,000/-	3,600/-	350/-	Class "D"	Two Months

CERTIFICATE

It is certified that the above works are required to be carried out immediately, being of emergent nature and in the larger public interest.

Tender Notice – Terms & Conditions

The tender documents shall be issued only to those Contractors/Firms who submit the following documents along with their application:

1. Valid enlistment/registration of contractor in the appropriate class.
2. Permanent Account Number (PAN).
3. GST Registration Number.
4. Earnest money in the shape of National Saving Certificate/Time Deposit Account in any Post Office in Himachal Pradesh, or F.D.R. from any Nationalized Bank duly pledged in favour of the Executive Engineer, Mandi Division No. 2, HPPWD, Mandi H.P.
5. Earnest money and cost of tender form for the above works must be submitted along with the application for purchase of tender form. Applications received without earnest money and cost of tender form shall be summarily rejected.
6. The offer of the tender shall remain valid for 75 (seventy-five) days after the opening of the tender.
7. Ambiguous, telephonic, conditional tenders or tenders submitted by fax/e-mail shall not be considered and will be summarily rejected.
8. The Executive Engineer reserves the right to reject or cancel any or all tenders without assigning any reason.
9. If the date specified above happens to be a holiday, the tenders shall be processed on the next working day.
10. The Contractor/Firm must quote their rates both in words as well as in figures, failing which the Executive Engineer reserves the right to accept or reject any or all tenders.
11. Tender forms shall not be issued to those Contractors/Firms whose past performance is not found satisfactory or who have failed to complete previously awarded works within the stipulated period.
12. No contractor shall have more than two major works in hand at a time.
13. The work shall be completed by the Contractor within the stipulated period.

No.PW-MDII-CB NIT (off line) /2025-

13098-108

Copy forwarded to the following for information and necessary action: -

1. The Engineer-in-chief, HPPWD: Shimla.
2. The Chief Engineer, (MZ)HPPWD: Mandi.
3. The Superintending Engineer, 1st Circle, HPPWD: Mandi.
4. All the Assistant Engineers' Working under this Division
5. The President of Contractor's Association.
6. Notice Board/Accounts Branch/Drawing Branch.

Executive Engineer
Mandi Division No II
HP.PWD Mandi

Dated: -

9/10/2026

Executive Engineer
Mandi Division No II
HP.PWD Mandi

203

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 486170.00
 Earnest Money Rs:- 9800.00
 Time :- One Month

Tender Inviting Authority :- Executive Engineer, Mandi Division No.-II, H.P.P.W.D. Mandi.

Name of work :- RRD on road to Vnot via Yala road KM. 0/00 to 4/00. (SH:- C/O B/wall at RD 0/530 to 0/548 and 2/400 to 2/410).

Contract No.:

Bidder Name:

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Item Description	Quantity	Units	Estimated Rate excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in words.
1	2	3	4	5	6	7
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 including carriage of materials with in all leads , lifts and other incidentals as per direction of Engineer-in-charge.	35.56	Per cubic metre	168.35	5987.00	Rupees Five Thousand Nine Hundred Eighty Seven Only
2	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out , construction of shoring and bracing removal of stumps and other deleterious materials and disposal upto a lead of 50m (fifty metre), dressing of sides and bottoms and back filling in trenches with excavated suitable material in ordinary soil upto 3m (three metre) depth including entire carriage of material within all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	31.88	Per cubic metre	517.65	16503.00	Rupees Sixteen Thousand Five Hundred Three Only
3	Providing and laying 1:5:10 (One cement : five sand : ten graded crushed stone aggregate 40mm (Forty millimetre nominal size) concrete for plain /reinforced concrete in open foundations and curing complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	98.28	Per cubic metre	4600.00	452088.00	Rupees Four Lakh Fifty Two Thousand Eighty Eight Only

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 490810.00
Earnest Money Rs:- 9900.00
Time :- One Month

Tender Inviting Authority :- Executive Engineer, Mandi Division No.-II, H.P.P.W.D. Mandi.

Name of work :- RRD on road to Vnot via Yala road KM. 0/00 to 4/00. (SH:- C/O R/wall at RD 0/500 to 0/519).

Contract No.:

Bidder Name:

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Item Description	Quantity	Units	Estimated Rate excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in words.
1	2	3	4	5	6	7
1	Excavation in soil in Hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto any lead as per drawing and Technical Specification Clause 1603.1 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	23.56	Per cubic metre	168.35	3966.00	Rupees Three Thousand Nine Hundred Sixty Six Only
2	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal upto a lead of 50m (fifty metre), dressing of sides and bottoms and back filling in trenches with excavated suitable material in ordinary soil upto 3m (three metre) depth including entire carriage of material within all leads and lifts as per entire satisfaction and direction of Engineer-in-charge.	30.59	Per cubic metre	517.65	15835.00	Rupees Fifteen Thousand Eight Hundred Thirty Five Only
3	Providing and laying 1:5:10 (One cement : five sand : ten graded crushed stone aggregate 40mm (Forty millimetre nominal size) concrete for plain /reinforced concrete in open foundations and curing complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	96.52	Per cubic metre	4600.00	443982.00	Rupees Four Lakh Forty Three Thousand Nine Hundred Ninety Two Only

Estimated Cost Rs:- 126779.00
Earnest Money Rs: 2536.00
Time :- One Month

Percentage of BoQ

Tender Inviting Authority : Executive Engineer, Mandi Division No.II HPPWD Mandi
Name of work :- NDF/2026/61,R/O (Repair of) Restoration of Rain damages on Anna Kenchi Kushmal road Km 0/00 to 8/080
(SH:- Hiring of JCB for removal of slips, dressing of berms, excavation of katcha drain etc 0/00 to 8/080) Deposit work

Contract No. : _____						
Name of the Bidder/ Bidding Firm/ Company : _____						
PRICE SCHEDULE						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Unit	Estimate Rate with all taxes excluding GST in Rs. P	TOTAL AMOUNT With all Taxes excluding GST in Rs. P	TOTAL AMOUNT with all Taxes excluding GST In Words
1	2 Hiring of JCB for removal of slips, dressing of berms, excavation of Kacha drain and loading of debris etc. as when required and disposing of excavated earth up to any lead from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the JCB owner which shall have to be fully compensated by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB owner. The repair and spare including watch and ward of JCB also borne by the contractor/ owner. The daily log book will be maintained at site which should be duly verified by the Engineer in-charge.	136.00	4 Per hours	5 932.20	6 1,26,779.00	7 Rupees One Lakh Twenty Six Thousand Seven Hundred Seventy Nine Only
Total					1,26,779.00	Rupees One Lakh Twenty Six Thousand Seven Hundred Seventy Nine Only

Quoted Rate in Figures :

Quoted Rate in words:

BOP checked and approved for Rs: 1,26,779.00/-

Executive Engineer,
Mandi Division No.II, ,
HP.PWD. Mandi.

Estimated Cost Rs:- 338389.00
Earnest Money Rs: 6768.00
Time :- One Month

Percentage of BoQ

Tender Inviting Authority : Executive Engineer, Mandi Division No.II HPPWD Mandi

Name of work :- NDF/2026/62,R/O (Repair of) Restoration of Rain damages on Madan Ka Ghar Samrahan road Km 0/00 to 8/00

(SH:- Hiring of JCB for removal of slips, dressing of berms, excavation of katcha drain etc 0/00 to 8/8/00) Deposit work

Contract No. :

Name of the Bidder/ Bidding Firm/ Company :

PRICE SCHEDULE

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Unit	Estimate Rate with all taxes excluding GST in Rs. P	TOTAL AMOUNT With all Taxes excluding GST in Rs. P	TOTAL AMOUNT with all Taxes excluding GST In Words	
1	Hiring of JCB for removal of slips, dressing of berms, excavation of Kacha drain and loading of debries etc. as when required and disposing of excavated earth up to any lead from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the JCB owner which shall have to be fully compensated by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB owner. The repair and spare including watch and ward of JCB also borne by the contractor/ owner. The daily log book will be maintained at site which should be duly verified by the Engineer in-charge.	363.00	Per hours	932.20	3,38,389.00	Rupees Three Lakh Eight Thousand Three Hundred Eighty Nine Only	7
Total					3,38,389.00	Rupees Three Lakh Eight Thousand Three Hundred Eighty Nine Only	

Quoted Rate in Figures :

Quoted Rate in words:

Executive Engineer,
Mandi Division No.II.,
H.P.W.D. Mandi.

BoQ checked and approved for Rs. 3,38,389.00

Estimated Cost Rs:- 128779.00
Earnest Money Rs: 2536.00
Time :- One Month

Tender Inviting Authority : Executive Engineer, Mandi Division No.II HPPWD Mandi
Name of work :- NDF/2026/58,R/O (Repair of) Restoration of Rain damages on Salgaloo to Nahlog road Km 0/00 to 6/00
(SH:- Hiring of JCB for removal of slips, dressing of berms, excavation of katcha drain etc 1/120 to 1/414) Deposit work

Percentage of BoQ

Contract No. :

Name of the Bidder/ Bidding Firm/ Company :

PRICE SCHEDULE						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	TEXT #	TEXT #
Sl. No.	Item Description	Quantity	Unit	Estimate Rate with all taxes excluding GST in Rs. P	TOTAL AMOUNT With all Taxes excluding GST in Rs. P	TOTAL AMOUNT with all Taxes excluding GST In Words
1	Hiring of JCB for removal of slips, dressing of berms, excavation of Kacha drain and loading of debris etc. as when required and disposing of excavated earth up to any lead from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the JCB owner which shall have to be fully compensated by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB owner. The repair and spare including watch and ward of JCB also borne by the contractor/ owner. The daily log book will be maintained at site which should be duly verified by the Engineer in-charge.	136.00	Per hours	932.20	1,26,779.00	Rupees One Lakh Twenty Six Thousand Seven Hundred Seventy Nine Only
Total					1,26,779.00	Rupees One Lakh Twenty Six Thousand Seven Hundred Seventy Nine Only

Quoted Rate in Figures :

Quoted Rate in words:

BOQ checked and approved for Rs. 1,26,779.00
Executive Engineer,
Mandi Division No.II.,
H.P.W.D. Mandi.

258

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 104561.00
 Earnest Money Rs:- 2100.00
 Time :- One Month

Tender Inviting Authority :- Executive Engineer, Mandi Division No.-II, H.P.P.W.D. Mandi.
 Name of work :- R.R.D. on Jablahi barnota karkoh road KM. 0/00 to 5/500. (SH:- P/L kharanja soling and PCC between KM. 0/310 to 0/345) under PDNA 2025.

Contract No.:

Bidder Name:

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Item Description	Quantity	Units	Estimated Rate excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in words.
1	2	3	4	5	6	7
1	Stone soling properly hand -packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and camber including spreading watering and rolling of binding materials moorum or earth etc . complete as per HP. PWD specification. 100 mm (one hundred millimetre) spread thickness (finished work including materials and labour) including carriage of materials with in all leads , lifts and other incidentals as per direction and entire satisfaction of Engineer - in- charge .	11.03	Per cubic metre	1909.80	21065.00	Rupees Twenty One Thousand Sixty Five Only
2	Providing and laying 1:4:8 (One cement : four sand : eight graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations and curing complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads , lifts and other incidentals as per direction of Engineer-in-charge.	9.78	Per cubic metre	4920.30	48121.00	Rupees Forty Eight Thousand One Hundred Twenty One Only
3	Providing plain cement concrete in open foundation including form work and curing complete as per drawings and technical specification clause 802, 803, 1202 and 1203 PCC 1:2:4 (one cement : two sand : four graded stone aggregate 20mm (twenty millimetre) nominal size including carriage of materials with in all leads , lifts and other incidentals.	5.51	Per cubic metre	6420.18	35375.00	Rupees Thirty Five Thousand Three Hundred Seventy Five Only
Total in Figure					104561.00	Rupees One Lakh Four Thousand Five Hundred Sixty One Only
Quoted Rate in Words		Rupees One Lakh Four Thousand Five Hundred Sixty One Only				

BOQ checked and approved

for Rs. 1,04,561/- only.

Executive Engineer
 Mandi Division No.-II
 H.P.P.W.D. Mandi

210

BOD Approved Rs. 338389.00 →

~~Executive Engineer,
Mandi Division No.II,
M.P.P.W.D. Mandi.~~

Estimated Cost Rs:- 126779.00
Earnest Money Rs: 2536.00
Time :- One Month

Percentage of BoQ

Tender Inviting Authority : Executive Engineer, Mandi Division No.II HPPWD Mandi
Name of work :- NDF/2026/57.R/O (Repair of) Restoration of Rain damages on Chambli to Kuthar road Km 0/00 to 5/500
(SH:- Hiring of JCB for removal of slips, dressing of berms, excavation of katcha drain etc 1/120 to 1/414) Deposit work

Contract No. :

Name of the Bidder/ Bidding Firm/ Company :

PRICE SCHEDULE

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
SL. No.	Item Description	Quantity	Unit	Estimate Rate with all taxes excluding GST in Rs. P	TOTAL AMOUNT With all Taxes excluding GST in Rs. P	TOTAL AMOUNT with all Taxes excluding GST in Words
1	2	3	4	5	6	7
1	Hiring of JCB for removal of slips, dressing of berms, excavation of Kacha drain and loading of debris etc. as when required and disposing of excavated earth up to any lead from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the JCB owner which shall have to be fully compensated by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB owner. The repair and spare including watch and ward of JCB also borne by the contractor/ owner. The daily log book will be maintained at site which should be duly verified by the Engineer in-charge.	136.00	Per hours	932.20	1,26,779.00	Rupees One Lakh Twenty Six Thousand Seven Hundred Seventy Nine Only
Total					1,26,779.00	Rupees One Lakh Twenty Six Thousand Seven Hundred Seventy Nine Only

Quoted Rate in Figures :

Estimated Cost Rs:- 75508.00
Earnest Money Rs: 1510.00
Time :- One Month

Tender Inviting Authority : Executive Engineer, Mandi Division No.II HPPWD Mandi
Percentage of BoQ

Name of work :- NDF/2026/51,R/O (Repair of) Restoration of Rain damages on Chansun Galoo to Sadyana road Km 0/00 to 5/00
(SH:- Hiring of JCB for removal of slips, dressing of berms, excavation of katcha drain etc 1/120 to 1/1/269) Deposit work

Contract No. :

Name of the Bidder/ Bidding Firm/ Company :

PRICE SCHEDULE

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Unit	Estimate Rate with all taxes excluding GST in Rs. P	TOTAL AMOUNT With all Taxes excluding GST in Rs. P	TOTAL AMOUNT with all Taxes excluding GST In Words	TEXT #	TEXT #
1	2	3	4	5	6	7		
1	Hiring of JCB for removal of slips, dressing of berms, excavation of Kacha drain and loading of debris etc. as when required and disposing of excavated earth up to any lead from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the JCB owner which shall have to be fully compensated by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB owner. The repair and spare including watch and ward of JCB also borne by the contractor/ owner. The daily log book will be maintained at site which should be duly verified by the Engineer in-charge.	81.00	Per hours	932.20	75,508.00	Rupees Seventy Five Thousand Five Hundred Eight Only		
Total					75,508.00	Rupees Seventy Five Thousand Five Hundred Eight Only		
Quoted Rate in Figures :								
Quoted Rate in words:								

Rs. 75508.00

208

Estimated Cost Rs:- 75508.00
Earnest Money Rs: 1510.00
Time :- One Month

Tender Inviting Authority : Executive Engineer, Mandi Division No.II HPPWD Mandi
Name of work :- NDF/2026/50,R/O (Repair of) Restoration of Rain damages on Lag Kathwari road Km 0/00 to 2/00
(SH:- Hiring of JCB for removal of slips, dressing of berms, excavation of katcha drain etc 1/120 to 1/268) Deposit work

Contract No. :

Name of the Bidder/ Bidding Firm/ Company :

PRICE SCHEDULE

[This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only]

NUMBER #	TEXT #	Item Description	NUMBER #	TEXT #	Unit	NUMBER #	Estimate Rate with all taxes excluding GST in Rs. P	NUMBER #	TOTAL AMOUNT With all Taxes excluding GST in Rs. P	NUMBER #	TOTAL AMOUNT with all Taxes excluding GST In Words
1	2	Hiring of JCB for removal of slips, dressing of berms, excavation of Kacha drain and loading of debries etc. as when required and disposing of excavated earth up to any lead from various sites of work with in all leads and lifts to the entire satisfaction of the Engineer-in-charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the JCB owner which shall have to be fully compensated by him in all cases. The fuel and JCB operator and stays for JCB operator will be provided by the JCB owner. The repair and spare including watch and ward of JCB also borne by the contractor/ owner. The daily log book will be maintained at site which should be duly verified by the Engineer in-charge.	3	4	Per hours	5	932.20	6	75,508.00	7	Rupees Seventy Five Thousand Five Hundred Eight Only
									75,508.00		Rupees Seventy Five Thousand Five Hundred Eight Only
Total											
Quoted Rate in Figures :											
Quoted Rate in words:											

BoQ approved Rs. 75508.00

Executive Engineer,
Mandi Division No.II,

Draft Schedule of Quantity

Estimated Cost:- Rs. 94099.00
Earnest Money:- Rs. 1900.00
Time:- One Month

Name of work:- Balance work of Co-Operative bank branch office building in Gandhi Bhawan Building Distt Mandi (H.P.)
Sub Head:- Providing and fixing PVC panel ceiling work.

Sr. No.	Description of item	Qty.	Rate		Unit	Amount
			In Figure	In Words		
1	2 Providing and fixing 8mm (eight millimetre) thick PVC panel for false ceiling at all height including providing and fixing of frame work made of special sections, power pressed from M.S. sheets and galvanized with zinc coating of 120 gms/sqm (one hundred twenty grams per squaremetre) (both side inclusive) as per IS 277 and consisting of angle cleats of size 25 mm wide x 16 mm (twenty five millimetre) into one point six millimetre) (thick with flanges of 27 mm (twenty seven millimetre) and 37mm (thirty seven millimetre), at 1200 mm (one thousand two hundred millimetre) centre to centre, one flange fixed to the ceiling with dash fastener 12.5 mm dia x 50mm (twelve point five millimetre diameter into fifty millimetre) long with 6mm dia (six millimetre diameter) bolts, other flange of cleat fixed to the angle hangers of 25x10x0.50 mm (twenty five into ten into zero point five zero millimetre) of required length with nuts and bolts of required size and other end of angle hanger fixed with intermediate G.I. channels 45x15x0.9 mm (forty five into fifteen into zero point nine millimetre) running at the spacing of 1200mm (one thousand two hundred millimetre) centre to centre, to which the ceiling section 0.5 mm (zero point five millimetre) thick bottom wedge of 80 mm (eighty millimetre) with tapered flanges of 26 mm (twenty six millimetre) each having lips of 10.5 mm (ten point five millimetre), at 450 mm (four hundred fifty millimetre) centre to centre. shall be fixed in a direction perpendicular to G.I. intermediate channel with connecting clips made out of 2.64 mm dia x 230 mm (two point six four millimetre diameter into two hundred thirty millimetre) long G.I. wire at every junction, including fixing perimeter channels 0.5 mm (zero point five millimetre) thick 27 mm (twenty seven millimetre) high having flanges of 20 mm (twenty millimetre) and 30 mm (thirty millimetre) long, the perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450 mm (four hundred fifty millimetre) centre, with 25mm (twenty five millimetre) long dry wall screws @ 230 mm (at the rate of two hundred thirty millimetre) interval, including fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5 x 25 mm (three point five into twenty five millimetre) at 230 mm c/c (two hundred thirty millimetre centre to centre), including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound jointing tapes. finishing with jointing compound in 3(three) layers covering upto 150 mm (one hundred fifty millimetre) on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitably fixed. all complete as per drawings, specification but excluding the cost of painting complete in all respect including carriage of materials within all leads and lifts as per direction and satisfaction of Engineer-in-Charge	33.47 Sqm	2811.45	Rupees Two Thousand Eight Hundred and Paise Forty Five Only	Per cubic metre	94099.00
Total:-						94099.00

*Draft schedule of quantity checked and approved for
Rs. 94099/- (Rupees ninety four thousand ninety nine) only*

*Executive Engineer,
Mandi Division No.-II
HP PWD, Mandi*

115

Draft Schedule of Quantity

Estimated Cost: Rs. 98497.00
Earnest Money: Rs. 2000.00
Time: One Month

Name of work: - Annual repair and maintenance of residential building at jail road under Mandi Division No.-II Distt. Mandi (H.P.).
Sub Head: - Providing and laying painting, cupboard & wood works etcetera in D-Block Qtr. No. 19.

Sr. No.	Description of item	Qty.	Rate excluding GST		Unit	Amount
			In Figure	In Words		
1	2	3	4	5	6	7
1	Providing and fixing 18mm (eighteen millimetre) thick. Prelaminated with decorative amination on both side exterior Grade-I MDF board make action tesa in Shutter, shelves/box for cup board with butt joints and fixing with nails and screws etcetera complete with all accessories including carriage of material and other incidental complete in all respect as per direction and satisfaction of Engineer-in-Charge.	18.23	1248.80	Rupees Thousand Hundred Forty Eight rupees and Paise Sixty Only	One Per Eight boards	22653.50
2	Providing M.S. Plano hinges having overall width 35mm (thirty five millimetre) ISI marked IS : 3818 finished with nickel plating and fixing with necessary screws etcetera complete in all respect including carriage of materials within all leads and lifts as per direction and satisfaction of Engineer-in-Charge.	10.58	232.80	Rupees Two Hundred Per Thirty Two and Paise Eighty Only	Per	2458.00
3	Providing and fixing 125mm (one hundred twenty five millimetre) fancy handle of superior quality with necessary screws etcetera complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction and satisfaction of Engineer-in-Charge.	7.00	188.40	Rupees One Hundred Eighty Six and Paise Forty Only	Each	1318.00
4	Providing and fixing double strip (horizontal type) magnetic catcher of approved quality in cupboard / ward robe shutters, including fixing with necessary screws etcetera complete in all respect including carriage of materials within all leads and lifts as per direction and satisfaction of Engineer-in-Charge.	10.00	53.00	Rupees Fifty Three Each Only	Each	530.00
5	Providing and fixing steel foot/Pave including fixing with necessary screws etc. complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction and satisfaction of Engineer-in-Charge.	10.00	186.40	Rupees One Hundred Eighty Six and Paise Forty Only	Each	1864.00
6	Providing and fixing 100x10mm (one hundred into ten millimetre) aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10(ten) as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etcetera complete in all respect including carriage of materials within all leads and lifts as per direction and satisfaction of Engineer-in-Charge.	15.00	50.45	Rupees Fifty and Paise Forty Five Only	Each	757.00
7	Providing and fixing 40mm (forty millimetre) special quality bright finished brass cupboard or ward robe locks with four levers of approved quality including necessary screws etcetera complete complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction and satisfaction of Engineer-in-Charge.	1.00	152.55	Rupees One Hundred Fifty Two and Paise Fifty Five Only	Each	153.00

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 180000.00
Earnest Money Rs: 3600.00
Time :- Two Months

Tender Inviting Authority:- Executive Engineer, Mandi Division No II, HP PWD, Mandi.
Name of work:- Restoration of rain damages on various roads under Sub-Division No. IV HP PWD, Mandi.. **(Sub Head:-** Hiring of Tipper for carriage of mucks/debris/ stone, boulders etcetera.) **(Job No.IV)**

SCHEDULE OF WORKS						
Sr. No.	Item Description	Quantity	Units	Estimated Rate Rs. P.	TOTAL AMOUNT with all Taxes including GST in Rs. P.	TOTAL AMOUNT with all Taxes including GST in words.
1	2	3	4	5	6	7
1	Hiring of Tipper 5.5 cum / 10 tonne capacity (five point five cubic metre/ten tonne capacity) capacity having lift system for carriage of earth/ debris, boulder and other construction materials from various location etc. complete with in all leads and lifts and to the entire satisfaction of the Engineer-in-charge. The tipper should work minimum 8 (eight) hours from 9.00 A.M. to 5.00 P.M. daily. Any loss to public/private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the owner which shall have to be fully compensated by him in all cases. The fuel of the tipper, driver and repair work shall have to be borne by the contractor/ owner. The daily log book shall be maintained at site which should be duly verified by the Engineer-in charge.	60.00	Per day	3000.00	180000.00	Rupees Eighty Thousand Only
Total in Figure					180000.00	Rupees One Lakh Thousand Only
Quoted Rate in Words		Rupees One Lakh Eighty Thousand Only				

Bill of quantity checked and approved for Rs. 1,80,000/- (Rupees one lac eighty thousand) only.


Executive Engineer,
Mandi Division No.II,
HP.PWD, Mandi.