



Office of Executive Engineer, Banjar Division ,
Himachal Pradesh Public Works Department Banjar 175123
Phone No.01903-221031 Fax: 01903-21031
No.PW/BD/CB/TA/Ten. Not/2026-10551-90

Dated:- 06-10-26

To

✓ The Chief Engineer (MZ)
HPPWD. Mandi -175001.

Subject :-

Publishing of Notice Inviting Tenders / Advertisement.

Enclosed please find herewith Copy of Notice Inviting Tender for the up-loading on department website as per Notification No. PBW(B) A (3) 8/2025-3000858 Dated 13.11.2025 and as direction issued Vide Engineer-in-Chief, HPPWD., Shimla letter No. PWD/ICTWing/Website Dated-22.05.2026 as the works mentioned in the Notice are emergent nature and in the public interest.

Encl:- Notice

Executive Engineer,
Banjar Division ,
H.P.W.D. Banjar.

Copy forwarded to the followings for information and necessary action.

The Engineer-in-Chief, HPPWD Shimla .
The Superintending Engineer 6th circle HPPWD Kullu.
All the Contractors enlisted in HPPWD.
The Superintendent, DAO ,HDM of this Office.
Notice Board

Executive Engineer,
Banjar Division,
H.P.P.W.D. Banjar

Himachal Pradesh
Public works Department

Notice Inviting Tender

Sealed Percentage rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, Banjar Division, HP, PWD, Banjar on behalf of Governor of H.P. from the eligible contractors enlisted in HP, PWD for the following works, so as to reach in this office on or before 17.10.2026 up to 11.00AM and the tender will be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender forms can be had from this office against cash payment (non-refundable) up to 16.10.2026 at 4.00 PM. The application for issue of tender forms shall be received up-to 3.00 PM on 16.10.2026.

The Earnest money in the shape of FDR/National Saving Certificate/Time deposit/Saving Account in any of the post office/Saving Bank Account of Nationalized Bank in HP duly pledged in favour of Executive Engineer, Banjar Division, HPPWD Banjar must be accompany with each tender. Conditional tender and the tender received without earnest money will summarily be rejected. The offer of tender shall remain open for 75 days from the date of opening. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

All the contractors will have to bring with them attested copy of enlistment/renewal/ exemption in earnest money. Contractor will be issued the tender forms only when they fulfill the terms and condition of form No. 6 & 8. Contractors should be registered under HP, Sales Tax Act. 1968/EPF/GST.

Sr.No.	Description of item	Estimated cost	EMD	Time	Cost of form
1	RRD on Sidhwan to Godigad road Km.0/0 to 8/0. (SH:- C/O Breast wall at RD- 2/680 to 2/697) (under PDNA)	411184	8300	Three Months	350/-
2	RRD on Sidhwan to Godigad road Km.0/0 to 8/00. (SH:- C/O Breast wall at RD- 2/640 to 2/662) (under PDNA)	410386	8300	Three Months	350/-
3	RRD on Bhuin to Diyar road Km.0/0 to 12/500. (SH:- C/O PCC Retaining wall at RD- 9/930 to 9/948.50 in between RD-9/930 to 9/975) (under PDNA-2025)	497713	10000	Three Months	350/-
4	RRD on Bhuin to Diyar road Km.0/0 to 12/500. (SH:- C/O PCC Retaining wall at RD- 6/200 to 6/210 in between RD- 6/200 to 6/223) (under PDNA-2025))	276506	5600	Three Months	350/-
5	RRD on Sainj Neuli Kartah road Km.0/0 to 10/020. (SH:- C/O Wire crated Retaining wall at RD-0/125 to 0/175 in between RD-0/100 to 0/300)(under PDNA 2025)	498535	10000	Three Months	350/-
6	RRD on Sainj Neuli Kartah road Km.0/0 to 10/020. (SH:- C/O Wire crated Retaining wall at RD-0/180 to 0/200 in between RD-0/100 to 0/300)(under PDNA 2025)	498920	10000	Three Months	350/-
7	RRD on Jhiri to Airport Gate Bhunter road Km.253/790 to 258/440. (SH:- Providing and laying WBM -III for repair of Pot Holes Km.255/200 to 255/300) (under PDNA)	321445	6500	Two Months	350/-
8	RRD on Approach road Govt. Degree College at Banjar Tehsil Banjar Distt. Kullu (HP). (SH:- C/O PCC Retaining wall at RD- 0/018 to 0/028 damaged during the disaster 2025) (Dep.)	470080	9500	Three Months	350/-
9	RRD on Banjar to Bathad road Km.0/0 to 20/0. (SH:- C/O PCC Retaining wall at RD- 1/715 to 1/730 in between RD- 1/715 to 2/620) (under PDNA 2025)	484373	9800	Three Months	350/-
10	RRD on Banjar to Bathad road Km.0/0 to 20/0. (SH:- C/O PCC Retaining wall at RD- 1/732 to 1/744 in between RD- 1/715 to 2/620) (under PDNA 2025)	497301	10000	Three Months	350/-
11	RRD on Helipad with approach road to Dhameuli (Banjar) Distt. Kullu Km.0/0 to 2/115. (SH:- C/O PCC Retaining wall at RD	494632	9900	Three Months	350/-

	0/157 to 0/166.50) (under PDNA)				
12	RRD on Helipad with approach road to Dhameuli (Banjar) Distt. Kullu Km.0/0 to 2/115. (SH:- C/O U-shape drain at Km.0/020 to 0/100) (under PDNA)	281632	5700	Three Months	350/-
13	RRD on Trehan to Piyashni road Km.0/0 to 3/0. (SH:- C/O Retaining wall at RD- 0/510 to 0/520) (under NDRF/SDRF)	430243	8700	Three Months	350/-
14	RRD on Jeepable road Bheyot road to Rohlo road Km.0/0 to 1/800. (SH:- C/O RR M Retaining wall at RD-0/839 0/854) (under PDNA 2023)	343407	6800	Two Months	350/-
15	RRD on Sainj Neuli Kartah road Km.0/0 to 10/020. (SH:- Removal of slips/Land slide at various reaches)(under NDRF)	497747	10000	Three Months	350/-

TERMS AND CONDITIONS :-

The contractors/Bidders must quote their PAN/Income Tax Number/Sale Tax number(TIN number)/EPF No./GST No. on the tender along with the copy of the same be attached with the application. The contractor/Firms should attach copy of registration/Renewal with the application, Contractor/Bidder are advised to visit and examine the site where the work are to be carrying out and its surrounding. The contractors/Bidders should quote his rates Both in figure and words. Where there is any discrepancy between the rates in figure and in words. The rates in words will be governed. Contractors/Bidders must inspect the site to ascertain/familiar the site condition accessibility etc. Before quoting the bid/tender. Conditional and telegraphic tenders shall not be accepted and rejected straightway. Tenders received after due date and time will be rejected. Executive Engineer reserves the right to reject or all tenders without assigning any reason. Certified that tender of above works are being called for emergent nature in exigency and in the public interest.

Executive Engineer
Banjar Division,
H.P.W.D. Banjar.

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Sidhwan to Godigad road Km. 0/00 to 8/00.
(SH :- Construction of Breast wall at RD.2/680 to 2/697).(Under PDNA).

Estimated Cost:- Rs.411184/- only.
Earnest Money :-Rs.8300/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures	Words		
1	Excavation soil in hilly area by manual means including cutting and trimming of side slopes and disposal of excavated earth with lift up to 1.5 m and a lead up to 20 m any as per drawing and technical specification clause 1603.1 all kind of soil with in all leads and lifts to the entire satisfaction as per direction of Engineer in-charge including hauling/carriage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	75.39	Cubic Metre.	333.65	Rupees three hundred thirty three paise sixty five only.	Per cubic metre.	25154.00
2	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock/hard rock (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects including hauling/carriage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	23.20	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	Per cubic metre.	12384.00
3	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702,704,1202 and 1204 including carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	40.00	Cubic Metre.	5022.25	Rupees five thousand two hundred twenty two paise twenty five only.	Per cubic metre.	200890.00
4	Construction of dry rubble stone masonry for Retaining walls, breast walls, revetment walls and parapets etc. for sub-structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for Rural road clause 704.6 and 1302.5 including hauling/ carriage of all labour equipment and materials to various location through all modes of transportation. with in all leads and lift of materials and as per direction of Engineer-in-charge.	41.04	Cubic Metre.	4209.45	Rupees four thousand two hundred nine paise fourty five only.	Per cubic metre.	172756.00
						Total:-	411184.00

Draft Schedule of Quantity checked and approved for Rs.411184/- only (7 four lac eleven thousand one hundred eighty four only).

Executive Engineer
Banjar Division
HPTWD Bangla

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Sidhwan to Godigad road Km. 0/00 to 8/00.
(SH :- Construction of Breast wall at RD.2/640 to 2/662) (Under PDNA).

Estimated Cost:- Rs.410386/- only.
Earnest Money :- Rs.8300/- only.
Time :- Three Month.

Sr. No	Description of Items	Quantity		Rate with all taxes excluding GST Figures	Words		Unit	Amount
		3	4		5	6		
1	Excavation soil in hilly area by manual means including cutting and trimming of side slopes and disposal of excavated earth with lift up to 1.5 m and a load up to 20 m any as per drawing and technical specification clause 1603.1 all kind of soil with in all leads and lifts to the entire satisfaction as per direction of Engineer in-Charge including hauling/carriage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	73.00	Cubic Metre.	333.65	Rupees three hundred thirty three paise sixty five only.	Per cubic metre.	8	24356.00
2	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock/hard rock (Requiring blasting), hard rock (blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost. including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidents to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, egg- and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects including hauling/carriage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	23.20	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	Per cubic metre.		12384.00
3	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702/704, 1202 and 1204 including carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	40.00	Cubic Metre.	5022.25	Rupees five thousand twenty two paise twenty five only.	Per cubic metre.		200890.00
4	Construction of dry rubble stone masonry for Retaining walls, breast walls, revetment walls and parapets etc for sub-structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for Rural road clause 704.6 and 1302.5 including hauling/ carriage of all labour equipment and materials to various location through all modes of transportation. with in all leads and lift of materials and as per direction of Engineer-in-charge.	41.04	Cubic Metre.	4209.45	Rupees four thousand two hundred nine paise fourty five only.	Per cubic metre.		172756.00
						Total:-		410386.00

Draft schedule of Quantity checked and approved for 4,10,386 only for six ten thousand three hundred eighty six only.

Executive Engineer
Banjar Division
HPPWD Banjar.

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Bhulin to Diyar road Km. 0/00 to 12/500.

(SH :-Construction of PCC Retaining wall at RD.6/200 to 6/210 in between RD.6/200 to 6/223),(Under PDNA 2025).

Estimated Cost:- Rs.276506/- only.

Earnest Money :-Rs.5600/- only.

Time :- Three Month.

Sr. No	Description of Items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures	Words		
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock-hard rock (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects including hauling/carryage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	39.60	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	Per cubic metre.	21139.00
2	Providing and laying cement concrete for plain concrete in open foundation 1:4:8 (One cement : four sand : eight graded crushed stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and sub structure of retaining walls, Breast walls and parapets etc. complete as per drawings and HP.PWD. specification/MORD technical specification section and clause 800.1202 and 1203 and curing complete including the cost of form work and hauling / carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	44.78	Cubic Metre.	5258.89	Rupees five thousand six hundred eighty one paise ninety only.	Per cubic metre.	235493.00
3	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification of Ministry of Rural Development for rural road clause 1204.38 including hauling/carryage of all labour equipment and materials to various location through with in all leads and lift of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	9.00	Cubic Metre.	1418.49	Rupees one thousand four hundred eighteen paise forty nine only.	Per cubic metre.	12766.00
4	Providing weep holes in brick masonry /stone masonry/ plain reinforced concrete abutment, wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipe extending through the full width of the structure with slope of 1 in 20 (1:20) towards draining face complete as per drawing and technical specifications clause 614.709, 1206.6 including hauling/ carriage of all labour equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	17.00	Each	418.09	Rupees four hundred eighteen paise nineteen only.	Each	7108.00
						Total:-	276506.00

Draft schedule of Quantity checked and approved for 276506/- only (Five hundred and seventy six thousand five hundred and six only)


 Executive Engineer
 Banjar Division
 HPPWD Banjar.

5

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Sainj Neuli kartah road Km. 0/00 to 10/020.
(SH :- Construction of wire crated Retaining wall 0/125 to 0/175 in between RD. 0/00 to 0/300),(Under PDNA 2025).

Estimated Cost:- Rs.498535/- only.
Earnest Money :-Rs.10000/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures	Words		
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock,hard rock (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost , including dressing of slopes and beds setting out conforming to required lines, grades , side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials,such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects,including hauling/carrriage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	50.00	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	Per cubic metre.	26691.00
2	Providing and laying of boulder upon laid in wire crates with 4mm (four millimetre) dia G-I wire conforming to IS 280 and IS 4826 in 100mmx100mm (one hundred millimetre x one hundred millimetre) mesh woven diagonally including ten percent extra for laps and joints laid with stone boulder weighting not less than 25 kg (twenty five kilogramme) each as per drawing and technical specification clause 1301 including haulage/carrriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	150.24	Cubic Metre.	2843.20	Rupees two thousand eight hundred forty three paise twenty only.	Per cubic metre.	427162.00
3	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification of Ministry of Rural Development for rural road clause 1204.3.8 including hauling/carrriage of all labour equipment and materials to various location through,with in all leads and lift of materials and as per direction of Engineer-in-charge.The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	31.50	Cubic Metre.	1418.49	Rupees one thousand four hundred eighteen paise forty nine only.	Per cubic metre.	44682.00
						Total:-	498535.00

Draft schedule of Quantity checked and approved for Rs.4,98,535 only (Four lac ninety eight thousand five hundred thirty five only).

[Signature]
Executive Engineer
Banjar Division
HPPWD Banjar

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Saini Neuli kartah road Km. 0/00 to 10/020.
(SH :- Construction of wire crated Retaining wall 0/180 to 0/200 in between RD. 0/000 to 0/300), (Under PDNA 2025).

Estimated Cost:- Rs.498920/- only.
Earnest Money :-Rs.10000/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST	Unit		Amount
		Figures	Words		Figures	Words	
1	Excavation soil in hilly area by manual means including cutting and trimming of side slopes and disposal of excavated earth with lift up to 1.5 m and a lead up to 20 m as per drawing and technical specification clause 1603.1 all kind of soil with in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge including hauling/carriage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	56.30	Cubic Metre.	333.65	Rupees three hundred thirty three paise sixty five only.	Per cubic metre.	18784.00
2	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock/hard rock (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects including hauling/carriage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	37.50	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	Per cubic metre.	20018.00
3	Providing and laying of boulder upon laid in wire crates with 4mm (four millimetre) dia G-I wire conforming to IS 280 and IS 4826 in 100mmx100mm (one hundred millimetre x one hundred millimetre) mesh woven diagonally including ten percent extra for laps and joints laid with stone boulder weighting not less than 25 kg (twenty five kilogramme) each as per drawing and technical specification clause 1301 including haulage/carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	153.15	Cubic Metre.	2843.20	Rupees two thousand eight hundred forty three paise twenty only.	Per cubic metre.	435436.00
4	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification of Ministry of Rural Development for rural road clause 1204.3.8 including hauling/carriage of all labour equipment and materials to various location through with in all leads and lift of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	17.40	Cubic Metre.	1418.49	Rupees one thousand four hundred eighteen paise forty nine only.	Per cubic metre.	24682.00
						Total:-	498920.00

Draft Schedule of Quantity checked and approved for ₹ 4,98,920/- only (Four lac ninety eight thousand nine hundred and twenty only).

Executive Engineer
Banjar Division
HPPWD Bangur

DRAFT SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on Ihiri to Airport Gate Bhunter Km. 253/790 to 258/440.
(SH :- Providing and laying WBM-III for repair of Pot Holes km. 255/200 to 255/300)

Estimated Cost:- Rs.321445/- only.
Earnest Money :-Rs.6500/- only.
Time :- Two Month.

Sr.N o.	Description of Items	Quantity	Rate with all taxes excluding GST		Unit	Amount
			Figures	Words		
1	Providing,laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 KN in stages proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading III as per Technical specification Clause 405. (By Mechanical means) including hauling/carriage of materials, labour and equipments to various location through all modes of transportation within all leads lifts and as per direction of Engineer-in-charge.The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	93.75	3428.75	Rupees two thousand nine hundred fifty nine paise twenty only.	Per Square metre	321445.00
					Total:-	321445.00

Draft schedule of Quantity checked and approved for Rs. 3,21,445/- only (Three lac twenty one thousand four hundred forty five only).

Executive Engineer
Banjar Division
HPPWD Banjar

8

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Approach road Govt. Degree College at Banjar Tehsil

Banjar Distt. Kullu (HP).

Estimated Cost:- Rs. 470080/- only.

(SH :-Construction of PCC Retaining wall at RD. 0/018 to 0/028 damaged during the disaster 2025) (Deposit).

Earnest Money :-Rs.9500/- only.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST Figures	Time :- Three Month.		Unit	Amount
		3	4		Words	6		
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock,hard rock (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials,such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects,including hauling/carriage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	45.85	Cubic Metre.	533.81	Rupess five hundred thirty three paise eighty one only.	Per cubic metre.	24475.00	
2	Providing and laying cement concrete for plain/reinforcement concrete 1:6:12 (One cement : Six sand :twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawings and H.P.W.D.specification. &MORD technical specification and curing complete including the cost of form work and hauling/carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	4.30	Cubic Metre.	4746.53	Rupess four thousand seven hundred forty six paise fifty three only.	Per cubic metre.	20410.00	
3	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803,1202 and 1203 1:3:6 (one cement : three sand : six graded stone aggregate graded stone aggregate 40mm (forty millimetre nominal size) including the cost of form work and curing complete and hauling/carriage of all labour, equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	65.60	Cubic Metre.	6076.58	Rupess six thousand seventy six paise fifty eight only.	Per cubic metre.	398624.00	
4	Providing weep holes in brick masonry /stone masonry/ plain reinforced concrete abutment,wing wall,return wall with 100 mm (one hundred millimetre) dia PVC pipe extending through the full width of the structure with slope of1%(v);20q (H) towards draining face complete as per drawing and technical specifications clause 614.709,1206.6 including hauling/ carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	32.00	Each	418.09	Rupess four hundred eighteen paise nineteen only.	Each	13379.00	
5	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification of Ministry of Rural Development for rural road clause 1204.3.8 including hauling/ carriage of all labour equipment and materials to various location through,with in all leads and lift of materials and as per direction of Engineer-in-charge.The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	9.30	Cubic Metre.	1418.49	Rupess one thousand four hundred eighteen paise forty nine only.	Per cubic metre.	13192.00	
						Total:-	470080.00	

Draft schedule of quantity checked and approved for Rs. 4,70,080/- only (Four lac seventy thousand eight hundred only).

Executive Engineer
Banjar Division
HPPWD Banjar

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Banjar to Bathad road Km. 0/00 to 20/00.
(SH :- Construction of PCC Retaining wall at RD. 1/715 to 1/730 in between RD. 1/715 to 2/620) (Under PDNA 2025).

Estimated Cost:- Rs.484373/- only.
Earnest Money :-Rs.9800/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures	Words		
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock, hard rock (Requiring blasting), hard rock (blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects including hauling/carryage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	48.52	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	Per cubic metre.	25900.00
2	Providing and laying cement concrete for plain/reinforcement concrete 1:6:12 (One cement : Six sand : twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawings and H.P.P.W.D. specification & MORO technical specification and curing complete including the cost of form work and hauling/carryage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	4.95	Cubic Metre.	4746.53	Rupees four thousand seven hundred forty six paise fifty three only.	Per cubic metre.	23495.00
3	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803.1202 and 1203 1:3:6 (one cement : three sand : six graded stone aggregate graded stone aggregate 40mm (forty millimetre nominal size) including the cost of form work and curing complete and hauling/carryage of all labour, equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	67.25	Cubic Metre.	6076.58	Rupees six thousand seventy six paise fifty eight only.	Per cubic metre.	408650.00
4	Providing weep holes in brick masonry /stone masonry/ plain reinforced concrete abutment, wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extending through the full width of the structure with slope of 1:20 (H) towards draining face complete as per drawing and technical specifications clause 614.709.1206.6 including hauling/ carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	36.00	Each	418.09	Rupees four hundred eighteen paise nineteen only.	Each	15051.00
5	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification of Ministry of Rural Development for rural road clause 1204.3.8 including hauling/ carriage of all labour equipment and materials to various location through with in all leads and lift of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	7.95	Cubic Metre.	1418.49	Rupees one thousand four hundred eighteen paise forty nine only.	Per cubic metre.	11277.00
						Total:-	484373.00

*Draft schedule of quantity checked and approved for
2 484373/- only (I have checked quantity and amount)
These hundred seventy three thousand four hundred and eighty seven rupees only*

Executive Engineer
Banjar Division
HPPWD Banjar.

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Banjar to Bathad road Km. 0/00 to 20/00.
(SH :-Construction of PCC Retaining wall at RD.1/732 to 1/744 in between RD. 1/715 to 2/620).(Under PDNA 2025).

Estimated Cost:- Rs.497301/- only.
Earnest Money :-Rs.10000/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount		
		Figures	Words	Figures	Words				
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock/hard rock (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects including hauling/carryage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	3	33.9	4	Cubic Metre.	7	Per cubic metre.	8	18096.00
2	Providing and laying cement concrete for plain/reinforcement concrete 1:6:12 (One cement : Six sand : twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawings and H.P.P.W.D.specification & MORD technical specification and curing complete including the cost of form work and hauling/carryage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	3.96		Cubic Metre.	4746.53	Rupees four thousand seven hundred forty six paise fifty three only.	Per cubic metre.	18796.00	
3	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803.1202 and 1203 1:3:6 (one cement : three sand : six graded stone aggregate graded stone aggregate 40mm (forty millimetre nominal size) including the cost of form work and curing complete and hauling/carryage of all labour, equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	71.4		Cubic Metre.	6076.58	Rupees six thousand seventy six paise fifty eight only.	Per cubic metre.	433868.00	
4	Providing weep holes in brick masonry /stone masonry/ plain reinforced concrete abutment/wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipe extending through the full width of the structure with slope of 1:20 (H) towards draining face complete as per drawing and technical specifications clause 614.709.1206.6 including hauling/ carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	36		Each	418.09	Rupees four hundred eighteen paise nineteen only.	Each	15051.00	
5	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification of Ministry of Rural Development for rural road clause 1204.3.8 including hauling/ carriage of all labour equipment and materials to various location through with in all leads and lift of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	8.1		Cubic Metre.	1418.49	Rupees one thousand four hundred eighteen paise forty nine only.	Per cubic metre.	11490.00	
							Total:-	497301.00	

Draft schedule of Quantity checked and approved for Rs. 497,301/- only (Five Lacs ninety seven thousand three hundred one only)

Executive Engineer
Banjar Division
HPPWD Banjar.

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on HeliPad with approach road to Dhameuli (Banjar) Distt. Kullu Km 0/00 to 2/115.
(SH :-Construction of PCC Retaining wall at RD.0/157 to 0/166.50)(under PDNA).

Estimated Cost:- Rs.494632/- only.
Earnest Money :-Rs.9900/- only.
Time :- Three Month.

Sr. No	Description of Items	Quantity		Rate with all taxes excluding GST	Unit	Amount
		Figures	Words	Figures	Words	Amount
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rockhard rock (requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, levelling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidents to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and unserviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects including hauling/carryage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	39.09	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	20867.00
2	Providing and laying cement concrete for plain/reinforcement concrete 1:6:12 (One cement : Six sand : twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawings and H.P.P.W.D.specification & MORD technical specification and curing complete including the cost of form work and hauling/carryage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	3.70	Cubic Metre.	4746.53	Rupees four thousand seven hundred forty six paise fifty three only.	17562.00
3	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 1202.803, 1202 and 1203 1:3:6 (one cement : three sand : six graded stone aggregate graded stone aggregate 40mm (forty millimetre nominal size) including the cost of form work and curing complete and hauling/carryage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	71.62	Cubic Metre.	6076.58	Rupees six thousand seventy six paise fifty eight only.	435205.00
4	Providing weep holes in brick masonry /sone masonry/ plain reinforced concrete abutment/wing wall/return wall with 100 mm (one hundred millimetre) dia PVC pipe extending through the full width of the structure with slope of (1V:20H) towards draining face complete as per drawing and technical specifications clause 614,709,1206.6 including hauling/ carryage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	28.00	Each	418.09	Rupees four hundred eighteen paise nineteen only.	11707.00
5	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification of Ministry of Rural Development for rural road clause 1204.3.8 including hauling/ carryage of all labour equipment and materials to various location through with in all leads and lift of materials and as per direction of Engineer-in-charge.The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	6.55	Cubic Metre.	1418.49	Rupees one thousand four hundred eighteen paise forty nine only.	9291.00
					Total:-	494632.00

Draft Schedule of Quantity checked and approved for ₹ 4,94,632/- only (Four lac ninety four thousand six hundred thirty two only).

[Signature]
Executive Engineer
Banjar Division
HPPWD Banjar.

12

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Heli pad with approach road to Dhameuli (Banjar) Dist. Kullu Km 0/00 to 2/115.
(SH :-Construction of U-shape drain at Km. 0/020 to 0/100). (Under PDNA).

Estimated Cost:- Rs.281632/- only.
Earnest Money :-Rs.5700/- only.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
				Figures	Words		
		3	4	5	6		
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rockhard rock (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost. including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials,such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.including hauling/carrriage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	104.00	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	Per cubic metre.	55516.00
2	Providing and laying cement concrete for plain/reinforcement concrete 1:6:12 (One cement : Six sand :twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawings and H.P.W.D.specification & MORD technical specification and curing complete including the cost of form work and hauling/carrriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	10.00	Cubic Metre.	4746.53	Rupees four thousand seven hundred forty six paise fifty three only.	Per cubic metre.	47465.00
3	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803.1202 and 1203 1:3:6 (one cement : three sand : six graded stone aggregate graded stone aggregate 40mm (forty millimetre nominal size) including the cost of form work and curing complete and hauling/carrriage of all labour, equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	29.40	Cubic Metre.	6076.58	Rupees six thousand seventy six paise fifty eight only.	Per cubic metre.	178651.00
Total:-							281632.00

Draft schedule of Quantity checked and approved for ₹ 2,81,632/- only (Two lac eighty one thousand six hundred thirty two only).

Executive Engineer
Banjar Division
HPPWD Banjar.

13

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Terhan to Piyashani road Km. 0/00 to 3/00.
(SH :- Construction of Retaining wall at RD.0/510 to 0/520) (under NDRE /SDRF).

Estimated Cost:- Rs.430243/- only.
Earnest Money :- Rs.8700/- only.

Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures	Words		
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock, hard rock (Requiring blasting), hard rock (blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost. Including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects including hauling/carryage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	45.90	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	Per cubic metre.	24502.00
2	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803.1202 and 1203 1:3:6 (one cement : three sand : six graded stone aggregate graded stone aggregate 40mm (forty millimetre nominal size) including the cost of form work and curing complete and hauling/carryage of all labour, equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	3.00	Cubic Metre.	6076.58	Rupees six thousand seventy six paise fifty eight only.	Per cubic metre.	18230.00
3	Providing and laying cement concrete for plain/reinforcement concrete 1:6:12 (One cement : Six sand : twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawings and H.P.P.W.D specification & MORD technical specification and curing complete including the cost of form work and hauling/carryage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	75.48	Cubic Metre.	4746.53	Rupees four thousand seven hundred forty six paise fifty three only.	Per cubic metre.	358268.00
4	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification of Ministry of Rural Development for rural road clause 1204.3.8 including hauling/ carriage of all labour equipment and materials to various location through with in all leads and lift of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	10.30	Cubic Metre.	1418.49	Rupees one thousand four hundred eighteen paise forty nine only.	Per cubic metre.	14610.00
5	Providing weep holes in brick masonry /stone masonry/ plain reinforced concrete abutment/wing wall/return wall with 100 mm (one hundred millimetre) dia PVC pipe extending through the full width of the structure with slope of (1 v):20 (H) towards draining face complete as per drawing and technical specifications clause 614.709.1206.6 including hauling/ carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	35.00	Each	418.09	Rupees four hundred eighteen paise nineteen only.	Each	14633.00
						Total:-	430243.00

Self schedule of quantity checked and approved for ₹ 4,30,243/- only (Four Lakhs Thirty Thousand and Two Hundred forty Three only)

Executive Engineer
Barjar Division
HPPWD Barjar

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Jeepable road Bheyot moor to Roholo road km. 0/00 to 1/800.
(SH :- Construction of R.R.M. Retaining wall at RD 0/839 to 0/854). (Under PDNA 2023).

Estimated Cost:- Rs. 343407/- only.

Earnest Money :-Rs. 6800/- only.

Time :- two Month.

Sr. No	Description of items	Quantity	Rate with all taxes excluding GST		Unit	Amount
			Figures	Words		
1	2	3	4	5	6	7
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead and lift complete including dressing of sides and bottom and backfilling in trenches with excavated suitable material with in all leads and lifts complete as per entire satisfaction of Engineer-in-charge.	41.02	533.81	Rupees Five hundred thirty three and paise eighty one only.	Per cubic metre.	21897.00
2	Providing and laying concrete for plain 1:6:12 (one cement: six sand: twelve aggregate 40 mm nominal size) in open foundations complete as per drawing and technical specification clause 802.803, 1202 and 1203. within all leads and lift of materials and as per direction of Engineer-in-charge.	6.45	4746.53	Rupees four thousand seven hundred forty six and paise fifty three only.	Per cubic metre.	30615.00
3	Stone masonry work in cement mortar 1:6 (one cement: six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702, 704, 1202 and 1204 including carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	22.05	6026.69	Rupees six thousand twenty six and paise sixty nine only.	Per cubic metre.	132889.00
4	Construction of dry rubble stone masonry for Retaining walls, breast walls, revetment walls and parapets etc for sub-structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for Rural road clause 704.6 and 1302.5 including hauling/ carriage of all labour equipment and materials to various location through all modes of transportation. with in all leads and lift of materials and as per direction of Engineer-in-charge.	34.20	4209.45	Rupees Four thousand two hundred nine and paise forty five only.	Per cubic metre.	143963.00
5	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification of Ministry of Rural Development for rural road clause 1204.3.8 including hauling/ carriage of all labour equipment and materials to various location through with in all leads and lift of materials and as per direction of Engineer-in-charge.	9.90	1418.49	Rupees one thousand four hundred eighteen and paise forty nine only.	Per cubic metre.	14043.00
Total:-						343407.00

Draft Schedule of Quantity checked and approved by 343,407 (Rupees Three Lacs forty three thousand seven hundred seventy) Rs. only

Executive Engineer,
Bantar Division
HPPWD; Badliar

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Sainj Neuli Kartah road Km. 0/00 to 10/020.
(SH :- Removal of slips / Land Slide at various reaches). (Under NDRF).

Estimated Cost:- Rs.497747/- only.
Earnest Money :-Rs.10000/- only.
Time :-Three Month.

Sr.No.	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures 5	Words 6		
1	Removal of slips/land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slope and disposal of material with in all lift upto any lead as per technical specification. Any loss to the public property or any accidents etc .During the execution of work the contractor will be fully responsible. The fuel/POL charges and operational staff for the machine will be provided by the owner. The repair and other incidental charges of machinery will be borne by the contractor. The useful material shall be stacked along the road side as per direction of Engineer-in-Charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	3750.92	Cubic Metre.	132.70	Rupees one hundred thirty two paise seventy only.	Per cubic metre.	497747.00
Total:-							497747.00

Draft Schedule of Quantity checked and approved for ₹ 4,97,747 only (Four lakhs seven thousand seven hundred forty seven only)

Executive Engineer
Banjar Division
HPPWD Banjar