

HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT

No.PW/W/S- mige R-#2 2012- 2105- 2260  
To

Dated:- 26/5/2012

All the Superintending Engineers,  
in HP-PWD.

Subject: - Clearance of side-drains and culverts

Before the rainy season sets-in, it is imperative that all the road-side drains and culverts are cleared and are made effectively functional.

To achieve the above objective, the following strategy be adopted:-

Sub-Divisions where adequate labour(say more than 0.75 beldar/Km) are available, the departmental labour be deployed.

In addition to above the departmental JCBs(with small 30 cm bucket, which can be procured (if not available) can also be deployed where either the new drain has to be dug or the existing kucha drain has considerably vanished.

The Superintending Engineers concerned should get their guideline implemented in their Circles and ensure that all drains/culverts are cleared by 20<sup>th</sup> June,2012, and submit the report on following format :-

ROAD SIDE-DRAIN/BERM/CULVERT CLEARANCE REPORT AS ON \_\_\_\_\_

Division	Sub-Divn.	Total road length.	Length where drain/berms/culverts cleared.	Balance length	Remarks
1	2	3	4	5	6

Contd.P/2



The Superintending Engineers should frequently inspect their area and should submit progress as ending on 31<sup>st</sup> May, 5th June and 20<sup>th</sup> June, 2012.

Engineer-in-Chief,  
HP-PWD, Shimla-2.

Copy for information to:-

1. ✓ The Pr. Secretary (PW) to the Govt. of HP.
2. ✓ All Zonal Chief Engineers. 3/2
3. All Executive Engineers.

Copy to - AET(IT) for putting  
on web-site.

Engineer-in-Chief, 24/5  
HP-PWD, Shimla-2.  
19/5